



USPS Tracking: EI 120 650 351 US
October 28, 2021

New Mexico Environment Department
Air Quality Bureau
525 Camino de los Marquez, Suite 1
Santa Fe, New Mexico, 87505

**RE: New Source Review (NSR) Permit
Bitter Lake Compressor Station, Chaves County, New Mexico
IACX Roswell LLC**

Dear Air Quality Bureau,

IACX Roswell, LLC is seeking to authorize the Bitter Lake Compressor Station, located in Chaves County, New Mexico (Facility) under a New Mexico Environment Department (NMED) New Source Review (NSR) Permit.

With this registration, IACX Roswell LLC is seeking to authorize the following equipment and operations at the Facility:

- Two (2) 1414 hp Compressor Engines
- Two (2) 425 hp Compressor Stations
- One (1) Glycol Dehydrator
- Three (3) 100 bbl/day Condensate Tanks
- Condensate and Produced Water Loading
- Facility Fugitive Emissions
- Startup, Shutdown & Maintenance (SSM) activities
- Malfunctions

This application includes the following elements and their requested supporting documentation:

- Universal Air Quality Permit Application
- Section 1 – General Facility Information
- Section 2 – Tables
- Section 3 – Application Summary
- Section 4 – Process Flow Sheet
- Section 5 – Plot Plan Drawn to Scale
- Section 6 – All calculations
- Section 7 – Information Used To Determine Emissions
- Section 8 – Maps
- Section 9 – Proof of Public Notice
- Section 10 – Written Description of the Routine Operations of the Facility



-
- Section 11 – Source Determination
 - Section 13 – Determination of State & Federal Air Quality Regulations
 - Section 16 – Air Dispersion Modeling
 - Section 17 – Compliance Test History
 - Section 22 – Certification
 - Air Emissions Calculation Tool (AECT)
 - Universal Application 4
 - PDF of the entire application

Enclosed you will find one (1) hardcopy with original signed and notarized Registration package printed double sided 'head-to-toe' with 2-hole top punch binding, one (1) double sided hard copy, flip on long edge, and one compact disk (CD) with a single PDF of the application and all editable file components of the application.

A permit registration fee of \$500 is enclosed via check #_____.

Any clarification questions or requests for additional information can be directed to myself via email to jva@resolutecompliance.com or by phone at 972-842-4304 or Mr. Justin Wheeler via email to justinwheeler@iacx.com or by phone at 972-679-2147.

Kind Regards,

James VanAssche, P.E., C.H.M.M.

Vice President of Environmental Compliance

Encl: New Source Review (NSR) Application

Cc: Mr. Justin Wheeler – IACX Energy

Mail Application To: New Mexico Environment Department Air Quality Bureau Permits Section 525 Camino de los Marquez, Suite 1 Santa Fe, New Mexico, 87505 Phone: (505) 476-4300 Fax: (505) 476-4375 www.env.nm.gov/aq		For Department use only: AIRS No.:
---	--	--

Universal Air Quality Permit Application

Use this application for NOI, NSR, or Title V sources.

Use this application for: the initial application, modifications, technical revisions, and renewals. For technical revisions, complete Sections, 1-A, 1-B, 2-E, 3, 9 and any other sections that are relevant to the requested action; coordination with the Air Quality Bureau permit staff prior to submittal is encouraged to clarify submittal requirements and to determine if more or less than these sections of the application are needed. Use this application for streamline permits as well. **See Section 1-I for submittal instructions for other permits.**

This application is submitted as (check all that apply): ☐ Request for a No Permit Required Determination (no fee)
☐ **Updating** an application currently under NMED review. Include this page and all pages that are being updated (no fee required).
 Construction Status: ☐ Not Constructed ☒ Existing Permitted (or NOI) Facility ☐ Existing Non-permitted (or NOI) Facility
 Minor Source: ☐ a NOI 20.2.73 NMAC ☐ 20.2.72 NMAC application or revision ☐ 20.2.72.300 NMAC Streamline application
 Title V Source: ☐ Title V (new) ☐ Title V renewal ☐ TV minor mod. ☐ TV significant mod. TV Acid Rain: ☐ New ☐ Renewal
 PSD Major Source: ☐ PSD major source (new) ☐ minor modification to a PSD source ☐ a PSD major modification

Acknowledgements:

- ☒ I acknowledge that a pre-application meeting is available to me upon request. ☐ Title V Operating, Title IV Acid Rain, and NPR applications have no fees.
- ☒ \$500 NSR application Filing Fee enclosed **OR** ☐ The full permit fee associated with 10 fee points (required w/ streamline applications).
- ☒ Check No.: **1337** in the amount of **500.00**
- ☒ I acknowledge the required submittal format for the hard copy application is printed double sided 'head-to-toe', 2-hole punched (except the Sect. 2 landscape tables is printed 'head-to-head'), numbered tab separators. Incl. a copy of the check on a separate page.
- ☒ I acknowledge there is an annual fee for permits in addition to the permit review fee: www.env.nm.gov/air-quality/permit-fees-2/.
- ☐ This facility qualifies for the small business fee reduction per 20.2.75.11.C. NMAC. The full \$500.00 filing fee is included with this application and I understand the fee reduction will be calculated in the balance due invoice. The Small Business Certification Form has been previously submitted or is included with this application. (Small Business Environmental Assistance Program Information: www.env.nm.gov/air-quality/small-biz-eap-2/.)

Citation: Please provide the **low level citation** under which this application is being submitted: **20.2.72.200.A NMAC** (e.g. application for a new minor source would be 20.2.72.200.A NMAC, one example for a Technical Permit Revision is 20.2.72.219.B.1.b NMAC, a Title V acid rain application would be: 20.2.70.200.C NMAC)

Section 1 – Facility Information

Section 1-A: Company Information

		AI # if known (see 1 st 3 to 5 #s of permit IDEA ID No.):14	Updating Permit/NOI #:
1	Facility Name: Bitter Lake Compressor Station		Plant primary SIC Code (4 digits): 1311
			Plant NAIC code (6 digits):211130
a	Facility Street Address (If no facility street address, provide directions from a prominent landmark):		
2	Plant Operator Company Name: IACX Roswell LLC		Phone/Fax: (972) 960-3219/ N/A
a	Plant Operator Address: 5001 LBJ Freeway, Suite 300, Dallas, TX 75244		

b	Plant Operator's New Mexico Corporate ID or Tax ID:	
3	Plant Owner(s) name(s): IACX Roswell LLC	Phone/Fax: (972) 960-3219/ N/A
a	Plant Owner(s) Mailing Address(s): 5001 LBJ Freeway, Suite 300, Dallas, TX 75244	
4	Bill To (Company): IACX Roswell LLC	Phone/Fax: (972) 960-3219/ N/A
a	Mailing Address: 5001 LBJ Freeway, Suite 300, Dallas, TX 75244	E-mail: justinwheeler@iacx.com
5	<input checked="" type="checkbox"/> Preparer: James VanAssche <input checked="" type="checkbox"/> Consultant : James VanAssche	Phone/Fax: 972-842-4304
a	Mailing Address: James VanAssche, 115 FM 2453, Suite A, Royse City, TX 75189	E-mail: jva@resolutecompliance.com
6	Plant Operator Contact: Justin Wheeler	Phone/Fax: (972) 679-2147/ N/A
a	Address: 5001 LBJ Freeway, Suite 300, Dallas, TX 75244	E-mail: justinwheeler@iacx.com
7	Air Permit Contact: Justin Wheeler	Title: Director of Environmental, Health and Safety
a	E-mail: justinwheeler@iacx.com	Phone/Fax: (972) 679-2147/ N/A
b	Mailing Address: 5001 LBJ Freeway, Suite 300, Dallas, TX 75244	
c	The designated Air permit Contact will receive all official correspondence (i.e. letters, permits) from the Air Quality Bureau.	

Section 1-B: Current Facility Status

1.a	Has this facility already been constructed? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	1.b If yes to question 1.a, is it currently operating in New Mexico? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
2	If yes to question 1.a, was the existing facility subject to a Notice of Intent (NOI) (20.2.73 NMAC) before submittal of this application? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	If yes to question 1.a, was the existing facility subject to a construction permit (20.2.72 NMAC) before submittal of this application? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
3	Is the facility currently shut down? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	If yes, give month and year of shut down (MM/YY):
4	Was this facility constructed before 8/31/1972 and continuously operated since 1972? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
5	If Yes to question 3, has this facility been modified (see 20.2.72.7.P NMAC) or the capacity increased since 8/31/1972? <input type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> N/A	
6	Does this facility have a Title V operating permit (20.2.70 NMAC)? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	If yes, the permit No. is:
7	Has this facility been issued a No Permit Required (NPR)? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	If yes, the NPR No. is:
8	Has this facility been issued a Notice of Intent (NOI)? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	If yes, the NOI No. is:
9	Does this facility have a construction permit (20.2.72/20.2.74 NMAC)? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	If yes, the permit No. is:
10	Is this facility registered under a General permit (GCP-1, GCP-2, etc.)? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	If yes, the register No. is: 0274M7

Section 1-C: Facility Input Capacity & Production Rate

1	What is the facility's maximum input capacity, specify units (reference here and list capacities in Section 20, if more room is required)			
a	Current	Hourly: 1.25 MMSCF/hr	Daily: 30 MMSCFD	Annually: 10,950 MMSCF/yr
b	Proposed	Hourly: 1.25 MMSCF/hr	Daily: 30 MMSCFD	Annually: 10,950 MMSCF/yr
2	What is the facility's maximum production rate, specify units (reference here and list capacities in Section 20, if more room is required)			
a	Current	Hourly: 1.25 MMSCF/hr	Daily: 30 MMSCFD	Annually: 10,950 MMSCF/yr

b	Proposed	Hourly: 1.25 MMSCF/hr	Daily: 30 MMSCFD	Annually: 10,950 MMSCF/yr
---	----------	-----------------------	------------------	---------------------------

Section 1-D: Facility Location Information

1	Section: 14	Range: 24 E	Township: 11S	County: Chaves	Elevation (ft): 3,558
2	UTM Zone: <input type="checkbox"/> 12 or <input checked="" type="checkbox"/> 13			Datum: <input checked="" type="checkbox"/> NAD 27 <input type="checkbox"/> NAD 83 <input type="checkbox"/> WGS 84	
a	UTM E (in meters, to nearest 10 meters): 556,550			UTM N (in meters, to nearest 10 meters): 3,712,770	
b	AND Latitude (deg., min., sec.): 33.553056			Longitude (deg., min., sec.): -104.390833	
3	Name and zip code of nearest New Mexico town: Roswell 88201				
4	Detailed Driving Instructions from nearest NM town (attach a road map if necessary):				
5	The facility is 13.31 (distance) miles Northeast (direction) of Roswell (nearest town).				
6	Status of land at facility (check one): <input checked="" type="checkbox"/> Private <input type="checkbox"/> Indian/Pueblo <input type="checkbox"/> Federal BLM <input type="checkbox"/> Federal Forest Service <input type="checkbox"/> Other (specify)				
7	List all municipalities, Indian tribes, and counties within a ten (10) mile radius (20.2.72.203.B.2 NMAC) of the property on which the facility is proposed to be constructed or operated:				
8	20.2.72 NMAC applications only : Will the property on which the facility is proposed to be constructed or operated be closer than 50 km (31 miles) to other states, Bernalillo County, or a Class I area (see www.env.nm.gov/aqb/modeling/class1areas.html)? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No (20.2.72.206.A.7 NMAC) If yes, list all with corresponding distances in kilometers:				
9	Name nearest Class I area: Salt Creek Wilderness				
10	Shortest distance (in km) from facility boundary to the boundary of the nearest Class I area (to the nearest 10 meters): 1.80				
11	Distance (meters) from the perimeter of the Area of Operations (AO is defined as the plant site inclusive of all disturbed lands, including mining overburden removal areas) to nearest residence, school or occupied structure:				
12	Method(s) used to delineate the Restricted Area: "Restricted Area" is an area to which public entry is effectively precluded. Effective barriers include continuous fencing, continuous walls, or other continuous barriers approved by the Department, such as rugged physical terrain with steep grade that would require special equipment to traverse. If a large property is completely enclosed by fencing, a restricted area within the property may be identified with signage only. Public roads cannot be part of a Restricted Area.				
13	Does the owner/operator intend to operate this source as a portable stationary source as defined in 20.2.72.7.X NMAC? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No A portable stationary source is not a mobile source, such as an automobile, but a source that can be installed permanently at one location or that can be re-installed at various locations, such as a hot mix asphalt plant that is moved to different job sites.				
14	Will this facility operate in conjunction with other air regulated parties on the same property? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes If yes, what is the name and permit number (if known) of the other facility?				

Section 1-E: Proposed Operating Schedule (The 1-E.1 & 1-E.2 operating schedules may become conditions in the permit.)

1	Facility maximum operating ($\frac{\text{hours}}{\text{day}}$): 24	($\frac{\text{days}}{\text{week}}$): 7	($\frac{\text{weeks}}{\text{year}}$): 52	($\frac{\text{hours}}{\text{year}}$): 8760
2	Facility's maximum daily operating schedule (if less than 24 $\frac{\text{hours}}{\text{day}}$)? Start:		<input type="checkbox"/> AM <input type="checkbox"/> PM	End: <input type="checkbox"/> AM <input type="checkbox"/> PM
3	Month and year of anticipated start of construction:			
4	Month and year of anticipated construction completion:			
5	Month and year of anticipated startup of new or modified facility:			
6	Will this facility operate at this site for more than one year? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No			

Section 1-F: Other Facility Information

1	Are there any current Notice of Violations (NOV), compliance orders, or any other compliance or enforcement issues related to this facility? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If yes, specify:		
a	If yes, NOV date or description of issue:	NOV Tracking No:	
b	Is this application in response to any issue listed in 1-F, 1 or 1a above? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If Yes, provide the 1c & 1d info below:		
c	Document Title:	Date:	Requirement # (or page # and paragraph #):
d	Provide the required text to be inserted in this permit:		
2	Is air quality dispersion modeling or modeling waiver being submitted with this application? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
3	Does this facility require an "Air Toxics" permit under 20.2.72.400 NMAC & 20.2.72.502, Tables A and/or B? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		
4	Will this facility be a source of federal Hazardous Air Pollutants (HAP)? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
a	If Yes, what type of source? <input type="checkbox"/> Major (<input type="checkbox"/> ≥10 tpy of any single HAP OR <input type="checkbox"/> ≥25 tpy of any combination of HAPS) OR <input checked="" type="checkbox"/> Minor (<input type="checkbox"/> <10 tpy of any single HAP AND <input checked="" type="checkbox"/> <25 tpy of any combination of HAPS)		
5	Is any unit exempt under 20.2.72.202.B.3 NMAC? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		
a	If yes, include the name of company providing commercial electric power to the facility: _____ Commercial power is purchased from a commercial utility company, which specifically does not include power generated on site for the sole purpose of the user.		

Section 1-G: Streamline Application

(This section applies to 20.2.72.300 NMAC Streamline applications only)

1	<input type="checkbox"/> I have filled out Section 18, "Addendum for Streamline Applications." <input checked="" type="checkbox"/> N/A (This is not a Streamline application.)
---	--

Section 1-H: Current Title V Information - Required for all applications from TV Sources

(Title V-source required information for all applications submitted pursuant to 20.2.72 NMAC (Minor Construction Permits), or 20.2.74/20.2.79 NMAC (Major PSD/NNSR applications), and/or 20.2.70 NMAC (Title V))

1	Responsible Official (R.O.) (20.2.70.300.D.2 NMAC):		Phone:
a	R.O. Title:	R.O. e-mail:	
b	R. O. Address:		
2	Alternate Responsible Official (20.2.70.300.D.2 NMAC):		Phone:
a	A. R.O. Title:	A. R.O. e-mail:	
b	A. R. O. Address:		
3	Company's Corporate or Partnership Relationship to any other Air Quality Permittee (List the names of any companies that have operating (20.2.70 NMAC) permits and with whom the applicant for this permit has a corporate or partnership relationship):		
4	Name of Parent Company ("Parent Company" means the primary name of the organization that owns the company to be permitted wholly or in part.):		
a	Address of Parent Company:		
5	Names of Subsidiary Companies ("Subsidiary Companies" means organizations, branches, divisions or subsidiaries, which are owned, wholly or in part, by the company to be permitted.):		
6	Telephone numbers & names of the owners' agents and site contacts familiar with plant operations:		

7	<p>Affected Programs to include Other States, local air pollution control programs (i.e. Bernalillo) and Indian tribes:</p> <p>Will the property on which the facility is proposed to be constructed or operated be closer than 80 km (50 miles) from other states, local pollution control programs, and Indian tribes and pueblos (20.2.70.402.A.2 and 20.2.70.7.B)? If yes, state which ones and provide the distances in kilometers:</p>
---	--

Section 1-I – Submittal Requirements

Each 20.2.73 NMAC (NOI), a 20.2.70 NMAC (Title V), a 20.2.72 NMAC (NSR minor source), or 20.2.74 NMAC (PSD) application package shall consist of the following:

Hard Copy Submittal Requirements:

- 1) One hard copy **original signed and notarized application package printed double sided 'head-to-toe' 2-hole punched** as we bind the document on top, not on the side; except Section 2 (landscape tables), which should be **head-to-head**. Please use **numbered tab separators** in the hard copy submittal(s) as this facilitates the review process. For NOI submittals only, hard copies of UA1, Tables 2A, 2D & 2F, Section 3 and the signed Certification Page are required. **Please include a copy of the check on a separate page.**
- 2) If the application is for a minor NSR, PSD, NNSR, or Title V application, include one working hard **copy** for Department use. This **copy** should be printed in book form, 3-hole punched, and **must be double sided**. Note that this is in addition to the head-to-toe 2-hole punched copy required in 1) above. Minor NSR Technical Permit revisions (20.2.72.219.B NMAC) only need to fill out Sections 1-A, 1-B, 3, and should fill out those portions of other Section(s) relevant to the technical permit revision. TV Minor Modifications need only fill out Sections 1-A, 1-B, 1-H, 3, and those portions of other Section(s) relevant to the minor modification. NMED may require additional portions of the application to be submitted, as needed.
- 3) The entire NOI or Permit application package, including the full modeling study, should be submitted electronically. Electronic files for applications for NOIs, any type of General Construction Permit (GCP), or technical revisions to NSRs must be submitted with compact disk (CD) or digital versatile disc (DVD). For these permit application submittals, **two CD** copies are required (in sleeves, not crystal cases, please), with additional CD copies as specified below. NOI applications require only a **single CD** submittal. Electronic files for other New Source Review (construction) permits/permit modifications or Title V permits/permit modifications can be submitted on CD/DVD or sent through AQB's secure file transfer service.

Electronic files sent by (check one):

☒ CD/DVD attached to paper application

☐ secure electronic transfer. Air Permit Contact Name _____

Email _____

Phone number _____

a. If the file transfer service is chosen by the applicant, after receipt of the application, the Bureau will email the applicant with instructions for submitting the electronic files through a secure file transfer service. Submission of the electronic files through the file transfer service needs to be completed within 3 business days after the invitation is received, so the applicant should ensure that the files are ready when sending the hard copy of the application. The applicant will not need a password to complete the transfer. **Do not use the file transfer service for NOIs, any type of GCP, or technical revisions to NSR permits.**

- 4) Optionally, the applicant may submit the files with the application on compact disk (CD) or digital versatile disc (DVD) following the instructions above and the instructions in 5 for applications subject to PSD review.
- 5) If **air dispersion modeling** is required by the application type, include the **NMED Modeling Waiver** and/or electronic air dispersion modeling report, input, and output files. The dispersion modeling **summary report only** should be submitted as hard copy(ies) unless otherwise indicated by the Bureau.
- 6) If the applicant submits the electronic files on CD and the application is subject to PSD review under 20.2.74 NMAC (PSD) or NNSR under 20.2.79 NMC include,
 - a. one additional CD copy for US EPA,
 - b. one additional CD copy for each federal land manager affected (NPS, USFS, FWS, USDI) and,
 - c. one additional CD copy for each affected regulatory agency other than the Air Quality Bureau.

If the application is submitted electronically through the secure file transfer service, these extra CDs do not need to be submitted.

Electronic Submittal Requirements [in addition to the required hard copy(ies)]:

- 1) All required electronic documents shall be submitted as 2 separate CDs or submitted through the AQB secure file transfer service. Submit a single PDF document of the entire application as submitted and the individual documents comprising the application.
- 2) The documents should also be submitted in Microsoft Office compatible file format (Word, Excel, etc.) allowing us to access the text and formulas in the documents (copy & paste). Any documents that cannot be submitted in a Microsoft Office compatible

format shall be saved as a PDF file from within the electronic document that created the file. If you are unable to provide Microsoft office compatible electronic files or internally generated PDF files of files (items that were not created electronically: i.e. brochures, maps, graphics, etc.), submit these items in hard copy format. We must be able to review the formulas and inputs that calculated the emissions.

- 3) It is preferred that this application form be submitted as 4 electronic files (3 MSWord docs: Universal Application section 1 [UA1], Universal Application section 3-19 [UA3], and Universal Application 4, the modeling report [UA4]) and 1 Excel file of the tables (Universal Application section 2 [UA2]). Please include as many of the 3-19 Sections as practical in a single MS Word electronic document. Create separate electronic file(s) if a single file becomes too large or if portions must be saved in a file format other than MS Word.
- 4) The **electronic file names** shall be a maximum of 25 characters long (including spaces, if any). The format of the electronic Universal Application shall be in the format: "A-3423-FacilityName". The "A" distinguishes the file as an application submittal, as opposed to other documents the Department itself puts into the database. Thus, all electronic application submittals should begin with "A-". Modifications to existing facilities should use the **core permit number** (i.e. '3423') the Department assigned to the facility as the next 4 digits. Use 'XXXX' for new facility applications. The format of any separate electronic submittals (additional submittals such as non-Word attachments, re-submittals, application updates) and Section document shall be in the format: "A-3423-9-description", where "9" stands for the **section #** (in this case Section 9-Public Notice). Please refrain, as much as possible, from submitting any scanned documents as this file format is extremely large, which uses up too much storage capacity in our database. Please take the time to fill out the **header information** throughout all submittals as this will identify any loose pages, including the Application Date (date submitted) & Revision number (0 for original, 1, 2, etc.; which will help keep track of subsequent partial update(s) to the original submittal. Do not use special symbols (#, @, etc.) in file names. The footer information should not be modified by the applicant.

Table of Contents

Section 1:	General Facility Information
Section 2:	Tables
Section 3:	Application Summary
Section 4:	Process Flow Sheet
Section 5:	Plot Plan Drawn to Scale
Section 6:	All Calculations
Section 7:	Information Used to Determine Emissions
Section 8:	Map(s)
Section 9:	Proof of Public Notice
Section 10:	Written Description of the Routine Operations of the Facility
Section 11:	Source Determination
Section 12:	PSD Applicability Determination for All Sources & Special Requirements for a PSD Application
Section 13:	Discussion Demonstrating Compliance with Each Applicable State & Federal Regulation
Section 14:	Operational Plan to Mitigate Emissions
Section 15:	Alternative Operating Scenarios
Section 16:	Air Dispersion Modeling
Section 17:	Compliance Test History
Section 18:	Addendum for Streamline Applications (streamline applications only)
Section 19:	Requirements for the Title V (20.2.70 NMAC) Program (Title V applications only)
Section 20:	Other Relevant Information
Section 21:	Addendum for Landfill Applications
Section 22:	Certification Page

Table 2-A: Regulated Emission Sources

Unit and stack numbering must correspond throughout the application package. If applying for a NOI under 20.2.73 NMAC, equipment exemptions under 2.72.202 NMAC do not apply.

Unit Number ¹	Source Description	Make	Model #	Serial #	Manufacturer's Rated Capacity ³ (Specify Units)	Requested Permitted Capacity ³ (Specify Units)	Date of Manufacture ²	Controlled by Unit #	Source Classification Code (SCC)	For Each Piece of Equipment, Check One	RICE Ignition Type (CI, SI, 4SLB, 4SRB, 2SLB) ⁴	Replacing Unit No.
							Date of Construction/Reconstruction ²	Emissions vented to Stack #				
C-891	Compressor Engine	Cooper Bessemer	GMVH-10C	48778	2250 hp	1414 hp	4/7/1981	N/A	20200202	X Existing (unchanged) <input type="checkbox"/> New/Additional <input type="checkbox"/> To Be Modified	2SLB	
							11/15/1987	C-891		<input type="checkbox"/> To be Removed <input type="checkbox"/> Replacement Unit <input type="checkbox"/> To be Replaced		
C-893	Compressor Engine	Cooper Bessemer	GMVH-10C	48776	2250 hp	1391 hp	4/7/1981	N/A	20200202	X Existing (unchanged) <input type="checkbox"/> New/Additional <input type="checkbox"/> To Be Modified	2SLB	
							12/1/1989	C-893		<input type="checkbox"/> To be Removed <input type="checkbox"/> Replacement Unit <input type="checkbox"/> To be Replaced		
C-894	Compressor Engine	CAT	3408C LE	BAZ02303	425 hp	425 hp	5/15/2006	N/A	20200202	X Existing (unchanged) <input type="checkbox"/> New/Additional <input type="checkbox"/> To Be Modified	4SLB	
							TBD	C-894		<input type="checkbox"/> To be Removed <input type="checkbox"/> Replacement Unit <input type="checkbox"/> To be Replaced		
C-895	Compressor Engine	CAT	3408C LE	BAZ00179	425 hp	425 hp	6/5/2002	N/A	20200202	X Existing (unchanged) <input type="checkbox"/> New/Additional <input type="checkbox"/> To Be Modified	4SLB	
							TBD	C-895		<input type="checkbox"/> To be Removed <input type="checkbox"/> Replacement Unit <input type="checkbox"/> To be Replaced		
BL-GDS-1	Glycol Dehydrator	Lakota	N/A	N/A	30 MMscf/d	30 MMscf/d	1/1/1980	BL-GDR-1a	31000301	X Existing (unchanged) <input type="checkbox"/> New/Additional <input type="checkbox"/> To Be Modified	N/A	
							1/1/1980	N/A		<input type="checkbox"/> To be Removed <input type="checkbox"/> Replacement Unit <input type="checkbox"/> To be Replaced		
TK-1	Produced Water Tank	N/A	N/A	19428	100 bbl/day	100 bbl/day	1/2/2008	N/A	40400311	<input type="checkbox"/> Existing (unchanged) <input type="checkbox"/> New/Additional X To Be Modified	N/A	
							1/23/2008	N/A		<input type="checkbox"/> To be Removed <input type="checkbox"/> Replacement Unit <input type="checkbox"/> To be Replaced		
TK-2	Condensate/Produced Water Tank	N/A	1415	19349	100 bbl/day	100 bbl/day	1/17/2008	N/A	40400311	<input type="checkbox"/> Existing (unchanged) <input type="checkbox"/> New/Additional X To Be Modified	N/A	
							1/17/2008	N/A		<input type="checkbox"/> To be Removed <input type="checkbox"/> Replacement Unit <input type="checkbox"/> To be Replaced		
TK-2a	Condensate Tank	N/A	N/A	19342	100 bbl/day	100 bbl/day	1/16/2008	N/A	40400311	<input type="checkbox"/> Existing (unchanged) <input type="checkbox"/> New/Additional X To Be Modified	N/A	
							1/16/2008	N/A		<input type="checkbox"/> To be Removed <input type="checkbox"/> Replacement Unit <input type="checkbox"/> To be Replaced		
FUG	Facility Fugitive Emissions	N/A	N/A	N/A	N/A	N/A	N/A	N/A	31000220	X Existing (unchanged) <input type="checkbox"/> New/Additional <input type="checkbox"/> To Be Modified	N/A	
							N/A	N/A		<input type="checkbox"/> To be Removed <input type="checkbox"/> Replacement Unit <input type="checkbox"/> To be Replaced		
Load-1	Condensate Loading Emissions	N/A	N/A	N/A	N/A	N/A	N/A	N/A	40600132	<input type="checkbox"/> Existing (unchanged) <input type="checkbox"/> New/Additional X To Be Modified	N/A	
							N/A	N/A		<input type="checkbox"/> To be Removed <input type="checkbox"/> Replacement Unit <input type="checkbox"/> To be Replaced		
Load-2	Produced Water Loading Emissions	N/A	N/A	N/A	N/A	N/A	N/A	N/A	40600132	<input type="checkbox"/> Existing (unchanged) <input type="checkbox"/> New/Additional X To Be Modified	N/A	
							N/A	N/A		<input type="checkbox"/> To be Removed <input type="checkbox"/> Replacement Unit <input type="checkbox"/> To be Replaced		
SSM	Startup, Shutdown, and Maintenance	N/A	N/A	N/A	N/A	N/A	N/A	N/A	31088811	X Existing (unchanged) <input type="checkbox"/> New/Additional <input type="checkbox"/> To Be Modified	N/A	
							N/A	N/A		<input type="checkbox"/> To be Removed <input type="checkbox"/> Replacement Unit <input type="checkbox"/> To be Replaced		
M	Malfunction	N/A	N/A	N/A	N/A	N/A	N/A	N/A	31088811	X Existing (unchanged) <input type="checkbox"/> New/Additional <input type="checkbox"/> To Be Modified	N/A	
							N/A	N/A		<input type="checkbox"/> To be Removed <input type="checkbox"/> Replacement Unit <input type="checkbox"/> To be Replaced		

¹ Unit numbers must correspond to unit numbers in the previous permit unless a complete cross reference table of all units in both permits is provided.² Specify dates required to determine regulatory applicability.³ To properly account for power conversion efficiencies, generator set rated capacity shall be reported as the rated capacity of the engine in horsepower, not the kilowatt capacity of the generator set.⁴ "4SLB" means four stroke lean burn engine, "4SRB" means four stroke rich burn engine, "2SLB" means two stroke lean burn engine, "CI" means compression ignition, and "SI" means spark ignition

Table 2-B: Exempted Equipment (20.2.72 NMAC)

All 20.2.70 NMAC (Title V) applications must list all Insignificant Activities in this table. All 20.2.72 NMAC applications must list Exempted Equipment in this table. If equipment listed on this table is exempt under 20.2.72.202.B.5, include emissions calculations and emissions totals for 202.B.5 "similar functions" units, operations, and activities in Section 6, Calculations. Equipment and activities exempted under 20.2.72.202 NMAC may not necessarily be Insignificant under 20.2.70 NMAC (and vice versa). Unit & stack numbering must be consistent throughout the application package. Per Exemptions Policy 02-012.00 (see http://www.env.nm.gov/aqb/permit/aqb_pol.html), 20.2.72.202.B NMAC Exemptions do not apply, but 20.2.72.202.A NMAC exemptions do apply to NOI facilities under 20.2.73 NMAC. List 20.2.72.301.D.4 NMAC Auxiliary Equipment for Streamline applications in Table 2-A. The List of Insignificant Activities (for TV) can be found online at <https://www.env.nm.gov/wp-content/uploads/sites/2/2017/10/InsignificantListTitleV.pdf>. TV sources may elect to enter both TV Insignificant Activities and Part 72 Exemptions on this form.

Unit Number	Source Description	Manufacturer	Model No.	Max Capacity	List Specific 20.2.72.202 NMAC Exemption (e.g. 20.2.72.202.B.5)	Date of Manufacture /Reconstruction ²	For Each Piece of Equipment, Check One
			Serial No.	Capacity Units	Insignificant Activity citation (e.g. IA List Item #1.a)	Date of Installation /Construction ²	
BL-GDR-1a	Dehydrator Reboiler	Flameco	SB24-12	0.75	20.2.72.202.B.5 NMAC	1980	<input checked="" type="checkbox"/> Existing (unchanged) <input type="checkbox"/> To be Removed <input type="checkbox"/> New/Additional <input type="checkbox"/> Replacement Unit <input type="checkbox"/> To Be Modified <input type="checkbox"/> To be Replaced
			0509-415	MMBtu/hr		1980	
BL-GDR-2b	Dehydrator Reboiler	Flameco	SB24-12	0.75	20.2.72.202.B.5 NMAC	1980	<input checked="" type="checkbox"/> Existing (unchanged) <input type="checkbox"/> To be Removed <input type="checkbox"/> New/Additional <input type="checkbox"/> Replacement Unit <input type="checkbox"/> To Be Modified <input type="checkbox"/> To be Replaced
			0411-688	MMBtu/hr		1980	
TK-3	Lube Oil Tank	N/A	N/A	N/A	20.2.72.202.B.2 NMAC	N/A	<input checked="" type="checkbox"/> Existing (unchanged) <input type="checkbox"/> To be Removed <input type="checkbox"/> New/Additional <input type="checkbox"/> Replacement Unit <input type="checkbox"/> To Be Modified <input type="checkbox"/> To be Replaced
			N/A	N/A		N/A	
TK-6	Used Lube Oil Tank	N/A	N/A	N/A	20.2.72.202.B.2 NMAC	N/A	<input checked="" type="checkbox"/> Existing (unchanged) <input type="checkbox"/> To be Removed <input type="checkbox"/> New/Additional <input type="checkbox"/> Replacement Unit <input type="checkbox"/> To Be Modified <input type="checkbox"/> To be Replaced
			N/A	N/A		N/A	
TK-10	Lube Oil Tank	N/A	N/A	N/A	20.2.72.202.B.2 NMAC	N/A	<input checked="" type="checkbox"/> Existing (unchanged) <input type="checkbox"/> To be Removed <input type="checkbox"/> New/Additional <input type="checkbox"/> Replacement Unit <input type="checkbox"/> To Be Modified <input type="checkbox"/> To be Replaced
			N/A	N/A		N/A	
TK-12	Used Lube Oil Tank	N/A	N/A	N/A	20.2.72.202.B.2 NMAC	N/A	<input checked="" type="checkbox"/> Existing (unchanged) <input type="checkbox"/> To be Removed <input type="checkbox"/> New/Additional <input type="checkbox"/> Replacement Unit <input type="checkbox"/> To Be Modified <input type="checkbox"/> To be Replaced
			N/A	N/A		N/A	
HRU	Helium Recovery Unit	N/A	N/A	N/A	20.2.72.202.B.5 NMAC	N/A	<input checked="" type="checkbox"/> Existing (unchanged) <input type="checkbox"/> To be Removed <input type="checkbox"/> New/Additional <input type="checkbox"/> Replacement Unit <input type="checkbox"/> To Be Modified <input type="checkbox"/> To be Replaced
			N/A	N/A		N/A	
Haul	Facility Haul Roads	N/A	N/A	N/A	20.2.72.202.B.5 NMAC	N/A	<input checked="" type="checkbox"/> Existing (unchanged) <input type="checkbox"/> To be Removed <input type="checkbox"/> New/Additional <input type="checkbox"/> Replacement Unit <input type="checkbox"/> To Be Modified <input type="checkbox"/> To be Replaced
			N/A	N/A		N/A	
PIG-TANK	Temporary Tank for Pigging Liquids	N/A	N/A	N/A	20.2.72.202.B.5 NMAC	N/A	<input type="checkbox"/> Existing (unchanged) <input type="checkbox"/> To be Removed <input type="checkbox"/> New/Additional <input type="checkbox"/> Replacement Unit <input type="checkbox"/> To Be Modified <input type="checkbox"/> To be Replaced
			N/A	N/A		N/A	
							<input type="checkbox"/> Existing (unchanged) <input type="checkbox"/> To be Removed <input type="checkbox"/> New/Additional <input type="checkbox"/> Replacement Unit <input type="checkbox"/> To Be Modified <input type="checkbox"/> To be Replaced
							<input type="checkbox"/> Existing (unchanged) <input type="checkbox"/> To be Removed <input type="checkbox"/> New/Additional <input type="checkbox"/> Replacement Unit <input type="checkbox"/> To Be Modified <input type="checkbox"/> To be Replaced
							<input type="checkbox"/> Existing (unchanged) <input type="checkbox"/> To be Removed <input type="checkbox"/> New/Additional <input type="checkbox"/> Replacement Unit <input type="checkbox"/> To Be Modified <input type="checkbox"/> To be Replaced
							<input type="checkbox"/> Existing (unchanged) <input type="checkbox"/> To be Removed <input type="checkbox"/> New/Additional <input type="checkbox"/> Replacement Unit <input type="checkbox"/> To Be Modified <input type="checkbox"/> To be Replaced

¹ Insignificant activities exempted due to size or production rate are defined in 20.2.70.300.D.6, 20.2.70.7.Q NMAC, and the NMED/AQB List of Insignificant Activities, dated September 15, 2008. Emissions from these insignificant activities do not need to be reported, unless specifically requested.

² Specify date(s) required to determine regulatory applicability.

Unit and stack numbering must correspond throughout the application package. Only list control equipment for TAPs if the TAP's maximum uncontrolled emissions rate is over its respective threshold as listed in 20.2.72 NMAC, Subpart V, Tables A and B. In accordance with 20.2.72.203.A(3) and (8) NMAC, 20.2.70.300.D(5)(b) and (e) NMAC, and 20.2.73.200.B(7) NMAC, the permittee shall report all control devices and list each pollutant controlled by the control device regardless if the applicant takes credit for the reduction in emissions.

List each control device on a separate line. For each control device, list all emission units controlled by the control device.

Table 2-F: Additional Emissions during Startup, Shutdown, and Routine Maintenance (SSM)

☐ This table is intentionally left blank since all emissions at this facility due to routine or predictable startup, shutdown, or scheduled maintenance are no higher than those listed in Table 2-E and a malfunction emission limit is not already permitted or requested. If you are required to report GHG emissions as described in Section 6a, include any GHG emissions during Startup, Shutdown, and/or Scheduled Maintenance (SSM) in Table 2-P. Provide an explanations of SSM emissions in Section 6 and 6a.

All applications for facilities that have emissions during routine or predictable startup, shutdown or scheduled maintenance (SSM)¹, including NOI applications, must include in this table the Maximum Emissions during routine or predictable startup, shutdown and scheduled maintenance (20.2.7 NMAC, 20.2.72.203.A.3 NMAC, 20.2.73.200.D.2 NMAC). In Section 6 and 6a, provide emissions calculations for all SSM emissions reported in this table. Refer to "Guidance for Submittal of Startup, Shutdown, Maintenance Emissions in Permit Applications (https://www.env.nm.gov/aqb/permit/aqb_pol.html) for more detailed instructions. Numbers shall be expressed to at least 2 decimal points (e.g. 0.41, 1.41, or 1.41E-4).

[illegible]

¹ **For instance**, if the short term steady-state Table 2-E emissions are 5 lb/hr and the SSM rate is 12 lb/hr, enter 7 lb/hr in this table. If the annual steady-state Table 2-E emissions are 21.9 TPY, and the number of scheduled SSM events result in annual emissions of 31.9 TPY, enter 10.0 TPY in the table below.

² **Condensable Particulate Matter:** Include condensable particulate matter emissions for PM10 and PM2.5 if the source is a combustion source. Do not include condensable particulate matter for PM unless PM is set equal to PM10 and PM2.5. Particulate matter (PM) is not subject to an ambient air quality standard, but it is a regulated air pollutant under PSD (20.2.74 NMAC) and Title V (20.2.70 NMAC).

Table 2-G: Stack Exit and Fugitive Emission Rates for Special Stacks

X I have elected to leave this table blank because this facility does not have any stacks/vents that split emissions from a single source or combine emissions from more than one source listed in table 2-A. Additionally, the emission rates of all stacks match the Requested allowable emission rates stated in Table 2-E.

Use this table to list stack emissions (requested allowable) from split and combined stacks. List Toxic Air Pollutants (TAPs) and Hazardous Air Pollutants (HAPs) in Table 2-I. List all fugitives that are associated with the normal, routine, and non-emergency operation of the facility. Unit and stack numbering must correspond throughout the application package. Refer to Table 2-E for instructions on use of the “-” symbol and on significant figures.

[illegible]

Table 2-H: Stack Exit Conditions

Unit and stack numbering must correspond throughout the application package. Include the stack exit conditions for each unit that emits from a stack, including blowdown venting parameters and tank emissions. If the facility has multiple operating scenarios, complete a separate Table 2-H for each scenario and, for each, type scenario name here:

[illegible]

Table 2-I: Stack Exit and Fugitive Emission Rates for HAPs and TAPs

In the table below, report the Potential to Emit for each HAP from each regulated emission unit listed in Table 2-A, only if the entire facility emits the HAP at a rate greater than or equal to one (1) ton per year. For each such emission unit, HAPs shall be reported to the nearest 0.1 tpy. Each facility-wide Individual HAP total and the facility-wide Total HAPs shall be the sum of all HAP sources calculated to the nearest 0.1 ton per year. Per 20.2.72.403.A.1 NMAC, facilities not exempt [see 20.2.72.402.C NMAC] from TAP permitting shall report each TAP that has an uncontrolled emission rate in excess of its pounds per hour screening level specified in 20.2.72.502 NMAC. TAPs shall be reported using one more significant figure than the number of significant figures shown in the pound per hour threshold corresponding to the substance. Use the HAP nomenclature as it appears in Section 112 (b) of the 1990 CAAA and the TAP nomenclature as it listed in 20.2.72.502 NMAC. Include tank-flashing emissions estimates of HAPs in this table. For each HAP or TAP listed, fill all cells in this table with the emission numbers or a "-" symbol. A "-" symbol indicates that emissions of this pollutant are not expected or the pollutant is emitted in a quantity less than the threshold amounts described above.

Stack No.	Unit No.(s)	Total HAPs		Formaldehyde X HAP		Acetaldehyde X HAP		Acrolein X HAP		Benzene X HAP		Ethylbenzene X HAP		n-Hexane X HAP		Toluene X HAP		Xylene X HAP	
		lb/hr	ton/yr	lb/hr	ton/yr	lb/hr	ton/yr	lb/hr	ton/yr	lb/hr	ton/yr	lb/hr	ton/yr	lb/hr	ton/yr	lb/hr	ton/yr	lb/hr	ton/yr
C-891	C-891	0.7	3.1	0.5	2.3	0.1	0.3	0.1	0.3	0.0	0.1	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
C-893	C-893	0.7	3.1	0.5	2.3	0.1	0.3	0.1	0.3	0.0	0.1	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
C-894	C-894	0.2	1.0	0.2	0.8	0.0	0.1	0.0	0.1	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
C-895	C-895	0.2	1.0	0.2	0.8	0.0	0.1	0.0	0.1	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
BL-GDS-1	BL-GDS-1	0.0	0.2	-	-	-	-	-	-	-	-	0.0	0.0	-	-	-	-	0.0	0.0
TK-1	TK-1	0.0	0.0	-	-	-	-	-	-	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
TK-2	TK-2	0.1	0.3	-	-	-	-	-	-	0.0	0.0	0.0	0.0	0.1	0.2	0.0	0.0	0.0	0.0
TK-2a	TK-2a	0.2	1.0	-	-	-	-	-	-	0.0	0.1	0.0	0.0	0.2	0.9	0.0	0.0	0.0	0.0
FUG-1	FUG-1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Load -1	Load-1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Load -2	Load-2	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
SSM	SSM	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
M	M	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Totals:		2.2	9.7	1.4	6.2	0.2	0.9	0.2	0.8	0.1	0.2	0.0	0.0	0.3	1.3	0.0	0.1	0.0	0.1

Specify fuel characteristics and usage. Unit and stack numbering must correspond throughout the application package.

Printed 10/28/2021 8:39 AM

For each tank, list the liquid(s) to be stored in each tank. If it is expected that a tank may store a variety of hydrocarbon liquids, enter "mixed hydrocarbons" in the Composition column for that tank and enter the corresponding data of the most volatile liquid to be stored in the tank. If tank is to be used for storage of different materials, list all the materials in the "All Calculations" attachment, run the newest version of TANKS on each, and use the material with the highest emission rate to determine maximum uncontrolled and requested allowable emissions rate. The permit will specify the most volatile category of liquids that may be stored in each tank. Include appropriate tank-flashing modeling input data. Use additional sheets if necessary. Unit and stack numbering must correspond throughout the application package.

Printed 10/28/2021 8:39 AM

Include appropriate tank-flashing modeling input data. Use an addendum to this table for unlisted data categories. Unit and stack numbering must correspond throughout the application package. Use additional sheets if necessary. See reference Table 2-L2. Note: 1.00 bbl = 10.159 M3 = 42.0 gal

[illegible]

Table 2-L2: Liquid Storage Tank Data Codes Reference Table

Roof Type	Seal Type, Welded Tank Seal Type		Seal Type, Riveted Tank Seal Type		Roof, Shell Color	Paint Condition
FX: Fixed Roof	Mechanical Shoe Seal	Liquid-mounted resilient seal	Vapor-mounted resilient seal	Seal Type	WH: White	Good
IF: Internal Floating Roof	A: Primary only	A: Primary only	A: Primary only	A: Mechanical shoe, primary only	AS: Aluminum (specular)	Poor
EF: External Floating Roof	B: Shoe-mounted secondary	B: Weather shield	B: Weather shield	B: Shoe-mounted secondary	AD: Aluminum (diffuse)	
P: Pressure	C: Rim-mounted secondary	C: Rim-mounted secondary	C: Rim-mounted secondary	C: Rim-mounted secondary	LG: Light Gray	
Note: 1.00 bbl = 0.159 M ³ = 42.0 gal					MG: Medium Gray	
					BL: Black	
					OT: Other (specify)	

Note: $1.00 \text{ bbl} = 0.159 \text{ M}^3 = 42.0 \text{ gal}$

Table 2-M: Materials Processed and Produced (Use additional sheets as necessary.)

[illegible]

Table 2-N: CEM Equipment

Enter Continuous Emissions Measurement (CEM) Data in this table. If CEM data will be used as part of a federally enforceable permit condition, or used to satisfy the requirements of a state or federal regulation, include a copy of the CEM's manufacturer specification sheet in the Information Used to Determine Emissions attachment. Unit and stack numbering must correspond throughout the application package. Use additional sheets if necessary.

[illegible]

Unit and stack numbering must correspond throughout the application package. Use additional sheets if necessary.

[illegible]

Table 2-P: Greenhouse Gas Emissions

Applications submitted under 20.2.70, 20.2.72, & 20.2.74 NMAC are required to complete this Table. Power plants, Title V major sources, and PSD major sources must report and calculate all GHG emissions for each unit. Applicants must report potential emission rates in short tons per year (see Section 6.a for assistance). Include GHG emissions during Startup, Shutdown, and Scheduled Maintenance in this table. For minor source facilities that are not power plants, are not Title V, or are not PSD, there are three options for reporting GHGs 1) report GHGs for each individual piece of equipment; 2) report all GHGs from a group of unit types, for example report all combustion source GHGs as a single unit and all venting GHG as a second separate unit; OR 3) check the following box ☐ By checking this box, the applicant acknowledges the total CO₂e emissions are less than 75,000 tons per year.

		CO ₂ ton/yr	N ₂ O ton/yr	CH ₄ ton/yr	SF ₆ ton/yr	PFC/HFC ton/yr ²									Total GHG Mass Basis ton/yr ⁴	Total CO ₂ e ton/yr ⁵
Unit No.	GWPs ¹	1	298	25	22,800	footnote 3										
C-891	mass GHG	1262.8	0.0024	0.024												
	CO ₂ e	1262.8	0.7152	0.6												
C-893	mass GHG	1242.28	0.0023	0.023												
	CO ₂ e	1242.28	0.6854	0.575												
C-894	mass GHG	84.96	1.59E-04	1.59E-03												
	CO ₂ e	84.96	4.74E-02	3.98E-02												
C-895	mass GHG	84.96	1.59E-04	1.59E-03												
	CO ₂ e	84.96	4.74E-02	3.98E-02												
BL- GDR-1a	mass GHG	46.06	8.68E-05	8.68E-04												
	CO ₂ e	46.06	2.59E-02	2.17E-02												
BL- GDR-2b	mass GHG	46.06	8.68E-05	8.68E-04												
	CO ₂ e	46.06	2.59E-02	2.17E-02												
	mass GHG															
	CO ₂ e															
	mass GHG															
	CO ₂ e															
	mass GHG															
	CO ₂ e															
	mass GHG															
	CO ₂ e															
	mass GHG															
	CO ₂ e															
	mass GHG															
	CO ₂ e															
	mass GHG															
	CO ₂ e															
Total	mass GHG	2767.12	0.0051916	0.051916												
	CO ₂ e	2767.12	1.5470968	1.2979												

¹ GWP (Global Warming Potential): Applicants must use the most current GWPs codified in Table A-1 of 40 CFR part 98. GWPs are subject to change, therefore, applicants need to check 40 CFR 98 to confirm GWP values.

² For HFCs or PFCs describe the specific HFC or PFC compound and use a separate column for each individual compound.

³ For each new compound, enter the appropriate GWP for each HFC or PFC compound from Table A-1 in 40 CFR 98.

⁴ Green house gas emissions on a **mass basis** is the ton per year green house gas emission before adjustment with its GWP.

⁵ CO₂e means Carbon Dioxide Equivalent and is calculated by multiplying the TPY mass emissions of the green house gas by its GWP.

Section 3

Application Summary

The **Application Summary** shall include a brief description of the facility and its process, the type of permit application, the applicable regulation (i.e. 20.2.72.200.A.X, or 20.2.73 NMAC) under which the application is being submitted, and any air quality permit numbers associated with this site. If this facility is to be collocated with another facility, provide details of the other facility including permit number(s). In case of a revision or modification to a facility, provide the lowest level regulatory citation (i.e. 20.2.72.219.B.1.d NMAC) under which the revision or modification is being requested. Also describe the proposed changes from the original permit, how the proposed modification will affect the facility's operations and emissions, de-bottlenecking impacts, and changes to the facility's major/minor status (both PSD & Title V).

The **Process Summary** shall include a brief description of the facility and its processes.

Startup, Shutdown, and Maintenance (SSM) routine or predictable emissions: Provide an overview of how SSM emissions are accounted for in this application. Refer to "Guidance for Submittal of Startup, Shutdown, Maintenance Emissions in Permit Applications (http://www.env.nm.gov/aqb/permit/app_form.html) for more detailed instructions on SSM emissions.

IACX Roswell LLC (IACX) is submitting an application to transition their Bitter Lake Compressor Station (Bitter Lake) from a GCP O&G permit to an NSR. This is due to Bitter Lake Compressor Station being located within 3 miles of a Class I area, making it out of scope for a GCP O&G. The facility is a natural gas compressor station. Bitter Lake is located approximately 9.6 miles northeast of Roswell in Chaves County, New Mexico.


Bitter Lake is an extension of a local gas transportation system that gathers casinghead gas from multiple wells in the area. The facility compresses the gas for delivery to a main line. The site operates natural gas-fired engines (Units C-891, C-893, C-894, and C-895) to raise the discharge pressure of the gas in the pipeline to overcome the effect of frictional losses in the pipeline upstream of the station or from pressure losses/changes within the facility in order to maintain the required suction pressure at the next downstream facility. The volume of gas flowing and the amount of subsequent frictional losses in the pipeline are dependent on field conditions and downstream plant conditions causing pressure variations. The glycol dehydrator (Unit BL-GDS-1) has a capacity of 30 MMscf/day and the two associated reboilers operate a 0.75 MMBtu/hr (Units BL-GDR-1a and BL-GDR-2a). Only one of the two reboilers operates under normal operating conditions. The second reboiler may be used either as a backup unit or as a second unit in series to accommodate higher production rates and the resultant increased heat load on the glycol system. The helium recovery unit (Unit HRU) re-injects gas into the pipeline for further separation at another facility further downstream; therefore, there are no emissions associated with the unit. There are three condensate tanks located at the facility (Units TK-1, TK-2, and TK-2a), which contain hydrocarbons and water that drop out of the line prior to compression. There are associated loading emissions with the three condensate and produced water tanks (Unit Load-1 and Load-2). There are also lube oil tanks (Units TK-3 and TK-10) along with used lube oil tanks (Units TK-6 and TK-12).

Additional emissions result from facility-wide fugitives (Unit FUG), haul roads (Unit Haul), venting emissions during Startup, Shutdown, and Maintenance (Unit SSM), and Malfunction emissions (Unit M).

Section 4

Process Flow Sheet


A **process flow sheet** and/or block diagram indicating the individual equipment, all emission points and types of control applied to those points. The unit numbering system should be consistent throughout this application.



Section 5

Plot Plan Drawn To Scale

A **plot plan drawn to scale** showing emissions points, roads, structures, tanks, and fences of property owned, leased, or under direct control of the applicant. This plot plan must clearly designate the restricted area as defined in UA1, Section 1-D.12. The unit numbering system should be consistent throughout this application.



Section 6

All Calculations

Show all calculations used to determine both the hourly and annual controlled and uncontrolled emission rates. All calculations shall be performed keeping a minimum of three significant figures. Document the source of each emission factor used (if an emission rate is carried forward and not revised, then a statement to that effect is required). If identical units are being permitted and will be subject to the same operating conditions, submit calculations for only one unit and a note specifying what other units to which the calculations apply. All formulas and calculations used to calculate emissions must be submitted. The "Calculations" tab in the UA2 has been provided to allow calculations to be linked to the emissions tables. Add additional "Calc" tabs as needed. If the UA2 or other spread sheets are used, all calculation spread sheet(s) shall be submitted electronically in Microsoft Excel compatible format so that formulas and input values can be checked. Format all spread sheets and calculations such that the reviewer can follow the logic and verify the input values. Define all variables. If calculation spread sheets are not used, provide the original formulas with defined variables. Additionally, provide subsequent formulas showing the input values for each variable in the formula. All calculations, including those calculations are imbedded in the Calc tab of the UA2 portion of the application, the printed Calc tab(s), should be submitted under this section.

Tank Flashing Calculations: The information provided to the AQB shall include a discussion of the method used to estimate tank-flashing emissions, relative thresholds (i.e., NOI, permit, or major source (NSPS, PSD or Title V)), accuracy of the model, the input and output from simulation models and software, all calculations, documentation of any assumptions used, descriptions of sampling methods and conditions, copies of any lab sample analysis. If Hysis is used, all relevant input parameters shall be reported, including separator pressure, gas throughput, and all other relevant parameters necessary for flashing calculation.

SSM Calculations: It is the applicant's responsibility to provide an estimate of SSM emissions or to provide justification for not doing so. In this Section, provide emissions calculations for Startup, Shutdown, and Routine Maintenance (SSM) emissions listed in the Section 2 SSM and/or Section 22 GHG Tables and the rational for why the others are reported as zero (or left blank in the SSM/GHG Tables). Refer to "Guidance for Submittal of Startup, Shutdown, Maintenance Emissions in Permit Applications (http://www.env.nm.gov/aqb/permit/app_form.html) for more detailed instructions on calculating SSM emissions. If SSM emissions are greater than those reported in the Section 2, Requested Allowables Table, modeling may be required to ensure compliance with the standards whether the application is NSR or Title V. Refer to the Modeling Section of this application for more guidance on modeling requirements.

Glycol Dehydrator Calculations: The information provided to the AQB shall include the manufacturer's maximum design recirculation rate for the glycol pump. If GRI-Glycalc is used, the full input summary report shall be included as well as a copy of the gas analysis that was used.

Road Calculations: Calculate fugitive particulate emissions and enter haul road fugitives in Tables 2-A, 2-D and 2-E for:

1. If you transport raw material, process material and/or product into or out of or within the facility and have PER emissions greater than 0.5 tpy.
2. If you transport raw material, process material and/or product into or out of the facility more frequently than one round trip per day.

Significant Figures:

A. All emissions standards are deemed to have at least two significant figures, but not more than three significant figures.

B. At least 5 significant figures shall be retained in all intermediate calculations.

C. In calculating emissions to determine compliance with an emission standard, the following rounding off procedures shall be used:

- (1) If the first digit to be discarded is less than the number 5, the last digit retained shall not be changed;
- (2) If the first digit discarded is greater than the number 5, or if it is the number 5 followed by at least one digit other than the number zero, the last figure retained shall be increased by one unit; **and**
- (3) If the first digit discarded is exactly the number 5, followed only by zeros, the last digit retained shall be rounded upward if it is an odd number, but no adjustment shall be made if it is an even number.
- (4) The final result of the calculation shall be expressed in the units of the standard.




Control Devices: In accordance with 20.2.72.203.A(3) and (8) NMAC, 20.2.70.300.D(5)(b) and (e) NMAC, and 20.2.73.200.B(7) NMAC, the permittee shall report all control devices and list each pollutant controlled by the control device

regardless if the applicant takes credit for the reduction in emissions. The applicant can indicate in this section of the application if they chose to not take credit for the reduction in emission rates. For notices of intent submitted under 20.2.73 NMAC, only uncontrolled emission rates can be considered to determine applicability unless the state or federal Acts require the control. This information is necessary to determine if federally enforceable conditions are necessary for the control device, and/or if the control device produces its own regulated pollutants or increases emission rates of other pollutants.



AIR EMISSIONS CALCULATION TOOL

Instructions for Completing the Equipment Calculation Forms

1. Click the **Start Button** below to reset the form to begin data entry.
2. The **Air Emissions Calculation Tool** initially loads with the **Core Data Information Form**. Once all information is entered on this form, the necessary equipment calculation pages will be created based on the information entered on the Core Data Information Form. The customized **Air Emissions Calculation Tool** should now be saved to your computer before entering any other information on the equipment calculation pages. **Warning, every time you click on the Start Button below, the Air Emissions Calculation Tool will reset and all data entered will be lost.**
3.  Green/Blue colored information boxes require users to enter the required information for the subject facility. Default values may be changed if not appropriate for the facility.
4.  Yellow colored boxes represent calculated values based on user information entered and may not be changed.
5.  Yellow boxes with green/blue cross-hatching represent calculated values based on user information entered, however users may input data in these boxes, if necessary.

Start



Core Data Information

Mandatory - All appropriate Data Must Be Entered For All Boxes Below. This Data Will Automatically Create All Required Equipment Forms And Populate This Data In All Emissions Calculation Forms.

Date Field	<input type="text" value="Aug 26, 2021"/>	Permit/NOI/NPR Number	<input type="text" value="NSR 0274 and P-047"/>
Company Name:	<input type="text" value="IACX Roswell LLC"/>	Select Application Type	<input type="text" value="NSR"/>
Facility Name:	<input type="text" value="Bitter Lake Compressor Station"/>	Alt# if Known	<input type="text" value="14"/>
Max. Facility Gas Production	<input type="text" value="30,000"/> (Mscf/d)	<input type="text" value="1,250"/> (Mscf/h)	Elevation (ft.)
Max. Facility Oil Production	<input type="text" value="300"/> (BOPD)	<input type="text" value="12.5"/> (BOPH)	<input type="text" value="3,500"/>
Max. Facility Produced Water	<input type="text"/> (BWPD)	<input type="text"/> (BWPH)	Sour Gas Streams at This Site?
			<input type="text" value="NO"/>

Enter The Quantity Of All Air Emissions Sources Located At The Facility
(Leave Blank For Each Equipment Type That Is Not Present)

Equipment	Quantity	Equipment	Quantity
Amine Unit(s)		Compressor Engine (s)	4
Dehydrator(s)	1	Enclosed Combustion Device(s) (ECD)	
Equipment Fugitives	✓	Flare(s)	
Flash Tower/Ultra-Low Pressure Separator(s)^		Generator Engine (s)	
Gunbarrel Separator(s)/Tank(s)		Heater(s), Heater Treaters	
Number of Paved Haul Roads Segments		Number of Unpaved Haul Road Segments	1
Low Pressure Compressor(s)* & Compressor(s)*		Oil/Condensate Storage Tank(s)	3
Oil/Condensate Truck Loading	✓	Produced Water Storage Tank(s)	
Produced Water Truck Loading	✓	Pumpjack Engine(s)	
Reboilers(s) (Amine Units)		Placeholder for Future Use	
Reboilers(s) (Glycol, others)	1	Startup, Shutdown & Maintenance and Malfunction	✓
Skim Oil or Slop Oil Tank(s)		Thermal Oxidizer(s) (TO)	
Vapor Combustion Device(s) (VCU)		Vapor Recovery Unit(s) (VRU)^	1

Click Here to Generate Required Forms & Save to Your Computer

Complete all required forms that follow, for the equipment at the subject facility, based on the selections made above. Items with an * indicate an air emissions calculation form currently not required at this time and those with ^ indicate forms under construction at this time.



New Mexico Environment Department Air Quality Bureau Equipment Emissions Calculation Form

Date: Aug 26, 2021 **Permit Number:** NSR-NSR 0274 and P-C
Company Name: IACX Roswell LLC **Alt# if Known:** 14
Facility Name: Bitter Lake Compressor Station **Elevation (ft.):** 3,500

Non-Emergency SI Rich Burn, Lean Burn & Clean Burn Natural Gas Fired Compressor Engines (100% Load) & Stationary & Non-Road Diesel (≤600hp & >600hp) & Gasoline Compressor Engines (≤600hp)

Enter data in green-shaded areas only! One engine per form unless like-kind engines

Emission Unit ID:	ENG 1	Quantity of Like-kind Engines:	1
Engine Manufacturer:	Other	Engine Description:	Compressor Engine
Engine Model:	GMVH-10C	Hours/year	8,760
Engine Serial #:	48778	Fuel Type:	Field Gas
Engine Manuf. Date:	4/7/1981	Engine Deration <input checked="" type="radio"/> No Deration <input type="radio"/> Stationary - Naturally Aspirated <input type="radio"/> Stationary - Turbo Aspirated <input type="radio"/> Portable - Naturally Aspirated <input type="radio"/> Portable - Turbo Aspirated Select Source of Emission Factors <input checked="" type="radio"/> AP-42 Emission Factors <input type="radio"/> Manufacturer Specs (Enter Appropriate Emission Factors Below) or Diesel Tier 1, 2, 3 or 4 <input type="radio"/> NSPS JJJJ; Engine Manuf. Between July 1, 2007-June 30, 2010 & Engine HP≥500HP <input type="radio"/> NSPS JJJJ; Engine Manuf. On or after July 1, 2010 & Engine HP≥500HP <input type="radio"/> NSPS JJJJ; Engine Manuf. Between July 1, 2008-Dec. 31, 2010 & Engine HP 100≤HP<500 <input type="radio"/> NSPS JJJJ; Engine Manuf. on or after Jan.1, 2011 & Engine HP 100≤HP<500 <input type="radio"/> NSPS JJJJ; Eng. Manuf. Betw. Jan. 1, 2008-June 30, 2010 & LB Engine HP 500≤HP<1350 <input type="radio"/> NSPS JJJJ; Engine Manuf. on or after July 1, 2010 & LB Engine HP 500≤HP<1350 <input type="radio"/> NSPS JJJJ; Engines < 100HP (Enter Appropriate Emission Factors Below) <input type="radio"/> NSPS IIII; Stationary Diesel Engines	
Engine Type:	2SLB		
Factory HP Rating	1,414		
Allowable HP Rating	1,414		
Engine BSFC (Btu/(Hp*Hr))	6,785		
Fuel LHV, (BTU/SCF)	1,020	Notes:	
Fuel Sulfur (grains/dscf)	0.002		
Hourly Fuel Flow Rate (MMSCF/hr)	0.009406		
Annual Fuel Flow Rate (MMSCF/yr)	82.39656		
Maximum Engine RPM	1,000		
Exhaust Temperature (°F)	230		
Exhaust Velocity (ft/sec)	37.7		
Exhaust Flow (ACFM)	7,105.93		
Stack Diameter (ft)	2		
Stack Height (ft)	61		

Emission Factors, Catalyst Control Efficiency & Safety Factor						Uncontrolled Emissions		AP-42 Emissions		Controlled Emissions (includes SF) ¹	
Pollutant	Uncontrld. EF g/hp-hr	% Control Efficiency	% Safety Factor	Contrld EF g/(hp-hr)	AP-42 EF g/hp-hr	lb/hr	Tons/yr	lb/hr	Tons/yr	lb/hr	Tons/yr
NOx [^]	4	23.97	10	3.0411	9.7562	12.4691	54.6147	30.4128	133.2081	10.428	45.6746
CO	2.5	25.6	10	1.86	1.188	7.7932	34.1342	3.7033	16.2205	6.378	27.9356
VOC*	0.6	0	0	0.6	0.3693	1.8704	8.1924	1.1512	5.0423	1.8704	8.1924
Formaldehyde			0			0	0	0.5296	2.3196	0.5296	2.3196
TSP/PM10/PM2.5	0.1487	0	0	0.1487	0.1487	0.4635	2.0301	0.4635	2.0301	0.4635	2.0301
² SO ₂	0.042	0	0	0.042	0.00181	0.130926	0.573456	0.005642	0.024712	0.130926	0.573456
AP-42 HAPs	lb/MMBtu										
Formaldehyde	0.0552	NA	NA	NA	NA	0.52959	2.3196	NA	NA	NA	NA
Acetaldehyde	0.00776	NA	NA	NA	NA	0.07445	0.32609	NA	NA	NA	NA
Acrolein	0.00778	NA	NA	NA	NA	0.07464	0.32692	NA	NA	NA	NA
Benzene	0.00194	NA	NA	NA	NA	0.01861	0.08151	NA	NA	NA	NA
Ethylbenzene	0.000108	NA	NA	NA	NA	0.00104	0.00456	NA	NA	NA	NA
n-Hexane	0.000445	NA	NA	NA	NA	0.00427	0.0187	NA	NA	NA	NA
Toluene	0.000963	NA	NA	NA	NA	0.00924	0.04047	NA	NA	NA	NA
Xylene	0.000268	NA	NA	NA	NA	0.00257	0.01126	NA	NA	NA	NA
Total HAPs	NA	NA	NA	NA	NA	0.71441	3.12911	NA	NA	0.71	3.13

* Uncontrolled & Controlled VOC emissions include aldehyde emissions. VOC Emissions for JJJJ do not include aldehyde emissions. ¹ For NOx's & NPR, controlled emissions cannot be less than JJJJ emissions. ² SO₂ EF (grains/scf or ppm) except for AP-42 EF in g/hp-hr for SO₂ & EF Values for NOx, CO, VOC, TSP/PM10/PM2.5 in lb/hp-hr for large gasoline & diesel engines. [^]NOx+NMHC Emission Factors for diesel engines assume 75% NOx and 25% VOC



New Mexico Environment Department Air Quality Bureau Emissions Calculation Forms

Calculation Tool for Non-Emergency SI Rich Burn, Lean Burn & Clean Burn Natural Gas Fired Compressor Engines (100% Load) & Large Stationary Diesel (≤ 600 hp & > 600 hp) & Gasoline Compressor Engines (≤ 600 hp) Emissions

AP-42 Gas-Fired Engine Emission factors based on AP-42, Tables 3.2-1, 3.2-2 & 3.2-3 (July 2000)

<https://www3.epa.gov/ttn/chief/ap42/ch03/final/c03s02.pdf>

40 CFR Part 60 Subpart JJJJ Emission Factors based on §60.4233 & Table 1

<http://www.ecfr.gov/cgi-bin/text-idx?node=sp40.7.60.jjjj>

AP-42 Diesel & Gasoline Fired Engine Emission factors based on AP-42, Tables 3.3-1, 3.2-2, 3.4-1, 3.4-2, 3.4-3 & 3.4-4

<https://www3.epa.gov/ttn/chief/ap42/ch03/final/c03s03.pdf>

40 CFR Part 60 Subpart IIII Emission Factors based on §60.4233 & Table 1

<http://www.ecfr.gov/cgi-bin/text-idx?node=sp40.7.60.iiiii>

EPA Tier 1-4 Nonroad Compression Ignition Emission Standards (EPA-42--B-16-022)

<https://nepis.epa.gov/Exe/ZyNET.exe/P100OA05.txt?ZyActionD=ZyDocument&Client=EPA&Index=2011%20Thru%202015&Docs=&Query=&Time=&EndTime=&SearchMethod=1&TocRestrict=n&Toc=&TocEntry=&QField=&QFieldYear=&QFieldMonth=&QFieldDay=&UseQField=&IntQFieldOp=0&ExtQFieldOp=0&XmlQuery=&File=D%3A%5CZYFILES%5CINDEX%20DATA%5C11THRU15%5CTXT%5C00000019%5CP100OA05.txt&User=ANONYMOUS&Password=anonymous&SortMethod=h%7C&MaximumDocuments=1&FuzzyDegree=0&ImageQuality=r75g8/r75g8/x150y150g16/i425&Display=hpfr&DefSeekPage=x&SearchBack=ZyActionL&Back=ZyActionS&BackDesc=Results%20page&MaximumPages=1&ZyEntry=1>

Emission factors for natural gas and field gas internal combustion engines may be based on AP-42, Tables 3.2-1, 3.2-2 or 3.2-3 or NSPS JJJJ emission standards or manufacturer specifications based on engine applicability.

NOx Sample Calculation Using AP-42 Emission Factors for a 500-HP 4-Stroke Rich Burn Engine

pph = NOx Emission Factor (EF) lb/MMBtu * Heat Value Btu/scf/1020 Btu/scf * Maximum Heat Input (MMBtu/hr) * Allowable HP * 1/1000000 MMBtu/Btu
 = 2.21 lb/MMBtu * 1020 Btu/scf/1020 Btu/scf * 7500 MMBtu/hr * 500 hp * 1/1000000 MMBtu/Btu
 = 8.29 lb/hr

tpy = NOx Emission Factor (EF) lb/MMBtu * Heat Value Btu/scf/1020 Btu/scf * Maximum Heat Input (MMBtu/hr) * Allowable HP * 1/1000000 MMBtu/Btu * 8760 hrs/yr * 1/2000 tons/lbs
 = 2.21 lb/MMBtu * 1020 Btu/scf/1020 Btu/scf * 0.5 MMBtu/hr * 1/1020 Btu/scf * 1000000/1 Btu/MMBtu * 8760 hrs/yr * 1ton/2000lbs
 = 36.31 tpy

AP-42 SO₂ emissions based on 100% conversion of fuel sulfur to SO₂ and assumes sulfur content in natural gas of 2,000 grains/10⁶ scf. The SO₂ emission factor is converted to other natural gas sulfur contents by multiplying the SO₂ emission factor by the ratio of the site-specific sulfur content (grains/10⁶ scf) to 2,000 grains/10⁶ scf. For all other engines not using AP-42, The SO₂ emissions are based on grains S/scf. Fuel Heat values for Diesel = 0.137 MMBtu/gal; LPG = 0.0905 MMBtu/gal and Gasoline = 0.13 MMBtu/gal per AP-42 Appendix A, pg 5 & 6. SO₂ emissions for all diesel engines not using AP-42, equals Gal Diesel/hr * diesel wt (lb)/gal * 15 ppm S * 64 lb SO₂/32 lb S, where diesel weighs 7.1089 lb/gal.

NOx Sample Calculation Using NSPS JJJJ Emission Factors for a July 1, 2010 500-HP 4-Stroke Rich Burn Engine

pph = NOx Emission Factor (EF) g/hp-hr * 1/453.6 lbs/grams * Allowable HP
 = 1 g/hp-hr * 1/453.6 lbs/grams * 500 hp
 = 1.1 lb/hr

tpy = NOx Emission Factor (EF) g/hp-hr * 1/453.6 lbs/grams * Allowable HP * 8760 hrs/yr * 1/2000 tons/lbs
 = 1 g/hp-hr * 1/453.6 lbs/grams * 500 hp * 8760 hrs/yr * 1ton/2000lbs
 = 4.82 tpy

Technical Disclaimer

This document is intended to help you accurately determine stationary compressor engine emissions. It does not supersede or replace any state or federal law, rule, or regulation. This guidance reflects the current understanding of how these units work and how they generate emissions, how they are monitored or tested, and what data are available for emissions determination, may change over time as the AQB continue scientific studies and as new information becomes available. The AQB welcome any data, information, or feedback that may improve our understanding of stationary compressor engine emissions and thereby further improve determinations within the emissions inventory. The calculation methods represented are intended as an emissions calculation aid; alternate calculation methods may be equally acceptable if they are based upon, and adequately demonstrate, sound engineering assumptions or data. If you have a question regarding the acceptability of a given emissions determination method, contact the Permitting Section at 505-476-4300.



New Mexico Environment Department Air Quality Bureau Equipment Emissions Calculation Form

Date: Aug 26, 2021 **Permit Number:** NSR-NSR 0274 and P-C
Company Name: IACX Roswell LLC **Alt# if Known:** 14
Facility Name: Bitter Lake Compressor Station **Elevation (ft.):** 3,500

Non-Emergency SI Rich Burn, Lean Burn & Clean Burn Natural Gas Fired Compressor Engines (100% Load) & Stationary & Non-Road Diesel (≤600hp & >600hp) & Gasoline Compressor Engines (≤600hp)

Enter data in green-shaded areas only! One engine per form unless like-kind engines

Emission Unit ID:	ENG 2	Quantity of Like-kind Engines:	1
Engine Manufacturer:	Other	Engine Description:	Compressor Engine
Engine Model:	GMVH-10C	Hours/year	8,760
Engine Serial #:	48776	Fuel Type:	Field Gas
Engine Manuf. Date:	4/7/1981	Engine Deration <input checked="" type="radio"/> No Deration <input type="radio"/> Stationary - Naturally Aspirated <input type="radio"/> Stationary - Turbo Aspirated <input type="radio"/> Portable - Naturally Aspirated <input type="radio"/> Portable - Turbo Aspirated Select Source of Emission Factors <input checked="" type="radio"/> AP-42 Emission Factors <input type="radio"/> Manufacturer Specs (Enter Appropriate Emission Factors Below) or Diesel Tier 1, 2, 3 or 4 <input type="radio"/> NSPS JJJJ; Engine Manuf. Between July 1, 2007-June 30, 2010 & Engine HP≥500HP <input type="radio"/> NSPS JJJJ; Engine Manuf. On or after July 1, 2010 & Engine HP≥500HP <input type="radio"/> NSPS JJJJ; Engine Manuf. Between July 1, 2008-Dec. 31, 2010 & Engine HP 100≤HP<500 <input type="radio"/> NSPS JJJJ; Engine Manuf. on or after Jan.1, 2011 & Engine HP 100≤HP<500 <input type="radio"/> NSPS JJJJ; Eng. Manuf. Betw. Jan. 1, 2008-June 30, 2010 & LB Engine HP 500≤HP<1350 <input type="radio"/> NSPS JJJJ; Engine Manuf. on or after July 1, 2010 & LB Engine HP 500≤HP<1350 <input type="radio"/> NSPS JJJJ; Engines < 100HP (Enter Appropriate Emission Factors Below) <input type="radio"/> NSPS IIII; Stationary Diesel Engines	
Engine Type:	2SLB		
Factory HP Rating	1,391		
Allowable HP Rating	1,391		
Engine BSFC (Btu/(Hp*Hr))	6,785		
Fuel LHV, (BTU/SCF)	1,020	Notes:	
Fuel Sulfur (grains/dscf)	0.002		
Hourly Fuel Flow Rate (MMSCF/hr)	0.009253		
Annual Fuel Flow Rate (MMSCF/yr)	81.05628		
Maximum Engine RPM	1,000		
Exhaust Temperature (°F)	230		
Exhaust Velocity (ft/sec)	36.4		
Exhaust Flow (ACFM)	6,862.5		
Stack Diameter (ft)	2		
Stack Height (ft)	61		

Emission Factors, Catalyst Control Efficiency & Safety Factor						Uncontrolled Emissions		AP-42 Emissions		Controlled Emissions (includes SF) ¹	
Pollutant	Uncontrld. EF g/hp-hr	% Control Efficiency	% Safety Factor	Contrld EF g/(hp-hr)	AP-42 EF g/hp-hr	lb/hr	Tons/yr	lb/hr	Tons/yr	lb/hr	Tons/yr
NOx [^]	4.001	52.16	0	1.914	9.7562	12.2694	53.74	29.9182	131.0417	5.8694	25.708
CO	2.5	-0.32	0	2.5079	1.188	7.6664	33.5788	3.6431	15.9568	7.6907	33.6853
VOC*	0.6	0	0	0.6	0.3693	1.8399	8.0588	1.1325	4.9604	1.8399	8.0588
Formaldehyde			0			0	0	0.521	2.282	0.521	2.282
TSP/PM10/PM2.5	0.1487	0	0	0.1487	0.1487	0.456	1.9973	0.456	1.9973	0.456	1.9973
² SO ₂	0.042	0	0	0.042	0.00181	0.128796	0.564126	0.005551	0.024313	0.128796	0.564126
AP-42 HAPs	lb/MMBtu										
Formaldehyde	0.0552	NA	NA	NA	NA	0.52097	2.28185	NA	NA	NA	NA
Acetaldehyde	0.00776	NA	NA	NA	NA	0.07324	0.32079	NA	NA	NA	NA
Acrolein	0.00778	NA	NA	NA	NA	0.07343	0.32162	NA	NA	NA	NA
Benzene	0.00194	NA	NA	NA	NA	0.01831	0.0802	NA	NA	NA	NA
Ethylbenzene	0.000108	NA	NA	NA	NA	0.00102	0.00447	NA	NA	NA	NA
n-Hexane	0.000445	NA	NA	NA	NA	0.0042	0.0184	NA	NA	NA	NA
Toluene	0.000963	NA	NA	NA	NA	0.00909	0.03981	NA	NA	NA	NA
Xylene	0.000268	NA	NA	NA	NA	0.00253	0.01108	NA	NA	NA	NA
Total HAPs	NA	NA	NA	NA	NA	0.70279	3.07822	NA	NA	0.7	3.08

* Uncontrolled & Controlled VOC emissions include aldehyde emissions. VOC Emissions for JJJJ do not include aldehyde emissions. ¹ For NOx's & NPR, controlled emissions cannot be less than JJJJ emissions. ² SO₂ EF (grains/scf or ppm) except for AP-42 EF in g/hp-hr for SO₂ & EF Values for NOx, CO, VOC, TSP/PM10/PM2.5 in lb/hp-hr for large gasoline & diesel engines. [^]NOx+NMHC Emission Factors for diesel engines assume 75% NOx and 25% VOC



New Mexico Environment Department Air Quality Bureau Equipment Emissions Calculation Form

Date: Aug 26, 2021 **Permit Number:** NSR-NSR 0274 and P-C
Company Name: IACX Roswell LLC **Alt# if Known:** 14
Facility Name: Bitter Lake Compressor Station **Elevation (ft.):** 3,500

Non-Emergency SI Rich Burn, Lean Burn & Clean Burn Natural Gas Fired Compressor Engines (100% Load) & Stationary & Non-Road Diesel (≤600hp & >600hp) & Gasoline Compressor Engines (≤600hp)

Enter data in green-shaded areas only! One engine per form unless like-kind engines

Emission Unit ID:	ENG 3	Quantity of Like-kind Engines:	1
Engine Manufacturer:	Caterpillar	Engine Description:	Compressor Engine
Engine Model:	3408C LE	Hours/year	8,760
Engine Serial #:	BAZ02303	Fuel Type:	Field Gas
Engine Manuf. Date:	5/15/2006	Engine Deration <input checked="" type="radio"/> No Deration <input type="radio"/> Stationary - Naturally Aspirated <input type="radio"/> Stationary - Turbo Aspirated <input type="radio"/> Portable - Naturally Aspirated <input type="radio"/> Portable - Turbo Aspirated Select Source of Emission Factors <input checked="" type="radio"/> AP-42 Emission Factors <input type="radio"/> Manufacturer Specs (Enter Appropriate Emission Factors Below) or Diesel Tier 1, 2, 3 or 4 <input type="radio"/> NSPS JJJJ; Engine Manuf. Between July 1, 2007-June 30, 2010 & Engine HP≥500HP <input type="radio"/> NSPS JJJJ; Engine Manuf. On or after July 1, 2010 & Engine HP≥500HP <input type="radio"/> NSPS JJJJ; Engine Manuf. Between July 1, 2008-Dec. 31, 2010 & Engine HP 100≤HP<500 <input type="radio"/> NSPS JJJJ; Engine Manuf. on or after Jan.1, 2011 & Engine HP 100≤HP<500 <input type="radio"/> NSPS JJJJ; Eng. Manuf. Betw. Jan. 1, 2008-June 30, 2010 & LB Engine HP 500≤HP<1350 <input type="radio"/> NSPS JJJJ; Engine Manuf. on or after July 1, 2010 & LB Engine HP 500≤HP<1350 <input type="radio"/> NSPS JJJJ; Engines < 100HP (Enter Appropriate Emission Factors Below) <input type="radio"/> NSPS IIII; Stationary Diesel Engines	
Engine Type:	4SLB		
Factory HP Rating	425		
Allowable HP Rating	425		
Engine BSFC (Btu/(Hp*Hr))	7,995		
Fuel LHV, (BTU/SCF)	1,020	Notes:	
Fuel Sulfur (grains/dscf)	0.002		
Hourly Fuel Flow Rate (MMSCF/hr)	0.003331		
Annual Fuel Flow Rate (MMSCF/yr)	29.17956		
Maximum Engine RPM	1,800		
Exhaust Temperature (°F)	880		
Exhaust Velocity (ft/sec)	54.5		
Exhaust Flow (ACFM)	2,570		
Stack Diameter (ft)	1		
Stack Height (ft)	18.1		

Emission Factors, Catalyst Control Efficiency & Safety Factor						Uncontrolled Emissions		AP-42 Emissions		Controlled Emissions (includes SF) ¹	
Pollutant	Uncontrld. EF g/hp-hr	% Control Efficiency	% Safety Factor	Contrld EF g/(hp-hr)	AP-42 EF g/hp-hr	lb/hr	Tons/yr	lb/hr	Tons/yr	lb/hr	Tons/yr
NOx [^]	1	0	0	1	14.7963	0.9369	4.1036	13.8634	60.7217	0.9369	4.1036
CO	1.84	0	0	1.84	1.1496	1.724	7.5511	1.0771	4.7177	1.724	7.5511
VOC*	0.53	0	0	0.53	0.4279	0.4966	2.1751	0.4009	1.7559	0.4966	2.1751
Formaldehyde			0			0	0	0.1794	0.7858	0.1794	0.7858
TSP/PM10/PM2.5	0.0362	0	0	0.0362	0.0362	0.0339	0.1485	0.0339	0.1485	0.0339	0.1485
² SO ₂	0.0479	0	0	0.0479	0.002132	0.04488	0.196574	0.001998	0.008751	0.04488	0.196574
AP-42 HAPs	lb/MMBtu										
Formaldehyde	0.0528	NA	NA	NA	NA	0.17941	0.78582	NA	NA	NA	NA
Acetaldehyde	0.00836	NA	NA	NA	NA	0.02841	0.12444	NA	NA	NA	NA
Acrolein	0.00514	NA	NA	NA	NA	0.01747	0.07652	NA	NA	NA	NA
Benzene	0.00044	NA	NA	NA	NA	0.0015	0.00657	NA	NA	NA	NA
Ethylbenzene	0.0000397	NA	NA	NA	NA	0.00013	0.00057	NA	NA	NA	NA
n-Hexane	0.0011	NA	NA	NA	NA	0.00374	0.01638	NA	NA	NA	NA
Toluene	0.000408	NA	NA	NA	NA	0.00139	0.00609	NA	NA	NA	NA
Xylene	0.000184	NA	NA	NA	NA	0.00063	0.00276	NA	NA	NA	NA
Total HAPs	NA	NA	NA	NA	NA	0.23268	1.01915	NA	NA	0.23	1.02

* Uncontrolled & Controlled VOC emissions include aldehyde emissions. VOC Emissions for JJJJ do not include aldehyde emissions. ¹ For NO_x's & NPR, controlled emissions cannot be less than JJJJ emissions. ² SO₂ EF (grains/scf or ppm) except for AP-42 EF in g/hp-hr for SO₂ & EF Values for NO_x, CO, VOC, TSP/PM10/PM2.5 in lb/hp-hr for large gasoline & diesel engines. [^]NO_x+NMHC Emission Factors for diesel engines assume 75% NO_x and 25% VOC



New Mexico Environment Department Air Quality Bureau Equipment Emissions Calculation Form

Date: Aug 26, 2021 **Permit Number:** NSR-NSR 0274 and P-C
Company Name: IACX Roswell LLC **Alt# if Known:** 14
Facility Name: Bitter Lake Compressor Station **Elevation (ft.):** 3,500

Non-Emergency SI Rich Burn, Lean Burn & Clean Burn Natural Gas Fired Compressor Engines (100% Load) & Stationary & Non-Road Diesel (≤600hp & >600hp) & Gasoline Compressor Engines (≤600hp)

Enter data in green-shaded areas only! One engine per form unless like-kind engines

Emission Unit ID:	ENG 4	Quantity of Like-kind Engines:	1
Engine Manufacturer:	Caterpillar	Engine Description:	Compressor Engine
Engine Model:	3408C LE	Hours/year	8,760
Engine Serial #:	BAZ00179	Fuel Type:	Field Gas
Engine Manuf. Date:	6/5/2002	Engine Deration <input checked="" type="radio"/> No Deration <input type="radio"/> Stationary - Naturally Aspirated <input type="radio"/> Stationary - Turbo Aspirated <input type="radio"/> Portable - Naturally Aspirated <input type="radio"/> Portable - Turbo Aspirated	No Deration. Notes:
Engine Type:	4SLB		
Factory HP Rating	425		
Allowable HP Rating	425		
Engine BSFC (Btu/(Hp*Hr))	7,995		
Fuel LHV, (BTU/SCF)	1,020	Select Source of Emission Factors <input checked="" type="radio"/> AP-42 Emission Factors <input type="radio"/> Manufacturer Specs (Enter Appropriate Emission Factors Below) or Diesel Tier 1, 2, 3 or 4 <input type="radio"/> NSPS JJJJ; Engine Manuf. Between July 1, 2007-June 30, 2010 & Engine HP≥500HP <input type="radio"/> NSPS JJJJ; Engine Manuf. On or after July 1, 2010 & Engine HP≥500HP <input type="radio"/> NSPS JJJJ; Engine Manuf. Between July 1, 2008-Dec. 31, 2010 & Engine HP 100≤HP<500 <input type="radio"/> NSPS JJJJ; Engine Manuf. on or after Jan.1, 2011 & Engine HP 100≤HP<500 <input type="radio"/> NSPS JJJJ; Eng. Manuf. Betw. Jan. 1, 2008-June 30, 2010 & LB Engine HP 500≤HP<1350 <input type="radio"/> NSPS JJJJ; Engine Manuf. on or after July 1, 2010 & LB Engine HP 500≤HP<1350 <input type="radio"/> NSPS JJJJ; Engines < 100HP (Enter Appropriate Emission Factors Below) <input type="radio"/> NSPS IIII; Stationary Diesel Engines	
Fuel Sulfur (grains/dscf)	0.002		
Hourly Fuel Flow Rate (MMSCF/hr)	0.003331		
Annual Fuel Flow Rate (MMSCF/yr)	29.17956		
Maximum Engine RPM	1,800		
Exhaust Temperature (°F)	800		
Exhaust Velocity (ft/sec)	54.5		
Exhaust Flow (ACFM)	2,570		
Stack Diameter (ft)	1		
Stack Height (ft)	18.8		

Emission Factors, Catalyst Control Efficiency & Safety Factor						Uncontrolled Emissions		AP-42 Emissions		Controlled Emissions (includes SF) ¹	
Pollutant	Uncontrl'd. EF g/hp-hr	% Control Efficiency	% Safety Factor	Contrl'd EF g/(hp-hr)	AP-42 EF g/hp-hr	lb/hr	Tons/yr	lb/hr	Tons/yr	lb/hr	Tons/yr
NOx [^]	1	0	0	1	14.7963	0.9369	4.1036	13.8634	60.7217	0.9369	4.1036
CO	1.84	0	0	1.84	1.1496	1.724	7.5511	1.0771	4.7177	1.724	7.5511
VOC*	0.53	0	0	0.53	0.4279	0.4966	2.1751	0.4009	1.7559	0.4966	2.1751
Formaldehyde			0			0	0	0.1794	0.7858	0.1794	0.7858
TSP/PM10/PM2.5	0.0362	0	0	0.0362	0.0362	0.0339	0.1485	0.0339	0.1485	0.0339	0.1485
² SO ₂	0.0479	0	0	0.0479	0.002132	0.04488	0.196574	0.001998	0.008751	0.04488	0.196574
AP-42 HAPs	lb/MMBtu										
Formaldehyde	0.0528	NA	NA	NA	NA	0.17941	0.78582	NA	NA	NA	NA
Acetaldehyde	0.00836	NA	NA	NA	NA	0.02841	0.12444	NA	NA	NA	NA
Acrolein	0.00514	NA	NA	NA	NA	0.01747	0.07652	NA	NA	NA	NA
Benzene	0.00044	NA	NA	NA	NA	0.0015	0.00657	NA	NA	NA	NA
Ethylbenzene	0.0000397	NA	NA	NA	NA	0.00013	0.00057	NA	NA	NA	NA
n-Hexane	0.0011	NA	NA	NA	NA	0.00374	0.01638	NA	NA	NA	NA
Toluene	0.000408	NA	NA	NA	NA	0.00139	0.00609	NA	NA	NA	NA
Xylene	0.000184	NA	NA	NA	NA	0.00063	0.00276	NA	NA	NA	NA
Total HAPs	NA	NA	NA	NA	NA	0.23268	1.01915	NA	NA	0.23	1.02

* Uncontrolled & Controlled VOC emissions include aldehyde emissions. VOC Emissions for JJJJ do not include aldehyde emissions. ¹ For NO_x's & NPR, controlled emissions cannot be less than JJJJ emissions. ² SO₂ EF (grains/scf or ppm) except for AP-42 EF in g/hp-hr for SO₂ & EF Values for NO_x, CO, VOC, TSP/PM10/PM2.5 in lb/hp-hr for large gasoline & diesel engines. ³ NO_x+NMHC Emission Factors for diesel engines assume 75% NO_x and 25% VOC



New Mexico Environment Department Air Quality Bureau Emissions Calculation Forms

Date: Aug 26, 2021

Company Name: IACX Roswell LLC

Facility Name: Bitter Lake Compressor Station

Permit Number: NSR 0274 and P-047

Altitude: 14

Elevation (ft.): 3,500

Total Requested Emissions For All Regulated Engines (NSR Request)																		
UnitID	NOx		CO		VOC		SOx		TSP		PM10		PM2.5		H2S		Total HAP	
	lb/hr	tons/yr	lb/hr	tons/yr	lb/hr	tons/yr	lb/hr	tons/yr	lb/hr	tons/yr	lb/hr	tons/yr	lb/hr	tons/yr	lb/hr	tons/yr	lb/hr	tons/yr
ENG 1	10.43	45.67	6.38	27.94	1.87	8.19	0.13	0.57	0.46	2.03	0.46	2.03	0.46	2.03	0.71	3.13		
ENG 2	5.87	25.71	7.69	33.69	1.84	8.06	0.13	0.56	0.46	2	0.46	2	0.46	2	0.7	3.08		
ENG 3	0.94	4.1	1.72	7.55	0.5	2.18	0.04	0.2	0.03	0.15	0.03	0.15	0.03	0.15	0.23	1.02		
ENG 4	0.94	4.1	1.72	7.55	0.5	2.18	0.04	0.2	0.03	0.15	0.03	0.15	0.03	0.15	0.23	1.02		
ENG 5	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
ENG 6	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
ENG 7	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
ENG 8	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
GEN 1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
GEN 2	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
GEN 3	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
GEN 4	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
GEN 5	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
GEN 6	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
GEN 7	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
GEN 8	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
PJENG 1	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
PJENG 2	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
PJENG 3	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
PJENG 4	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
PJENG 5	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
PJENG 6	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
PJENG 7	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
PJENG 8	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
Page Totals	18.18	79.58	17.51	76.73	4.71	20.61	0.34	1.53	0.98	4.33	0.98	4.33	0.98	4.33	1.87	8.25		



New Mexico Environment Department Air Quality Bureau Equipment Emissions Calculation Form

Date: Aug 26, 2021	Permit Number: NSR-NSR 0274 and P-C
Company Name: IACX Roswell LLC	Alt# if Known: 14
Facility Name: Bitter Lake Compressor Station	Elevation (ft.): 3,500

Dehydration Unit Emissions Calculations Form

GRI-GLYCalc	Select Dehydration Unit Emission Calculation Method	Process Simulator
Is 40 CFR Part 63, Subpart HH Applicable?	Yes	Explain Below & Indicate How Compliance Will be Achieved.
Notes:		

Process Simulator Dehydration Unit Emission Calculations

Please attach the selected Process Simulator printout with all input data provided along with the calculated emissions. Enter the uncontrolled VOC, Benzene & H₂S emissions below. If the tank vapors are routed to a flare, enclosed combustion device, vapor combustion unit, vapor recovery unit or thermal oxidizer select the appropriate VOC destruction method below along with selected VOC & H₂S destruction efficiency supported by manufacturer specifications submitted with the application.

Dehydration Unit Information			
Select Process Simulator	ProMax	Is a Flash Tank Used?	No
Hours of Operation (hrs/yr)	8,760	Dry Gas Flow Rate (MMscf/d)	30
Type of Glycol Employed	TEG (Triethylene Glycol)	Wet Gas Temperature (°F)	112
Glycol Flow Rate (gpm)	5.49	Wet Gas Pressure (psig)	820
Flash Tank Pressure (psig)	86	Flash Tank Temperature (°F)	140

Dehydration Unit Control Information				
	Flash Tank		Regenerator	
	pph	tpy	pph	tpy
Uncontrolled VOC Emissions	0	0	16.56	72.53
Uncontrolled Total HAP Emissions	0	0	2.9965	13.1248
Uncontrolled Benzene Emissions	0	0	0	0
Uncontrolled H ₂ S Emissions	0	0	0	0
Control Method	Fuel Gas		Condenser & Reboiler	
VOC Destruction Efficiency	100		97.5	
H ₂ S Destruction Efficiency			97.5	

Notes: Flash tank not-in-use.

Total VOC, Benzene & H₂S Emissions From Dehydration Unit Calculated with Selected Process Simulator

Unit Number	VOC		Total HAP		Benzene		H ₂ S	
	pph	tpy	pph	tpy	pph*	tpy*	pph	tpy
BL-GDS-1								
Uncontrolled Emissions	16.56	72.53	3	13.12	0	0	0	0
Controlled Emissions	0.41	1.81	0.07	0.33	0	0	0	0



Date: Aug 26, 2021

Company Name: IACX Roswell LLC

Facility Name: Bitter Lake Compressor Station

Permit Number: NSR 0274 and P-047

Altitude: 14

Elevation (ft.): 3,500

Reboilers for Glycol Dehydration Units & Other Units (Only for units rated <100 MMBTU/Hr)

Enter appropriate information in green boxes below changing default values as appropriate and adding additional rows for each heater unit.

Enter the Sulfur Content of Gas or use default value (grains/10⁶ scf).

2,000

SO₂ emissions based on AP-42 EF and assumes 100% conversion of fuel sulfur to SO₂ and assumes sulfur content in natural gas of 2,000 grains/1000000 scf. Change default value of 2000 as needed based on gas analysis submitted with application.

1,020

Total Emissions For Reboilers For Glycol Dehydration Units & Other Units												
Add/Remove Rows	Unit ID	Heat Input	NO _x		CO		VOC		SO ₂		PM/PM ₁₀ /PM _{2.5}	
			pph	tpy	pph	tpy	pph	tpy	pph	tpy	pph	tpy
+	ReBoiler-1	0.75	0.074	0.324	0.062	0.272	0.004	0.018	0	0	0.006	0.026
-												
+	ReBoiler-2	0.75	0.074	0.324	0.062	0.272	0.004	0.018	0	0	0.006	0.026
-												
	Totals		0.148	0.648	0.124	0.544	0.008	0.036	0	0	0.012	0.052



Uncontrolled Emissions Calculation Tool for All Reboilers For Glycol Dehydration Units & Other Units (Only for units rated <100 MMBTU/Hr)

All emission factors based on AP-42, Table 1.4-1, Table 1.4-2 and Table 1.4-3 (July 1998)

<https://www3.epa.gov/ttn/chief/ap42/ch01/final/c01s04.pdf>

Emission factors for natural gas combustion in boilers and furnaces are presented in AP42, Tables 1.4-1, 1.4-2, 1.4-3, and 1.4-4. The Tables present emission factors on a volume basis (lb/10⁶ scf). To convert to an energy basis (lb/MMBtu), divide by a heating value of 1,020 MMBtu/10⁶ scf. The emission factors may be converted to other natural gas heating values by multiplying the given emission factor by the ratio of the specified heating value to this average heating value.

NOx Sample Calculation

pph = AP 42 NOx Emission Factor (EF) * heat value Btu/scf/1020 Btu/scf * Maximum Heat Input (MMBtu/hr) * 1/Heat Value Btu/scf * 1000000/1Btu/MMBtu
= 100 lb/1000000 scf * 2000 Btu/scf/1020 Btu/scf * 0.5 MMBtu/hr * 1/2000 Btu/scf * 1000000/1Btu/MMBtu
= 0.096 lb/hr

tpy = AP 42 NOx Emission Factor (EF) * heat value Btu/scf/1020 Btu/scf * Maximum Heat Input (MMBtu/hr) * 1/Heat Value Btu/scf * 1000000/1 Btu/MMBtu * 8760 hrs/yr * 1ton/2000 lbs
= 100 lb/1000000 scf * 2000 Btu/scf/1020 Btu/scf * 0.5 MMBtu/hr * 1/2000 Btu/scf * 1000000/1 Btu/MMBtu * 8760 hrs/yr * 1ton/2000lbs
= 0.42 tpy

SO₂ emissions based on 100% conversion of fuel sulfur to SO₂ and assumes sulfur content in natural gas of 2,000 grains/10⁶ scf. The SO₂ emission factor in this table can be converted to other natural gas sulfur contents by multiplying the SO₂ emission factor by the ratio of the site-specific sulfur content (grains/10⁶ scf) to 2,000 grains/10⁶ scf.

Technical Disclaimer

This document is intended to help you accurately determine glycol reboiler emissions. It does not supersede or replace any state or federal law, rule, or regulation. This guidance reflects the current understanding of how these combustion units work and how they generate emissions, how they are monitored or tested, and what data are available for emissions determination, may change over time as the AQB continue scientific studies and as new information becomes available. The AQB welcome any data, information, or feedback that may improve our understanding of glycol reboiler emissions and thereby further improve determinations within the emissions inventory. The calculation methods represented are intended as an emissions calculation aid; alternate calculation methods may be equally acceptable if they are based upon, and adequately demonstrate, sound engineering assumptions or data. If you have a question regarding the acceptability of a given emissions determination method, contact the Permitting Section at 505-476-4300.



Date:	Aug 26, 2021	Permit Number:	NSR-NSR 0274 and P-C
Company Name:	IACX Roswell LLC	AI# if Known:	14
Facility Name:	Bitter Lake Compressor Station	Elevation (ft.):	3,500

Vapor Recovery Unit Air Emissions Calculations Form Under Development

Please submit all required calculations and supporting documentation for all vapor recovery unit emissions.



New Mexico Environment Department Air Quality Bureau Equipment Emissions Calculation Form

Date: Aug 26, 2021
Company Name: IACX Roswell LLC
Facility Name: Bitter Lake Compressor Station

Permit Number: NSR-NSR 0274 and P-C
Alt# if Known: 14
Elevation (ft.): 3,500

Vapor Recovery Unit (VRU) Process vs Control Determination

Please complete the Process vs. Control determination below for the VRT/ULPS, which addresses the three criteria referenced in the EPA Nov. 27, 1995 Process Guidance memo and enter appropriate Information in all green boxes.

1. Is the primary purpose of the equipment to control air pollution? (Check appropriate box)

☐ No, the primary purpose of the VRU equipment is to recover flash gas vapors and route them into an available gas sales line.

☐ Yes, the primary purpose of the VRULPS equipment is to control air pollution.

2. Where the equipment is recovering product, how do the cost savings from the product recovery compare to the cost of the equipment? (Check appropriate box)

☐ Yes, the benefit-cost analysis below demonstrates a positive return on investment. The benefit-cost analysis of the VRU equipment compared to the product recovered is shown below:

☐ No, the benefit- cost analysis below demonstrates a negative return on investment.

VRU-1	VRU-1 Benefit-Cost Analysis*		
Capital Cost of VRT/ULPS (\$)		Oil Production (BOPD)	300
VRT/ULPS/LPC/VRU Rental Costs (\$/mo)	\$0.00	VRT/ULPS Vapor Production (Mcf/d)	
Capital Cost of LPC/VRU (\$)	NA	Heating Value of Vapors (Btu/scf)	
Annual Maintenance & Service Costs (\$/yr)		Natural Gas Price (\$/MMBtu)	
Annual Electricity or Fuel Costs (\$/yr)		VRT/ULPS/LPC/VRU Life Expectancy (Yrs)	5
VRT/ULPS/LPC/VRU Lifetime Costs (\$)	\$0.00	Lifetime VRT/ULPS/LPC/VRU Profit (Revenues-Costs) (\$/yr)	\$0.00
Annual VRT/ULPS/LPC/VRU Revenue (\$/yr)	\$0.00	Payback Period (Yrs)	
VRT/ULPS/LPC/VRU Lifetime Revenue (\$)	\$0.00	Lifetime Benefit-Cost Ratio	

3. Would the equipment be installed if no air quality regulations are in place? (Check appropriate box)

☐ Yes, the VRU equipment would still be installed regardless of air quality regulations, due to the significant cost benefits of product recovery.

☐ No, the VRU equipment would not be installed if there were no air quality regulations in place.

Notes:

Footnote: All estimates based on current dollars unless specified otherwise; Tank vapor estimates based on flash calculation method noted in Tanks form based on oil throughput noted in p2 of AECT (this can be changed by user); Gas price based on EIA Natural Gas Weekly Update. * The time value of money is not taken into account.



Date: Aug 26, 2021
Company Name: IACX Roswell LLC
Facility Name: Bitter Lake Compressor Station

Permit Number: NSR-NSR 0274 and P-C
Alt if Known: 14
Elevation (ft.): 3,500

Vertical Fixed Roof (VFR) Oil/Condensate VOC Flash Emissions Calculations Form

Select Tanks Flash Emission Calculation Method

GOR	E & P Tanks	ProMax
Vasquez-Beggs	HYSYS	VMGSim

ProMax Oil Tanks Emission Calculations

Please attach the ProMAX printout with all input data provided along with the calculated emissions. Enter the uncontrolled VOC emissions below. If the tank vapors are routed to a flare, enclosed combustion device, vapor combustion unit, vapor recovery unit or thermal oxidizer select the appropriate VOC destruction method below along with selected VOC destruction efficiency supported by manufacturer specifications submitted with the application.

Tanks VOC Control Method

Capture Efficiency	100	Represent Uncaptured/Uncollected VOC's at Tanks	YES
VOC Control Method ¹	Vapor Recovery Unit (VRU)	Represent VRU/ULPC Downtime Emissions at Tanks	YES
VOC Destruction Efficiency ²	95	Represent VOC Controlled Emissions at Tanks*	YES

Notes

Total VOC Flash Emissions From Oil/Condensate Storage Tanks Calculated with ProMax

Add/Remove Rows	Tank ID	VOC Uncontrolled Emissions		VOC Emissions after Control		VOC Emissions at the Tanks	
Up To 10 Units		pph	tpy	pph*	tpy*	pph	tpy
<input type="checkbox"/> + <input type="checkbox"/> -	TK-1	0.01	0.01	0	0	0	0
<input type="checkbox"/> + <input type="checkbox"/> -	TK-2	18.24	79.87	0.91	3.99	0.91	3.99
<input type="checkbox"/> + <input type="checkbox"/> -	TK-2a	0.01	0.01	0	0	0	0
	Totals	18.26	79.89	0.91	3.99	0.91	3.99



New Mexico Environment Department Air Quality Bureau Emissions Calculation Forms

Calculation Tool for Tanks Flashing & Working & Standing Emissions for Oil & Gas Production Sites

All flash emissions based on flash calculation methodology selected;

- 1) The appropriate ECD, flare, TO, VCU or VRU form must also be completed.
- 2) Manufacturer documentation required to support % control selected. If using a VRU/LPC, calculations assume VRU/ULPC with a 100% control efficiency, but with 5% downtime;
- 3) Information included in calculation tool must be based on representative oil and gas analysis which must be submitted with application;
- 4) GOR and Vasquez-Beggs sample calculations outlined below; E & P Tanks, ProMax, HYSYS & VMG Sim flash emissions require submittal of computer simulation model emissions calculations print-outs;
- 5) Working & Standing emissions based on AP-42 Chpt. 7, tanks 4.09d computer simulation or ProMax, or VMG computer simulation models.

Sample Calculations

GOR Methodology

$$\begin{aligned} \text{VOC pph} &= \text{GOR (scf/bbl)} * \text{Facility Oil Throughput (BOPD)} * 1/24 (\text{Hours/Day} * 1/\text{Universal Gas Constant } 385 \text{ scf/lb-mole @ } 70^{\circ}\text{F, } 1 \text{ atm}) * \text{Molecular Weight of Tank Vapors (lb/lb-mol)} \\ &= 40 (\text{scf/bbl}) * 1000 (\text{BOPD}) * 1/24 (\text{hrs/day}) * 1/385 \text{ scf/lb-mol} * 50 \text{ lb/lb-mol} \\ &= 216.45 \text{ lbs/hr} \end{aligned}$$

$$\begin{aligned} \text{VOC tpy} &= \text{GOR (scf/bbl)} * \text{Facility Oil Throughput (BOPD)} * 1/24 (\text{Hours/Day} * 1/\text{Universal Gas Constant } 385 \text{ scf/lb-mole @ } 70^{\circ}\text{F, } 1 \text{ atm}) * \text{Molecular Weight of Tank Vapors (lb/lb-mol)} * 8760 \text{ hr/yr} * 1/2000 \text{ lbs/ton} \\ &= 40 (\text{scf/bbl}) * 1000 (\text{BOPD}) * 1/24 (\text{hrs/day}) * 1/385 \text{ scf/lb-mol} * 50 \text{ lb/lb-mol} * 8760 \text{ hr/yr} * 1/2000 \text{ lbs/ton} \\ &= 948.05 \text{ tpy} \end{aligned}$$

Vasquez-Beggs Methodology

INPUTS			Constraints				Constants			
API Gravity		API	16	<API>	58	⁰ API	⁰ API Gravity			
Separator Pressure (psig)		P	50	<P+Patm>	5250	psia	⁰ API	<30	≥30	Given ⁰ API
Separator Temp. (°F)		Ti	70	<Ti>	295	⁰ F	C1	0.0362	0.0178	
Separator Gas Gravity at Initial Condition		SGi	0.56	<SGi>	1.18	MW/28.97	C2	1.0937	1.187	
Barrels of Oil/Day (BOPD)	100	Q	None	<Q>	None	BOPD	C3	25.724	23.931	
Tank Gas MW		MW	18	<MW>	125	lb/lb-mole				
VOC Fraction of Tank Gas		VOC	0.5	<VOC>	1.00	Fraction				
Atmospheric Pressure (psia)		Patm	20	<Rs>	2070	scf/bbl				

$$\text{SGx} = \text{Dissolved gas gravity at Separator pressure} = \text{SGi} [1.0 + 0.00005912 * \text{API} * \text{Ti} * \text{Log}(\text{Pi}/114.7)]$$

$$\text{Rs} = (\text{C1} * \text{SGx} * \text{Pi}^{\text{C2}}) \exp((\text{C3} * \text{API}) / (\text{Ti} + 460)) \text{ for } P + \text{Patm}$$

$$\text{THC} = \text{Rs} * \text{Q} * \text{MW} * 1/385 \text{ scf/lb-mole} * 365 \text{ D/Yr} * 1 \text{ ton}/2000 \text{ lbs}$$

$$\text{VOC} = \text{THC} * \text{Frac. of C3+ in the Stock Tank Vapor}$$

Technical Disclaimer

This document is intended to help you accurately determine oil/condensate storage tank flash, working and standing emissions. It does not supersede or replace any state or federal law, rule, or regulation. This guidance reflects the current understanding of how these units work and how they generate emissions, how they are monitored or tested, and what data are available for emissions determination, may change over time as the AQB continue scientific studies and as new information becomes available. The AQB welcome any data, information, or feedback that may improve our understanding of oil/condensate storage tank flash, working and standing emissions and thereby further improve determinations within the emissions inventory. The calculation methods represented are intended as an emissions calculation aid; alternate calculation methods may be equally acceptable if they are based upon, and adequately demonstrate, sound engineering assumptions or data. If you have a question regarding the acceptability of a given emissions determination method, contact the Permitting Section at 505-476-4300.



Date: Aug 26, 2021
Company Name: IACX Roswell LLC
Facility Name: Bitter Lake Compressor Station

Permit Number: NSR-NSR 0274 and P-C
Alt# if Known: 14
Elevation (ft.): 3,500

Vertical Fixed Roof (VFR) Oil/Condensate VOC Working & Standing Emissions Calculations Form

Select Tanks W & S Emission Calculation Method

AP-42 Chpt. 7

EPA Tanks 4.09d

ProMax

E & P Tanks

ProMax Oil Tanks W & S Emission Calculations

Please attach the ProMAX printout with all input data provided along with the calculated emissions. Enter the uncontrolled VOC emissions below. If the tank vapors are routed to a flare, enclosed combustion device, vapor combustion unit, vapor recovery unit or thermal oxidizer select the appropriate VOC destruction method below along with selected VOC destruction efficiency supported by manufacturer specifications submitted with the application.

Tanks VOC Control Method

Capture Efficiency	100	Represent Uncaptured and/or Controlled VOC's at Tanks	YES
VOC Control Method	Vapor Recovery Unit (VRU)	Represent VRU/ULPC Downtime Emissions at Tanks	YES
VOC Destruction Efficiency	95	Represent VOC Controlled Emissions at Tanks*	YES

Notes: Based on ProMax flashing considering 5 psi pressure drop and sample analyzed 1/7/2019.
 VRU assumes a total of 5% bypass and downtime.

Total VOC W & S Emissions From Oil/Condensate Storage Tanks Calculated with ProMax

Add/Remove Rows Up To 10 Units	Tank ID	VOC Uncontrolled Emissions		VOC Emissions after Control		VOC Emissions at the Tanks	
		pph	tpy	pph*	tpy*	pph	tpy
<input type="checkbox"/> + <input type="checkbox"/> -	TK-1	0.01	0.01	0	0	0	0
<input type="checkbox"/> + <input type="checkbox"/> -	TK-2	1.06	4.65	0.05	0.23	0.05	0.23
<input type="checkbox"/> + <input type="checkbox"/> -	TK-2a	4.26	18.66	0.21	0.93	0.21	0.93
	Totals	5.33	23.32	0.26	1.16	0.26	1.16



New Mexico Environment Department Air Quality Bureau Equipment Emissions Calculation Form

Date: Aug 26, 2021
Company Name: IACX Roswell LLC
Facility Name: Bitter Lake Compressor Station

Permit Number: NSR-NSR 0274 and P-C
Alt# if Known: 14
Elevation (ft.): 3,500

Emissions From Loading Petroleum Liquid

Select Appropriate AP-42 Petroleum Liquid Loading Methodology & Enter appropriate information in the green boxes below changing default values as appropriate.

Emission Unit ID: OILLOAD-1

Facility Oil Throughput
(gal/yr)

2,820,720

Max. Hourly Loading
Rate (gal/hr)

8,000

Select Appropriate AP-42 Petroleum Liquid Loading Methodology Below*

☐ AP-42, 5.2-4 Equation 1

☒ AP-42, Table 5.2-5

S - Saturation Factor
(From AP-42 Table 5.2-1)

0.6

M - Molecular Weight of
Vapors (lb/lb-mole)

51.3

P_{annual} - Avg. Annual
True Vapor Pressure of
Liquid Loaded (psia)

12.03

P_{hourly} - Max Hourly
True Vapor Pressure of
Liquid Loaded (psia)

11.8

T_{annual} - Average
Annual Temperature °F
of Bulk Liquid Loaded

65.6

T_{hourly} - Maximum
Hourly Temperature °F
of Bulk Liquid Loaded

92.88

Select Emission Source - From AP-42 Table 5.2-5

- ☒ Submerged Loading Dedicated Normal Service
- ☐ Submerged Loading Vapor Balance Service
- ☐ Splash Loading Dedicated Normal Service
- ☐ Splash Loading Vapor Balance Service

Truck Loading VOC Control Method

Capture Efficiency	100	Represent Uncaptured/Uncollected VOC's at Loading Rack	YES
VOC Control Method ¹	Vapor Recovery Unit (VRU)	Represent VRU/ULPC Downtime Emissions at Loading Rack	YES
VOC Destruction Efficiency ²	95	Represent VOC Controlled Emissions at Loading Rack	NO

Notes

Total VOC Emissions From Loading Petroleum Liquids

Pollutant	VOC Uncontrolled Emissions		VOC Emissions after Control		VOC Emissions at the Loading Rack	
	pph*	tpy*	pph*	tpy*	pph*	tpy*
VOC	13.6	2.4	0.68	0.12	0.68	0.12

Footnote: * All emission factors based on AP-42, 5.2-4 Equation 1 or AP-42 Table 5.2-5 (July 2008); See next page for calculation notes. You may elect to represent the controlled emissions at the loading rack or at the control device or tanks by selecting the appropriate drop-down options under *Truck Loading VOC Control Method*.



Calculation Tool for Emissions From Loading Petroleum Liquid

Emissions based on AP-42, 5.2-4 Equation 1 (July 2008) or AP-42, Table 5.2-5
<https://www3.epa.gov/ttn/chief/ap42/ch05/final/c05s02.pdf>

AP-42 5.2-4 Equation 1

Emissions from loading petroleum liquid can be estimated (with a probable error of ± 30 percent)⁴ using the following expression:

$$\text{Equation 1} \quad L_L = 12.46 * \text{SPM}/T$$

where:

L_L = loading loss, pounds per 1000 gallons (lb/10³ gal) of liquid loaded;

S = a saturation factor (see Table 5.2-1 reproduced below))

P = true vapor pressure of liquid loaded, pounds per square inch absolute (psia) (see Section 7.1, "Organic Liquid Storage Tanks")

M = molecular weight of vapors, pounds per pound-mole (lb/lb-mole) (see Section 7.1, "Organic Liquid Storage Tanks")

T = temperature of bulk liquid loaded, °R (°F + 460)

$$\begin{aligned} \text{VOC pph} &= (12.46 * 0.6 * 7.0 \text{ (psia)} * 50 \text{ (lb/lb-mole)} / 550^\circ\text{R}) / 1000 \text{ (gal)} * 8400 \text{ (gal/hr)} \\ &= 39.96 \text{ lb/hr} \end{aligned}$$

$$\begin{aligned} \text{VOC tpy} &= (12.46 * 0.6 * 4.5 \text{ (psia)} * 50 \text{ (lb/lb-mole)} / 525^\circ\text{R}) / 1000 * 1533000 \text{ (gal/yr)} * 1/2000 \text{ (ton/lb)} \\ &= 2.46 \text{ tpy} \end{aligned}$$

Table 5.2-1. SATURATION (S) FACTORS FOR CALCULATING PETROLEUM LIQUID LOADING LOSSES

Cargo Carrier	Mode of Operation	S Factor
Tank trucks and rail tank cars	Submerged loading of a clean cargo tank	0.5
	Submerged loading: dedicated normal service	0.6
	Submerged loading: dedicated vapor balance service	1.0
	Splash loading of a clean cargo tank	1.45
	Splash loading: dedicated normal service	1.45
	Splash loading: dedicated vapor balance service	1.0
Marine vessels ^a	Submerged loading: ships	0.2
	Submerged loading: barges	0.5

^a For products other than gasoline and crude oil. For marine loading of gasoline, use factors from Table 5.2-2. For marine Loading of crude oil, use Equations 2 and 3 and Table 5.2-3.

AP-42 Table 5.2-5

$$\text{VOC pph} = (2\text{lb}/1000 \text{ (gal)}) * ((100-15)/100) * 8400 \text{ (gal/hr)} = 16.8 \text{ pph}$$

$$\text{VOC tpy} = (2\text{lb}/1000 \text{ (gal)}) * ((100-15)/100) * 100 \text{ (BOPD)} * 42 \text{ (gal/bbl)} * 365 \text{ (days/yr)} * 1/2000 \text{ (ton/lb)} = 1.53 \text{ tpy}$$

Table 5.2-5 TOTAL UNCONTROLLED ORGANIC EMISSION FACTORS FOR PETROLEUM LIQUID RAIL TANK CARS AND TANK TRUCKS

Emission Source	Mode of Operation	Crude Oil (lb/1000 gal transferred) ^b
Loading Operations ^c		
	Submerged loading: dedicated normal service	2
	Submerged loading: dedicated vapor balance service	3
	Splash loading: dedicated normal service	5
	Splash loading: dedicated vapor balance service	3

a Reference 2. VOC factors for crude oil can be assumed to be 15% lower than the total organic factors, to account for the methane and ethane content of crude oil evaporative emissions. All other products should be assumed to have VOC factors equal to total organics; b The example crude oil has an RVP of 34 kPa (5 psia); c Loading emission factors are calculated using Equation 1 for a dispensed product temperature of 16°C (60°F). In the absence of specific inputs for Equations 1, the typical evaporative emission factors presented in Tables 5.2-5 should be used. It should be noted that, although the crude oil used to calculate the emission values presented in this tables has an RVP of 5, the RVP of crude oils can range from less than 1 up to 10. In areas where loading and transportation sources are major factors affecting air quality, it is advisable to obtain the necessary parameters and to calculate emission estimates using Equations 1.

- 1) The appropriate ECD, flare, TO, VCU or VRU form must also be completed.
- 2) Manufacturer documentation required to support % control selected. If using a VRU/LPC, calculations assume VRU/ULPC with a 100% control efficiency, but with 5% downtime;
- 3) Information included in calculation tool must be based on representative oil and gas analysis which must be submitted with application;
- 4) Vapor balancing emissions to tanks must be represented at the tanks;

Technical Disclaimer

This document is intended to help you accurately determine truck loading petroleum emissions. It does not supersede or replace any state or federal law, rule, or regulation. This guidance reflects the current understanding of how truck loading operations work and how it generates emissions, how it is monitored or tested, and what data are available for emissions determination, may change over time as the AQB continue scientific studies and as new information becomes available. The AQB welcome any data, information, or feedback that may improve our understanding of truck loading petroleum emissions and thereby further improve determinations within the emissions inventory. The calculation methods represented are intended as an emissions calculation aid; alternate calculation methods may be equally acceptable if they are based upon, and adequately demonstrate, sound engineering assumptions or data. If you have a question regarding the acceptability of a given emissions determination method, contact the Permitting Section at 505-476-4300.



New Mexico Environment Department Air Quality Bureau Equipment Emissions Calculation Form

Date: Aug 26, 2021
Company Name: IACX Roswell LLC
Facility Name: Bitter Lake Compressor Station

Permit Number: NSR-NSR 0274 and P-C
Alt# if Known: 14
Elevation (ft.): 3,500

Startup, Shutdown & Maintenance and Malfunction

- ☐ No SSM emissions are expected from routine operations.
- ☒ Request up to 10 tpy of VOC SSM emissions.
- ☐ Request site specific VOC & H₂S SSM and enter information below.
- ☐ Request site specific VOC & H₂S SSM plus 10 tpy VOC and enter information below.
- ☐ Request site specific combustion SSM and those emissions are included in Section 4 (attach calculations.)
- ☒ Request 10 tpy VOC Malfunction emissions for GCP-O&G, GCP-6 or NSR permitting actions only.

	Blowdowns			Engine Startups		
Unit Numbers						
Quantity of Like-kind Blowdown Units or Engines	1					
Total Volume of Each Blowdown or Engine Startup Vent (acf)						
Duration of Event (Minutes)						
Maximum Blowdowns or Startups/hr	1					
Frequency of Blowdowns or Engine Startups (Events/yr)						
Total Actual Volume of Gas Vented (acf/yr)	0					
Pressure of Gas Inside Unit Before Venting (psig)						
Final Pressure (psia)	14.7					
Gas Temperature Prior to Venting (°F)						
Vented Gas Molecular Weight (lb/lb-mol)						
Vented Gas VOC wt %						
Vented Total HAP wt %						
Vented Gas Benzene wt %						
Vented Gas H ₂ S wt %						

Startup, Shutdown and Maintenance Emissions (SSM) and Malfunction Emissions

SSM	VOC		Total HAP		Benzene		H ₂ S	
	PPH	TPY	PPH	TPY	PPH	TPY	PPH	TPY
SSM Blowdowns								
SSM Startups								
SSM Other (Attach Calculations)								
SSM Totals		10						
Malfunction Total		10						

Notes



New Mexico Environment Department Air Quality Bureau Emissions Calculation Forms

Planned SSM Emissions

The venting emissions calculations herein should only be used when only gas (no liquids) is present in the unit. The calculation of the vented gas is based on the volume of the unit and assumes the unit is saturated with vapor at the pressure and temperature of the unit before venting occurs. If liquids are also present in the gas, please enter the calculated amounts in the SSM Other row only and submit separate calculations, since the calculations on this form do not account for the evaporation of liquids that may be present in the unit.

Calculations are based on the Ideal gas law: $P(V) = n(R)(T)$

VOC result = $\frac{((\text{Pressure of Gas Inside the Unit Before Venting}) * (\text{Actual Volume of the Vented Unit}))}{(\text{Frequency of events}) * (\text{Molecular Weight}) * \text{VOC wt\%}} \div (\text{Ideal Gas Constant}) * (\text{Temperature of Gas Inside the Unit Before Venting})$

Where the Ideal Gas Constant = 10.73159 (ft³*psia)/R*lb-mol

For SSM combustion emissions, attach separate calculations.



New Mexico Environment Department Air Quality Bureau Equipment Emissions Calculation Form

Date: Aug 26, 2021
Company Name: IACX Roswell LLC
Facility Name: Bitter Lake Compressor Station

Permit Number: NSR-NSR 0274 and P-C
Alt# if Known: 14
Elevation (ft.): 3,500

Emissions From Loading Produced Water Liquids

Select Appropriate AP-42 Petroleum Liquid Loading Methodology & Enter appropriate information in the green boxes below changing default values as appropriate.

Emission Unit ID: PWLOAD-1

Facility Produced Water Throughput (gal/yr)

1,793,610

Max. Hourly Loading Rate (gal/hr)

8,000

% Oil in Water

1

Select Appropriate AP-42 Petroleum Liquid Loading Methodology Below*

☐ AP-42, 5.2-4 Equation 1

☒ AP-42, Table 5.2-5

S - Saturation Factor
(From AP-42 Table 5.2-1)

0.6

M - Molecular Weight of Vapors (lb/lb-mole)

18.31

P_{annual} - Avg. Annual True Vapor Pressure of Liquid Loaded (psia)

0.31

P_{hourly} - Max Hourly True Vapor Pressure of Liquid Loaded (psia)

0.58

T_{annual} - Average Annual Temperature °F of Bulk Liquid Loaded

65.6

T_{hourly} - Maximum Hourly Temperature °F of Bulk Liquid Loaded

92.88

Select Emission Source - From AP-42 Table 5.2-5

- ☒ Submerged Loading Dedicated Normal Service
- ☐ Submerged Loading Vapor Balance Service
- ☐ Splash Loading Dedicated Normal Service
- ☐ Splash Loading Vapor Balance Service

Notes:

Total VOC Emissions From Loading Produced Water Liquids Based On % Oil in Water Selected Above

Pollutant	Uncontrolled Emissions (pph)	Uncontrolled Emissions (tpy)
VOC	0.14	0.02

Footnote: * All emission factors based on AP-42, 5.2-4 Equation 1 or AP-42 Table 5.2-5 (July 2008); See reverse side for calculation notes



Calculation Tool for Emissions From Loading Produced Water Liquids

Emissions based on AP-42, 5.2-4 Equation 1 (July 2008) or AP-42, Table 5.2-5

<https://www3.epa.gov/ttn/chief/ap42/ch05/final/c05s02.pdf>

AP-42 5.2-4 Equation 1

Emissions from loading produced water liquids can be estimated (with a probable error of ± 30 percent)⁴ using the following expression:

$$\text{Equation 1} \quad L_L = 12.46 * \text{SPM}/T$$

where:

L_L = loading loss, pounds per 1000 gallons (lb/10³ gal) of liquid loaded (assumes 1% oil in water)

S = a saturation factor (see Table 5.2-1 reproduced below)

P = true vapor pressure of liquid loaded, pounds per square inch absolute (psia) (see Section 7.1, "Organic Liquid Storage Tanks")

M = molecular weight of vapors, pounds per pound-mole (lb/lb-mole) (see Section 7.1, "Organic Liquid Storage Tanks")

T = temperature of bulk liquid loaded, °R (°F + 460)

$$\begin{aligned} \text{VOC pph} &= (12.46 * 0.6 * 7.0 \text{ (psia)} * 50 \text{ (lb/lb-mole)} / 550^\circ\text{R}) / 1000 \text{ (gal)} * 8400 \text{ (gal/hr)} * 0.01 \text{ (1\% oil in water)} \\ &= 39.96 \text{ lb/hr} \end{aligned}$$

$$\begin{aligned} \text{VOC tpy} &= (12.46 * 0.6 * 4.5 \text{ (psia)} * 50 \text{ (lb/lb-mole)} / 525^\circ\text{R}) / 1000 * 1533000 \text{ (gal/hr)} * 1/2000 \text{ (ton/lbs)} * 0.01 \text{ (1\% oil in water)} \\ &= 2.46 \text{ tpy} \end{aligned}$$

Table 5.2-1. SATURATION (S) FACTORS FOR CALCULATING PETROLEUM LIQUID LOADING LOSSES

Cargo Carrier	Mode of Operation	S Factor
Tank trucks and rail tank cars	Submerged loading of a clean cargo tank	0.5
	Submerged loading: dedicated normal service	0.6
	Submerged loading: dedicated vapor balance service	1.0
	Splash loading of a clean cargo tank	1.45
	Splash loading: dedicated normal service	1.45
	Splash loading: dedicated vapor balance service	1.0
Marine vessels ^a	Submerged loading: ships	0.2
	Submerged loading: barges	0.5

^a For products other than gasoline and crude oil. For marine loading of gasoline, use factors from Table 5.2-2. For marine Loading of crude oil, use Equations 2 and 3 and Table 5.2-3.

AP-42 Table 5.2-5 (assumes 1% oil in water)

$$\text{VOC pph} = (2\text{lb}/1000 \text{ (gal)}) * ((100-15)/100) * 8400 \text{ (gal/hr)} * 0.01 \text{ (1\% oil in water)} = 0.168 \text{ pph}$$

$$\text{VOC tpy} = (2\text{lb}/1000 \text{ (gal)}) * ((100-15)/100) * 100 \text{ (BOPD)} * 42 \text{ (gal/bbl)} * 365 \text{ (days/yr)} * 1/2000 \text{ (ton/lb)} * 0.01 \text{ (1\% oil in water)} = 0.0153 \text{ tpy}$$

Table 5.2-5 TOTAL UNCONTROLLED ORGANIC EMISSION FACTORS FOR PETROLEUM LIQUID RAIL TANK CARS AND TANK TRUCKS

Emission Source	Mode of Operation	Crude Oil (lb/1000 gal transferred) ^b
Loading Operations ^c		
	Submerged loading: dedicated normal service	2
	Submerged loading: dedicated vapor balance service	3
	Splash loading: dedicated normal service	5
	Splash loading: dedicated vapor balance service	3

^a Reference 2. VOC factors for crude oil can be assumed to be 15% lower than the total organic factors, to account for the methane and ethane content of crude oil evaporative emissions. All other products should be assumed to have VOC factors equal to total organics; ^b The example crude oil has an RVP of 34 kPa (5 psia); ^c Loading emission factors are calculated using Equation 1 for a dispensed product temperature of 16°C (60°F). In the absence of specific inputs for Equations 1, the typical evaporative emission factors presented in Tables 5.2-5 should be used. It should be noted that, although the crude oil used to calculate the emission values presented in this tables has an RVP of 5, the RVP of crude oils can range from less than 1 up to 10. In areas where loading and transportation sources are major factors affecting air quality, it is advisable to obtain the necessary parameters and to calculate emission estimates using Equations 1.

Technical Disclaimer

This document is intended to help you accurately determine truck loading produced water emissions. It does not supersede or replace any state or federal law, rule, or regulation. This guidance reflects the current understanding of how truck loading operations work and how it generates emissions, how it is monitored or tested, and what data are available for emissions determination, may change over time as the AQB continue scientific studies and as new information becomes available. The AQB welcome any data, information, or feedback that may improve our understanding of truck loading produced water emissions and thereby further improve determinations within the emissions inventory. The calculation methods represented are intended as an emissions calculation aid; alternate calculation methods may be equally acceptable if they are based upon, and adequately demonstrate, sound engineering assumptions or data. If you have a question regarding the acceptability of a given emissions determination method, contact the Permitting Section at 505-476-4300.



New Mexico Environment Department Air Quality Bureau Equipment Emissions Calculation Form

Date: Aug 26, 2021
Company Name: IACX Roswell LLC
Facility Name: Bitter Lake Compressor Station

Permit Number: NSR-NSR 0274 and P-C
Al# if Known: 14
Elevation (ft.): 3,500

Emission Unit ID: FUG-1 **Fill all green/blue boxes changing default values as appropriate.**

Fugitive Volatile Organic Compounds (VOC), Total HAPs (HAP), Benzene (CH6) & Hydrogen Sulfide (H2S) Emissions																				
					Uncontrolled Total								Controlled Total							
					VOC		Total HAP		CH ₆		H ₂ S		VOC		Total HAP		CH ₆		H ₂ S	
Service	%VOC	%HAP	%CH ₆	%H ₂ S	PPH	TPY	PPH	TPY	PPH	TPY	PPH	TPY	PPH	TPY	PPH	TPY	PPH	TPY	PPH	TPY
Gas	9.902%				0.06	0.27	0	0	0	0	0	0	0.006	0.027	0	0	0	0	0	0
Heavy Oil	100%				0.29	1.27	0	0	0	0	0	0	0.161	0.704	0	0	0	0	0	0
Light Oil	100%				0.41	1.78	0	0	0	0	0	0	0.042	0.182	0	0	0	0	0	0
Water/Oil	1%				0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
Totals					0.76	3.32	0	0	0	0	0	0	0.209	0.913	0	0	0	0	0	0

				Uncontrolled VOC, HAP & CH ₆ Emissions							Controlled VOC, HAP & CH ₆ Emissions						
Equipment Type	Service ^a	EF ^b PPH/Source	No. of Sources	VOC PPH	VOC TPY	HAP PPH	HAP TPY	CH ₆ PPH	CH ₆ TPY	Control Efficiency	VOC PPH	VOC TPY	HAP PPH	HAP TPY	CH ₆ PPH	CH ₆ TPY	
Valves	Gas	0.0099207	60	0.0589	0.258	0	0	0	0	9.9%	0.0058	0.0255	0	0	0	0	
	Heavy Oil	0.00001852	0	0	0	0	0	0	0	0%	0	0	0	0	0	0	
	Light Oil	0.0055115	0	0	0	0	0	0	0	0%	0	0	0	0	0	0	
	Water/Oil	0.00021605	0	0	0	0	0	0	0	0%	0	0	0	0	0	0	
Subtotals				0.0589	0.258	0	0	0	0		0.0058	0.0255	0	0	0	0	
Pump Seals	Gas	0.00529104	0	0	0	0	0	0	0	0%	0	0	0	0		0	
	Heavy Oil	0.0286598	10	0.2866	1.2553	0	0	0	0	56%	0.1605	0.703	0	0	0	0	
	Light Oil	0.0286598	4	0.1146	0.5019	0	0	0	0	22%	0.0252	0.1104	0	0	0	0	
	Water/Oil	0.00005291	4	0	0	0	0	0	0	22%	0	0	0	0	0	0	
Subtotals				0.4012	1.7572	0	0	0	0		0.1857	0.8134	0	0	0	0	
Connectors	Gas	0.00044092	20	0.0009	0.0039	0	0	0	0	9.9%	0.0001	0.0004	0	0	0	0	
	Heavy Oil	0.00001653	0	0	0	0	0	0	0	0%	0	0	0	0	0	0	
	Light Oil	0.00046297	15	0.0069	0.0302	0	0	0	0	75%	0.0052	0.0227	0	0	0	0	
	Water/Oil	0.00024251	5	0	0	0	0	0	0	25%	0	0	0	0	0	0	
Subtotals				0.0078	0.0341	0	0	0	0		0.0053	0.0231	0	0	0	0	
Flanges	Gas	0.00085979	20	0.0017	0.0074	0	0	0	0	9.9%	0.0002	0.0007	0	0	0	0	
	Heavy Oil	0.00000086	0	0	0	0	0	0	0	0%	0	0	0	0	0	0	
	Light Oil	0.00024251	20	0.0049	0.0215	0	0	0	0	100%	0.0049	0.0215	0	0	0	0	
	Water/Oil	0.00000639	0	0	0	0	0	0	0	0%	0	0	0	0	0	0	
Subtotals				0.0066	0.0289	0	0	0	0		0.0051	0.0222	0	0	0	0	
Open Ends	Gas	0.0044092	0	0	0	0	0	0	0	0%	0	0	0	0	0	0	
	Heavy Oil	0.00030864	0	0	0	0	0	0	0	0%	0	0	0	0	0	0	
	Light Oil	0.00308644	0	0	0	0	0	0	0	0%	0	0	0	0	0	0	
	Water/Oil	0.00055115	0	0	0	0	0	0	0	0%	0	0	0	0	0	0	
Subtotals				0	0	0	0	0	0		0	0	0	0	0	0	
Other ^c	Gas	0.01940048	0	0	0	0	0	0	0	0%	0	0	0	0	0	0	
	Heavy Oil	0.00007055	58	0.0041	0.018	0	0	0	0	7.656%	0.0003	0.0014	0	0	0	0	
	Light Oil	0.0165345	17	0.2811	1.2312	0	0	0	0	2.244%	0.0063	0.0276	0	0	0	0	
	Water/Oil	0.0308644	0	0	0	0	0	0	0	0%	0	0	0	0	0	0	
Subtotals				0.2852	1.2492	0	0	0	0		0.0066	0.029	0	0	0	0	

Based on: 1995 Protocol for Equipment Leak Emission Estimates, Table 2.4 Version Date: 6/23/16; See next page for calculation notes.



New Mexico Environment Department Air Quality Bureau Emissions Calculation Forms

Calculation Tool for Fugitive Emissions Oil & Gas Production

Protocol for Equipment Leak Emission Estimates (EPA-453/R-95-017), Table 2-4;
available at the EPA Web site at <https://www3.epa.gov/ttn/chief/efdocs/equiplks.pdf>

a) Service categories are defined as follows:

- 1) Gas/vapor - material in a gaseous state at operating conditions;
- 2) Light liquid - material in a liquid state in which the sum of the concentration of individual constituents with a vapor pressure over 0.3 kilopascals (kPa) at 200C is greater than or equal to 20 weight percent;
- 3) Heavy liquid - not in gas/vapor service or light liquid service.
- 4) Water/Oil emission factors apply to water streams in oil service with a water content greater than 50%, from the point of origin to the point where the water content reaches 99%. For water streams with a water content greater than 99%, the emission rate is considered negligible.

b) These factors are for total organic compound emission rates (including non-VOC's such as methane and ethane) and apply to light crude, heavy crude, gas plant, gas production, and off shore facilities. "NA" indicates that not enough data were available to develop the indicated emission factor.

c) The "other" equipment type was derived from compressors, diaphragms, drains, dump arms, hatches, instruments, meters, pressure relief valves, polished rods, relief valves, and vents. This "other" equipment type should be applied for any equipment type other than connectors, flanges, open-ended lines, pumps, or valves.

d) Note that the average factors generally determine total hydrocarbon emissions. Therefore, you may need to multiply the calculated emission rates by the stream's weight percentage of VOC compounds to determine total VOC emissions. Please attach a copy of the appropriate gas and oil analysis with the stream's weight percentage of VOC compounds identified.

VOC Sample Calculation

For 10 Valves in Gas Service with a gas stream weight percentage of 25% VOC

Emission Factor (EF) $\text{lb/hr} = 0.0045 \text{ kg/hr} * 2.2046 \text{ lbs/kg}$

Gas Valves Uncontrolled Emissions

pph EF (Valves in Gas Service) * Number of Valves in Gas Service & VOC wt%

$$0.0099207 \text{ lb/hr} * 10 \text{ valves} = 0.099207 \text{ lb/hr} * 25\%/100$$

tpy EF (Valves in Gas Service) * Number of Valves in Gas Service * 8760 hrs/yr * 1ton/2000 lbs

$$0.0099207 \text{ lb/hr} * 10 \text{ valves} * 8760 \text{ hrs/yr} * 1/2000 \text{ ton/lbs} = 0.4345 \text{ tons/yr} * 25\%/100$$

Total Uncontrolled Fugitive Emissions for all Service types in Gas Service

pph (Uncontrolled pph Emissions for Valves + Pump Seals + Connectors + Flanges + Open Ends + Other) * VOC wt%/100

tpy (Uncontrolled tpy Emissions for Valves + Pump Seals + Connectors + Flanges + Open Ends + Other) * VOC wt%/100

Technical Disclaimer

This document is intended to help you accurately determine equipment leak fugitive emissions. It does not supersede or replace any state or federal law, rule, or regulation. This guidance reflects the current understanding of how piping components work and how they generate emissions, how they are monitored or tested, and what data are available for emissions determination, may change over time as we continue our scientific studies and as new information becomes available. We welcome any data, information, or feedback that may improve our understanding of equipment leak fugitive emissions and thereby further improve determinations within the emissions inventory. The calculation methods represented are intended as an emissions calculation aid; alternate calculation methods may be equally acceptable if they are based upon, and adequately demonstrate, sound engineering assumptions or data. If you have a question regarding the acceptability of a given emissions determination method, contact the Permitting Section at 505-476-4300.



New Mexico Environment Department Air Quality Bureau Equipment Emissions Calculation Form

Date:	Aug 26, 2021	Permit Number:	NSR-NSR 0274 and P-C
Company Name:	IACX Roswell LLC	Alt# if Known:	14
Facility Name:	Bitter Lake Compressor Station	Elevation (ft.):	3,500

Unpaved Haul Roads

Enter Information in all green boxes.

Haul Road Fugitive Emission Unit ID:

HR-1

% Silt

4.8

Mean Vehicle Weight (tons)

26.6

Rain Days

60

User % Control

0

**Haul Road Distance-Round-trip in Miles
(Only enter round-trip distance within
facility boundaries)**

0.08

Number of Haul Road Round-trips/hour

1

Number of Haul Road Round-trips/yr

4,380

Vehicle Miles Traveled/hr (VMT/hr)

0.08

Vehicle Miles Traveled/yr (VMT/yr)

350

Notes:

Hourly lbs/VMT			Annually lbs/VMT		
TSP	PM10	PM2.5	TSP	PM10	PM2.5
6.89	1.76	0.18	5.76	1.47	0.15

TSP/PM10/PM2.5 Emission Rates						
Control	TSP		PM10		PM2.5	
	lb/hr	tons/yr	lb/hr	tons/yr	lb/hr	tons/yr
Continuous	0.55	2.02	0.14	0.52	0.01	0.05
0% Control	0.55	1.01	0.14	0.26	0.01	0.03
User % Control	0.55	1.01	0.14	0.26	0.01	0.03

Footnote: All emissions based on AP-42, 13.2.2-4 (November 2006); See reverse side for calculation notes.



NMED-AQB Unpaved Haul Road Calculation Tool
All emission factors based on AP-42, AP-42 13.2.2-4; November 2006
<https://www3.epa.gov/ttn/chief/ap42/ch13/final/c13s0202.pdf>

Emissions from vehicles traveling on unpaved surfaces at industrial sites (based on 8760 Hours/year) can be estimated using the following expression:

AP-42 13.2.2-4; Equation 1a: **$E = k (s/12)^a (W/3)^b$**

where k, a, b, c and d are empirical constants (Reference 6) given below and

E = size-specific emission factor (lb/VMT)

s = surface material silt content (%)

W = mean vehicle weight (tons)

M = surface material moisture content (%)

Table 13.2.2-2. CONSTANTS FOR EQUATION 1a			
Constant	Industrial Roads (Equation 1a)		
	PM-2.5	PM-10	PM-30*
k (lb/VMT)	0.15	1.5	4.9
a	0.9	0.9	0.7
b	0.45	0.45	0.45
Quality Rating	B	B	B
*Assumed equivalent to total suspended particulate matter (TSP)			

Technical Disclaimer

This document is intended to help you accurately determine unpaved haul road emissions. It does not supersede or replace any state or federal law, rule, or regulation. This guidance reflects the current understanding of how unpaved haul roads work and how they generate emissions, how they are monitored or tested, and what data are available for emissions determination, may change over time as we continue our scientific studies and as new information becomes available. We welcome any data, information, or feedback that may improve our understanding of unpaved haul road emissions and thereby further improve determinations within the emissions inventory. The calculation methods represented are intended as an emissions calculation aid; alternate calculation methods may be equally acceptable if they are based upon, and adequately demonstrate, sound engineering assumptions or data. If you have a question regarding the acceptability of a given emissions determination method, contact the Permitting Section at 505-476-4300.



New Mexico Environment Department Air Quality Bureau Emissions Calculation Forms

Date:	Aug 26, 2021	Permit Number:	NSR 0274 and P-047
Company Name:	IACX Roswell LLC	Altitude (ft.):	3,500
Facility Name:	Bitter Lake Compressor Station	Altitude (ft.):	3,500

Total Requested Emissions For All Regulated Facility Equipment (NSR Request)																		
Emission Unit	NOx		CO		VOC		SOx		TSP		PM10		PM2.5		H2S		Total HAP	
	lb/hr	tons/yr	lb/hr	tons/yr	lb/hr	tons/yr	lb/hr	tons/yr	lb/hr	tons/yr	lb/hr	tons/yr	lb/hr	tons/yr	lb/hr	tons/yr	lb/hr	tons/yr
Engines	18.18	79.58	17.51	76.73	4.71	20.61	0.34	1.53	0.98	4.33	0.98	4.33	0.98	4.33	-	-	1.87	8.25
Heaters	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-	-		
Oil Tanks Flash	-	-	-	-	0.91	3.99	-	-	-	-	-	-	-	-				
Oil Tanks W & S	-	-	-	-	0.26	1.16	-	-	-	-	-	-	-	-				
Water Tks Flash	-	-	-	-			-	-	-	-	-	-	-	-				
Water Tks W & S	-	-	-	-			-	-	-	-	-	-	-	-				
Skim or Slop Tank	-	-	-	-			-	-	-	-	-	-	-	-				
GBS	-	-	-	-			-	-	-	-	-	-	-	-				
ECD	0	0	0	0	0	0	0	0										
VCU	0	0	0	0	0	0	0	0										
TO	0	0	0	0	0	0	0	0										
Flares	0	0	0	0	0	0	0	0										
Fugitives	-	-	-	-	0.76	3.32									0	0	0	0
SSM						10												
Malf.	-	-	-	-	-	10	-	-	-	-	-	-	-	-	-	-	-	-
Unpaved Haul Rds.	-	-	-	-	-	-	-	-	0.55	1.01	0.14	0.26	0.01	0.03	-	-	-	-
Paved Haul Rds.	-	-	-	-	-	-	-	-	0	0	0	0	0	0	-	-	0	0
Oil Load	-	-	-	-	0.68	0.12	-	-	-	-	-	-	-	-				
Water Loading	-	-	-	-	0.14	0.02	-	-	-	-	-	-	-	-				
Amine Unit	-	-	-	-	0	0	-	-	-	-	-	-	-	-	0	0	0	0
Amine Reb	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-	-		
Dehy Unit	-	-	-	-	0.41	1.81	-	-	-	-	-	-	-	-			0.07	0.33
Dehy Reb.	0.15	0.65	0.12	0.54	0.01	0.04	0	0	0.01	0.05	0.01	0.05	0.01	0.05	-	-		
Totals	18.33	80.23	17.63	77.27	7.88	51.07	0.34	1.53	1.54	5.39	1.13	4.64	1	4.41	0	0	1.94	8.58

Section 6.a

Green House Gas Emissions

(Submitting under 20.2.70, 20.2.72 20.2.74 NMAC)

Title V (20.2.70 NMAC), Minor NSR (20.2.72 NMAC), and PSD (20.2.74 NMAC) applicants must estimate and report greenhouse gas (GHG) emissions to verify the emission rates reported in the public notice, determine applicability to 40 CFR 60 Subparts, and to evaluate Prevention of Significant Deterioration (PSD) applicability. GHG emissions that are subject to air permit regulations consist of the sum of an aggregate group of these six greenhouse gases: carbon dioxide (CO₂), nitrous oxide (N₂O), methane (CH₄), hydrofluorocarbons (HFCs), perfluorocarbons (PFCs), and sulfur hexafluoride (SF₆).

Calculating GHG Emissions:

1. Calculate the ton per year (tpy) GHG mass emissions and GHG CO₂e emissions from your facility.
2. GHG mass emissions are the sum of the total annual tons of greenhouse gases without adjusting with the global warming potentials (GWPs). GHG CO₂e emissions are the sum of the mass emissions of each individual GHG multiplied by its GWP found in Table A-1 in 40 CFR 98 Mandatory Greenhouse Gas Reporting.
3. Emissions from routine or predictable start up, shut down, and maintenance must be included.
4. Report GHG mass and GHG CO₂e emissions in Table 2-P of this application. Emissions are reported in **short** tons per year and represent each emission unit's Potential to Emit (PTE).
5. All Title V major sources, PSD major sources, and all power plants, whether major or not, must calculate and report GHG mass and CO₂e emissions for each unit in Table 2-P.
6. For minor source facilities that are not power plants, are not Title V, and are not PSD there are three options for reporting GHGs in Table 2-P: 1) report GHGs for each individual piece of equipment; 2) report all GHGs from a group of unit types, for example report all combustion source GHGs as a single unit and all venting GHGs as a second separate unit; 3) or check the following ☐ By checking this box, the applicant acknowledges the total CO₂e emissions are less than 75,000 tons per year.

Sources for Calculating GHG Emissions:

- Manufacturer's Data
- AP-42 Compilation of Air Pollutant Emission Factors at <http://www.epa.gov/ttn/chief/ap42/index.html>
- EPA's Internet emission factor database WebFIRE at <http://cfpub.epa.gov/webfire/>
- 40 CFR 98 Mandatory Green House Gas Reporting except that tons should be reported in short tons rather than in metric tons for the purpose of PSD applicability.
- API Compendium of Greenhouse Gas Emissions Methodologies for the Oil and Natural Gas Industry. August 2009 or most recent version.
- Sources listed on EPA's NSR Resources for Estimating GHG Emissions at <http://www.epa.gov/nsr/clean-air-act-permitting-greenhouse-gases>:

Global Warming Potentials (GWP):

Applicants must use the Global Warming Potentials codified in Table A-1 of the most recent version of 40 CFR 98 Mandatory Greenhouse Gas Reporting. The GWP for a particular GHG is the ratio of heat trapped by one unit mass of the GHG to that of one unit mass of CO₂ over a specified time period.

"Greenhouse gas" for the purpose of air permit regulations is defined as the aggregate group of the following six gases: carbon dioxide, nitrous oxide, methane, hydrofluorocarbons, perfluorocarbons, and sulfur hexafluoride. **(20.2.70.7 NMAC, 20.2.74.7 NMAC)**. You may also find GHGs defined in 40 CFR 86.1818-12(a).

Metric to Short Ton Conversion:

Short tons for GHGs and other regulated pollutants are the standard unit of measure for PSD and title V permitting programs. 40 CFR 98 Mandatory Greenhouse Reporting requires metric tons.

1 metric ton = 1.10231 short tons (per Table A-2 to Subpart A of Part 98 – Units of Measure Conversions)

Section 7

Information Used To Determine Emissions

Information Used to Determine Emissions shall include the following:

- ☒ X If manufacturer data are used, include specifications for emissions units and control equipment, including control efficiencies specifications and sufficient engineering data for verification of control equipment operation, including design drawings, test reports, and design parameters that affect normal operation.
 - ☐ □ If test data are used, include a copy of the complete test report. If the test data are for an emissions unit other than the one being permitted, the emission units must be identical. Test data may not be used if any difference in operating conditions of the unit being permitted and the unit represented in the test report significantly effect emission rates.
 - ☒ X If the most current copy of AP-42 is used, reference the section and date located at the bottom of the page. Include a copy of the page containing the emissions factors, and clearly mark the factors used in the calculations.
 - ☐ □ If an older version of AP-42 is used, include a complete copy of the section.
 - ☐ □ If an EPA document or other material is referenced, include a complete copy.
 - ☐ □ Fuel specifications sheet.
 - ☒ X If computer models are used to estimate emissions, include an input summary (if available) and a detailed report, and a disk containing the input file(s) used to run the model. For tank-flashing emissions, include a discussion of the method used to estimate tank-flashing emissions, relative thresholds (i.e., permit or major source (NSPS, PSD or Title V)), accuracy of the model, the input and output from simulation models and software, all calculations, documentation of any assumptions used, descriptions of sampling methods and conditions, copies of any lab sample analysis.
-

TABLE 3.2-1 UNCONTROLLED EMISSION FACTORS FOR 2-STROKE LEAN-BURN ENGINES^a
(SCC 2-02-002-52)

Pollutant	Emission Factor (lb/MMBtu) ^b (fuel input)	Emission Factor Rating
Criteria Pollutants and Greenhouse Gases		
NO _x ^c 90 - 105% Load	3.17 E+00	A
NO _x ^c <90% Load	1.94 E+00	A
CO ^c 90 - 105% Load	3.86 E-01	A
CO ^c <90% Load	3.53 E-01	A
CO ₂ ^d	1.10 E+02	A
SO ₂ ^e	5.88 E-04	A
TOC ^f	1.64 E+00	A
Methane ^g	1.45 E+00	C
VOC ^h	1.20 E-01	C
PM10 (filterable) ⁱ	3.84 E-02	C
PM2.5 (filterable) ⁱ	3.84 E-02	C
PM Condensable ^j	9.91 E-03	E
Trace Organic Compounds		
1,1,2,2-Tetrachloroethane ^k	6.63 E-05	C
1,1,2-Trichloroethane ^k	5.27 E-05	C
1,1-Dichloroethane	3.91 E-05	C
1,2,3-Trimethylbenzene	3.54 E-05	D
1,2,4-Trimethylbenzene	1.11 E-04	C
1,2-Dichloroethane	4.22 E-05	D
1,2-Dichloropropane	4.46 E-05	C
1,3,5-Trimethylbenzene	1.80 E-05	D
1,3-Butadiene ^k	8.20 E-04	D
1,3-Dichloropropene ^k	4.38 E-05	C
2,2,4-Trimethylpentane ^k	8.46 E-04	B
2-Methylnaphthalene ^k	2.14 E-05	C
Acenaphthene ^k	1.33 E-06	C

Table 3.2-1. UNCONTROLLED EMISSION FACTORS FOR 2-STROKE LEAN-BURN ENGINES

(Continued)

Pollutant	Emission Factor (lb/MMBtu) ^b (fuel input)	Emission Factor Rating
Acenaphthylene ^k	3.17 E-06	C
Acetaldehyde ^{k,l}	7.76 E-03	A
Acrolein ^{k,l}	7.78 E-03	A
Anthracene ^k	7.18 E-07	C
Benz(a)anthracene ^k	3.36 E-07	C
Benzene ^k	1.94 E-03	A
Benzo(a)pyrene ^k	5.68 E-09	D
Benzo(b)fluoranthene ^k	8.51 E-09	D
Benzo(e)pyrene ^k	2.34 E-08	D
Benzo(g,h,i)perylene ^k	2.48 E-08	D
Benzo(k)fluoranthene ^k	4.26 E-09	D
Biphenyl ^k	3.95 E-06	C
Butane	4.75 E-03	C
Butyr/Isobutyraldehyde	4.37 E-04	C
Carbon Tetrachloride ^k	6.07 E-05	C
Chlorobenzene ^k	4.44 E-05	C
Chloroform ^k	4.71 E-05	C
Chrysene ^k	6.72 E-07	C
Cyclohexane	3.08 E-04	C
Cyclopentane	9.47 E-05	C
Ethane	7.09 E-02	A
Ethylbenzene ^k	1.08 E-04	B
Ethylene Dibromide ^k	7.34 E-05	C
Fluoranthene ^k	3.61 E-07	C
Fluorene ^k	1.69 E-06	C
Formaldehyde ^{k,l}	5.52 E-02	A

Table 3.2-1. UNCONTROLLED EMISSION FACTORS FOR 2-STROKE LEAN-BURN ENGINES
(Concluded)

Pollutant	Emission Factor (lb/MMBtu) ^b (fuel input)	Emission Factor Rating
Indeno(1,2,3-c,d)pyrene ^k	9.93 E-09	D
Isobutane	3.75 E-03	C
Methanol ^k	2.48 E-03	A
Methylcyclohexane	3.38 E-04	C
Methylene Chloride ^k	1.47 E-04	C
n-Hexane ^k	4.45 E-04	C
n-Nonane	3.08 E-05	C
n-Octane	7.44 E-05	C
n-Pentane	1.53 E-03	C
Naphthalene ^k	9.63 E-05	C
PAH ^k	1.34 E-04	D
Perylene ^k	4.97 E-09	D
Phenanthrene ^k	3.53 E-06	C
Phenol ^k	4.21 E-05	C
Propane	2.87 E-02	C
Pyrene ^k	5.84 E-07	C
Styrene ^k	5.48 E-05	A
Toluene ^k	9.63 E-04	A
Vinyl Chloride ^k	2.47 E-05	C
Xylene ^k	2.68 E-04	A

^a Reference 7. Factors represent uncontrolled levels. For NO_x, CO, and PM₁₀, “uncontrolled” means no combustion or add-on controls; however, the factor may include turbocharged units. For all other pollutants, “uncontrolled” means no oxidation control; the data set may include units with control techniques used for NO_x control, such as PCC and SCR for lean burn engines, and PSC for rich burn engines. Factors are based on large population of engines. Factors are for engines at all loads, except as indicated. SCC = Source Classification Code. TOC = Total Organic Compounds. PM₁₀ = Particulate Matter ≤ 10 microns (μm) aerodynamic diameter. A “<” sign in front of a factor means that the corresponding emission factor is based on one-half of the method detection limit.

^b Emission factors were calculated in units of (lb/MMBtu) based on procedures in EPA

Table 3.2-2. UNCONTROLLED EMISSION FACTORS FOR 4-STROKE LEAN-BURN ENGINES^a
(SCC 2-02-002-54)

Pollutant	Emission Factor (lb/MMBtu) ^b (fuel input)	Emission Factor Rating
Criteria Pollutants and Greenhouse Gases		
NO _x ^c 90 - 105% Load	4.08 E+00	B
NO _x ^c <90% Load	8.47 E-01	B
CO ^c 90 - 105% Load	3.17 E-01	C
CO ^c <90% Load	5.57 E-01	B
CO ₂ ^d	1.10 E+02	A
SO ₂ ^e	5.88 E-04	A
TOC ^f	1.47 E+00	A
Methane ^g	1.25 E+00	C
VOC ^h	1.18 E-01	C
PM10 (filterable) ⁱ	7.71 E-05	D
PM2.5 (filterable) ⁱ	7.71 E-05	D
PM Condensable ^j	9.91 E-03	D
Trace Organic Compounds		
1,1,2,2-Tetrachloroethane ^k	<4.00 E-05	E
1,1,2-Trichloroethane ^k	<3.18 E-05	E
1,1-Dichloroethane	<2.36 E-05	E
1,2,3-Trimethylbenzene	2.30 E-05	D
1,2,4-Trimethylbenzene	1.43 E-05	C
1,2-Dichloroethane	<2.36 E-05	E
1,2-Dichloropropane	<2.69 E-05	E
1,3,5-Trimethylbenzene	3.38 E-05	D
1,3-Butadiene ^k	2.67E-04	D
1,3-Dichloropropene ^k	<2.64 E-05	E
2-Methylnaphthalene ^k	3.32 E-05	C
2,2,4-Trimethylpentane ^k	2.50 E-04	C
Acenaphthene ^k	1.25 E-06	C

Table 3.2-2. UNCONTROLLED EMISSION FACTORS FOR 4-STROKE LEAN-BURN ENGINES
(Continued)

Pollutant	Emission Factor (lb/MMBtu) ^b (fuel input)	Emission Factor Rating
Acenaphthylene ^k	5.53 E-06	C
Acetaldehyde ^{k,l}	8.36 E-03	A
Acrolein ^{k,l}	5.14 E-03	A
Benzene ^k	4.40 E-04	A
Benzo(b)fluoranthene ^k	1.66 E-07	D
Benzo(e)pyrene ^k	4.15 E-07	D
Benzo(g,h,i)perylene ^k	4.14 E-07	D
Biphenyl ^k	2.12 E-04	D
Butane	5.41 E-04	D
Butyr/Isobutyraldehyde	1.01 E-04	C
Carbon Tetrachloride ^k	<3.67 E-05	E
Chlorobenzene ^k	<3.04 E-05	E
Chloroethane	1.87 E-06	D
Chloroform ^k	<2.85 E-05	E
Chrysene ^k	6.93 E-07	C
Cyclopentane	2.27 E-04	C
Ethane	1.05 E-01	C
Ethylbenzene ^k	3.97 E-05	B
Ethylene Dibromide ^k	<4.43 E-05	E
Fluoranthene ^k	1.11 E-06	C
Fluorene ^k	5.67 E-06	C
Formaldehyde ^{k,l}	5.28 E-02	A
Methanol ^k	2.50 E-03	B
Methylcyclohexane	1.23 E-03	C
Methylene Chloride ^k	2.00 E-05	C
n-Hexane ^k	1.11 E-03	C
n-Nonane	1.10 E-04	C

Table 3.2-2. UNCONTROLLED EMISSION FACTORS FOR 4-STROKE LEAN-BURN
ENGINES
(Continued)

Pollutant	Emission Factor (lb/MMBtu) ^b (fuel input)	Emission Factor Rating
n-Octane	3.51 E-04	C
n-Pentane	2.60 E-03	C
Naphthalene ^k	7.44 E-05	C
PAH ^k	2.69 E-05	D
Phenanthrene ^k	1.04 E-05	D
Phenol ^k	2.40 E-05	D
Propane	4.19 E-02	C
Pyrene ^k	1.36 E-06	C
Styrene ^k	<2.36 E-05	E
Tetrachloroethane ^k	2.48 E-06	D
Toluene ^k	4.08 E-04	B
Vinyl Chloride ^k	1.49 E-05	C
Xylene ^k	1.84 E-04	B

^a Reference 7. Factors represent uncontrolled levels. For NO_x, CO, and PM₁₀, “uncontrolled” means no combustion or add-on controls; however, the factor may include turbocharged units. For all other pollutants, “uncontrolled” means no oxidation control; the data set may include units with control techniques used for NO_x control, such as PCC and SCR for lean burn engines, and PSC for rich burn engines. Factors are based on large population of engines. Factors are for engines at all loads, except as indicated. SCC = Source Classification Code. TOC = Total Organic Compounds. PM-10 = Particulate Matter ≤ 10 microns (μm) aerodynamic diameter. A “<” sign in front of a factor means that the corresponding emission factor is based on one-half of the method detection limit.

^b Emission factors were calculated in units of (lb/MMBtu) based on procedures in EPA Method 19. To convert from (lb/MMBtu) to (lb/10⁶ scf), multiply by the heat content of the fuel. If the heat content is not available, use 1020 Btu/scf. To convert from (lb/MMBtu) to (lb/hp-hr) use the following equation:

$$\text{lb/hp-hr} = (\text{lb/MMBtu}) (\text{heat input, MMBtu/hr}) (1/\text{operating HP, 1/hp})$$

^c Emission tests with unreported load conditions were not included in the data set.

^d Based on 99.5% conversion of the fuel carbon to CO₂. CO₂ [lb/MMBtu] = (3.67)(%CON)(C)(D)(1/h), where %CON = percent conversion of fuel carbon to CO₂, C = carbon content of fuel by weight (0.75), D = density of fuel, 4.1 E+04 lb/10⁶ scf, and

Table 1.4-1. EMISSION FACTORS FOR NITROGEN OXIDES (NO_x) AND CARBON MONOXIDE (CO)
FROM NATURAL GAS COMBUSTION^a

Combustor Type (MMBtu/hr Heat Input) [SCC]	NO _x ^b		CO	
	Emission Factor (lb/10 ⁶ scf)	Emission Factor Rating	Emission Factor (lb/10 ⁶ scf)	Emission Factor Rating
Large Wall-Fired Boilers (>100) [1-01-006-01, 1-02-006-01, 1-03-006-01]				
Uncontrolled (Pre-NSPS) ^c	280	A	84	B
Uncontrolled (Post-NSPS) ^c	190	A	84	B
Controlled - Low NO _x burners	140	A	84	B
Controlled - Flue gas recirculation	100	D	84	B
Small Boilers (<100) [1-01-006-02, 1-02-006-02, 1-03-006-02, 1-03-006-03]				
Uncontrolled	100	B	84	B
Controlled - Low NO _x burners	50	D	84	B
Controlled - Low NO _x burners/Flue gas recirculation	32	C	84	B
Tangential-Fired Boilers (All Sizes) [1-01-006-04]				
Uncontrolled	170	A	24	C
Controlled - Flue gas recirculation	76	D	98	D
Residential Furnaces (<0.3) [No SCC]				
Uncontrolled	94	B	40	B

^a Reference 11. Units are in pounds of pollutant per million standard cubic feet of natural gas fired. To convert from lb/10⁶ scf to kg/10⁶ m³, multiply by 16. Emission factors are based on an average natural gas higher heating value of 1,020 Btu/scf. To convert from lb/10⁶ scf to lb/MMBtu, divide by 1,020. The emission factors in this table may be converted to other natural gas heating values by multiplying the given emission factor by the ratio of the specified heating value to this average heating value. SCC = Source Classification Code. ND = no data. NA = not applicable.

^b Expressed as NO₂. For large and small wall fired boilers with SNCR control, apply a 24 percent reduction to the appropriate NO_x emission factor. For tangential-fired boilers with SNCR control, apply a 13 percent reduction to the appropriate NO_x emission factor.

^c NSPS=New Source Performance Standard as defined in 40 CFR 60 Subparts D and Db. Post-NSPS units are boilers with greater than 250 MMBtu/hr of heat input that commenced construction modification, or reconstruction after August 17, 1971, and units with heat input capacities between 100 and 250 MMBtu/hr that commenced construction modification, or reconstruction after June 19, 1984.

TABLE 1.4-2. EMISSION FACTORS FOR CRITERIA POLLUTANTS AND GREENHOUSE GASES FROM NATURAL GAS COMBUSTION^a

Pollutant	Emission Factor (lb/10 ⁶ scf)	Emission Factor Rating
CO ₂ ^b	120,000	A
Lead	0.0005	D
N ₂ O (Uncontrolled)	2.2	E
N ₂ O (Controlled-low-NO _x burner)	0.64	E
PM (Total) ^c	7.6	D
PM (Condensable) ^c	5.7	D
PM (Filterable) ^c	1.9	B
SO ₂ ^d	0.6	A
TOC	11	B
Methane	2.3	B
VOC	5.5	C

^a Reference 11. Units are in pounds of pollutant per million standard cubic feet of natural gas fired. Data are for all natural gas combustion sources. To convert from lb/10⁶ scf to kg/10⁶ m³, multiply by 16. To convert from lb/10⁶ scf to lb/MMBtu, divide by 1,020. The emission factors in this table may be converted to other natural gas heating values by multiplying the given emission factor by the ratio of the specified heating value to this average heating value. TOC = Total Organic Compounds.

VOC = Volatile Organic Compounds.

^b Based on approximately 100% conversion of fuel carbon to CO₂. CO₂[lb/10⁶ scf] = (3.67) (CON) (C)(D), where CON = fractional conversion of fuel carbon to CO₂, C = carbon content of fuel by weight (0.76), and D = density of fuel, 4.2x10⁴ lb/10⁶ scf.

^c All PM (total, condensable, and filterable) is assumed to be less than 1.0 micrometer in diameter. Therefore, the PM emission factors presented here may be used to estimate PM₁₀, PM_{2.5} or PM₁ emissions. Total PM is the sum of the filterable PM and condensable PM. Condensable PM is the particulate matter collected using EPA Method 202 (or equivalent). Filterable PM is the particulate matter collected on, or prior to, the filter of an EPA Method 5 (or equivalent) sampling train.

^d Based on 100% conversion of fuel sulfur to SO₂.

Assumes sulfur content is natural gas of 2,000 grains/10⁶ scf. The SO₂ emission factor in this table can be converted to other natural gas sulfur contents by multiplying the SO₂ emission factor by the ratio of the site-specific sulfur content (grains/10⁶ scf) to 2,000 grains/10⁶ scf.

TABLE 1.4-3. EMISSION FACTORS FOR SPECIATED ORGANIC COMPOUNDS FROM
NATURAL GAS COMBUSTION^a

CAS No.	Pollutant	Emission Factor (lb/10 ⁶ scf)	Emission Factor Rating
91-57-6	2-Methylnaphthalene ^{b, c}	2.4E-05	D
56-49-5	3-Methylcholanthrene ^{b, c}	<1.8E-06	E
	7,12-Dimethylbenz(a)anthracene ^{b, c}	<1.6E-05	E
83-32-9	Acenaphthene ^{b, c}	<1.8E-06	E
203-96-8	Acenaphthylene ^{b, c}	<1.8E-06	E
120-12-7	Anthracene ^{b, c}	<2.4E-06	E
56-55-3	Benz(a)anthracene ^{b, c}	<1.8E-06	E
71-43-2	Benzene ^b	2.1E-03	B
50-32-8	Benzo(a)pyrene ^{b, c}	<1.2E-06	E
205-99-2	Benzo(b)fluoranthene ^{b, c}	<1.8E-06	E
191-24-2	Benzo(g,h,i)perylene ^{b, c}	<1.2E-06	E
207-08-9	Benzo(k)fluoranthene ^{b, c}	<1.8E-06	E
106-97-8	Butane	2.1E+00	E
218-01-9	Chrysene ^{b, c}	<1.8E-06	E
53-70-3	Dibenzo(a,h)anthracene ^{b, c}	<1.2E-06	E
25321-22-6	Dichlorobenzene ^b	1.2E-03	E
74-84-0	Ethane	3.1E+00	E
206-44-0	Fluoranthene ^{b, c}	3.0E-06	E
86-73-7	Fluorene ^{b, c}	2.8E-06	E
50-00-0	Formaldehyde ^b	7.5E-02	B
110-54-3	Hexane ^b	1.8E+00	E
193-39-5	Indeno(1,2,3-cd)pyrene ^{b, c}	<1.8E-06	E
91-20-3	Naphthalene ^b	6.1E-04	E
109-66-0	Pentane	2.6E+00	E
85-01-8	Phenanthrene ^{b, c}	1.7E-05	D
74-98-6	Propane	1.6E+00	E

TABLE 1.4-3. EMISSION FACTORS FOR SPECIATED ORGANIC COMPOUNDS FROM
NATURAL GAS COMBUSTION (Continued)

CAS No.	Pollutant	Emission Factor (lb/10 ⁶ scf)	Emission Factor Rating
129-00-0	Pyrene ^{b, c}	5.0E-06	E
108-88-3	Toluene ^b	3.4E-03	C

^a Reference 11. Units are in pounds of pollutant per million standard cubic feet of natural gas fired. Data are for all natural gas combustion sources. To convert from lb/10⁶ scf to kg/10⁶ m³, multiply by 16. To convert from lb/10⁶ scf to lb/MMBtu, divide by 1,020. Emission Factors preceded with a less-than symbol are based on method detection limits.

^b Hazardous Air Pollutant (HAP) as defined by Section 112(b) of the Clean Air Act.

^c HAP because it is Polycyclic Organic Matter (POM). POM is a HAP as defined by Section 112(b) of the Clean Air Act.

^d The sum of individual organic compounds may exceed the VOC and TOC emission factors due to differences in test methods and the availability of test data for each pollutant.

where:

L_T = transit loss from ships and barges, lb/week-10³ gal transported
 P = true vapor pressure of the transported liquid, psia
 W = density of the condensed vapors, lb/gal

Emissions from gasoline truck cargo tanks during transit have been studied by a combination of theoretical and experimental techniques, and typical emission values are presented in Table 5.2-5.¹¹⁻¹² Emissions depend on the extent of venting from the cargo tank during transit, which in turn depends on the vapor tightness of the tank, the pressure relief valve settings, the pressure in the tank at the start of the trip, the vapor pressure of the fuel being transported, and the degree of fuel vapor saturation of the space in the tank. The emissions are not directly proportional to the time spent in transit. If the vapor leakage rate of the tank increases, emissions increase up to a point, and then the rate changes as other determining factors take over. Truck tanks in dedicated vapor balance service usually contain saturated vapors, and this leads to lower emissions during transit because no additional fuel evaporates to raise the pressure in the tank to cause venting. Table 5.2-5 lists "typical" values for transit emissions and "extreme" values that could occur in the unlikely event that all determining factors combined to cause maximum emissions.

Table 5.2-5 (Metric And English Units). TOTAL UNCONTROLLED ORGANIC EMISSION FACTORS FOR PETROLEUM LIQUID RAIL TANK CARS AND TANK TRUCKS

Emission Source	Gasoline ^a	Crude Oil ^b	Jet Naphtha (JP-4)	Jet Kerosene	Distillate Oil No. 2	Residual Oil No. 6
Loading operations ^c						
Submerged loading - Dedicated normal service ^d						
mg/L transferred	590	240	180	1.9	1.7	0.01
lb/10 ³ gal transferred	5	2	1.5	0.016	0.014	0.0001
Submerged loading - Vapor balance service ^d						
mg/L transferred	980	400	300	— ^e	— ^e	— ^e
lb/10 ³ gal transferred	8	3	2.5	— ^e	— ^e	— ^e
Splash loading - Dedicated normal service						
mg/L transferred	1,430	580	430	5	4	0.03
lb/10 ³ gal transferred	12	5	4	0.04	0.03	0.0003
Splash loading - Vapor balance service						
mg/L transferred	980	400	300	— ^e	— ^e	— ^e
lb/10 ³ gal transferred	8	3	2.5	— ^e	— ^e	— ^e

Table 5.2-5 (cont.).

Emission Source	Gasoline ^a	Crude Oil ^b	Jet Naphtha (JP-4)	Jet Kerosene	Distillate Oil No. 2	Residual Oil No. 6
Transit losses						
Loaded with product						
mg/L transported						
Typical	0 - 1.0	ND	ND	ND	ND	ND
Extreme	0 - 9.0	ND	ND	ND	ND	ND
lb/10 ³ gal transported						
Typical	0 - 0.01	ND	ND	ND	ND	ND
Extreme	0 - 0.08	ND	ND	ND	ND	ND
Return with vapor						
mg/L transported						
Typical	0 - 13.0	ND	ND	ND	ND	ND
Extreme	0 - 44.0	ND	ND	ND	ND	ND
lb/10 ³ gal transported						
Typical	0 - 0.11	ND	ND	ND	ND	ND
Extreme	0 - 0.37	ND	ND	ND	ND	ND

^a Reference 2. Gasoline factors represent emissions of VOC as well as total organics, because methane and ethane constitute a negligible weight fraction of the evaporative emissions from gasoline. VOC factors for crude oil can be assumed to be 15% lower than the total organic factors, to account for the methane and ethane content of crude oil evaporative emissions. All other products should be assumed to have VOC factors equal to total organics. The example gasoline has an RVP of 69 kPa (10 psia). ND = no data.

^b The example crude oil has an RVP of 34 kPa (5 psia).

^c Loading emission factors are calculated using Equation 1 for a dispensed product temperature of 16°C (60°F).

^d Reference 2.

^e Not normally used.

In the absence of specific inputs for Equations 1 through 5, the typical evaporative emission factors presented in Tables 5.2-5 and 5.2-6 should be used. It should be noted that, although the crude oil used to calculate the emission values presented in these tables has an RVP of 5, the RVP of crude oils can range from less than 1 up to 10. Similarly, the RVP of gasolines ranges from 7 to 13. In areas where loading and transportation sources are major factors affecting air quality, it is advisable to obtain the necessary parameters and to calculate emission estimates using Equations 1 through 5.

5.2.2.2 Service Stations -

Another major source of evaporative emissions is the filling of underground gasoline storage tanks at service stations. Gasoline is usually delivered to service stations in 30,000-liter (8,000-gal) tank trucks or smaller account trucks. Emissions are generated when gasoline vapors in the underground storage tank are displaced to the atmosphere by the gasoline being loaded into the tank. As with other loading losses, the quantity of loss in service station tank filling depends on several variables, including the method and rate of filling, the tank configuration, and the gasoline temperature, vapor pressure and composition. An average emission rate for submerged filling is 880 mg/L (7.3 lb/1000 gal) of transferred gasoline, and the rate for splash filling is 1380 mg/L (11.5 lb/1000 gal) transferred gasoline (see Table 5.2-7).⁵

as shown in Table 13.2.2-4

Table 13.2.2-4. EMISSION FACTOR FOR 1980'S VEHICLE FLEET
EXHAUST, BRAKE WEAR AND TIRE WEAR

Particle Size Range ^a	C, Emission Factor for Exhaust, Brake Wear and Tire Wear ^b lb/VMT
PM _{2.5}	0.00036
PM ₁₀	0.00047
PM ₃₀ ^c	0.00047

^a Refers to airborne particulate matter (PM-x) with an aerodynamic diameter equal to or less than x micrometers.

^b Units shown are pounds per vehicle mile traveled (lb/VMT).

^c PM-30 is sometimes termed "suspendable particulate" (SP) and is often used as a surrogate for TSP.

It is important to note that the vehicle-related source conditions refer to the average weight, speed, and number of wheels for all vehicles traveling the road. For example, if 98 percent of traffic on the road are 2-ton cars and trucks while the remaining 2 percent consists of 20-ton trucks, then the mean weight is 2.4 tons. More specifically, Equations 1a and 1b are *not* intended to be used to calculate a separate emission factor for each vehicle class within a mix of traffic on a given unpaved road. That is, in the example, one should *not* determine one factor for the 2-ton vehicles and a second factor for the 20-ton trucks. Instead, only one emission factor should be calculated that represents the "fleet" average of 2.4 tons for all vehicles traveling the road.

Moreover, to retain the quality ratings when addressing a group of unpaved roads, it is necessary that reliable correction parameter values be determined for the road in question. The field and laboratory procedures for determining road surface silt and moisture contents are given in AP-42 Appendices C.1 and C.2. Vehicle-related parameters should be developed by recording visual observations of traffic. In some cases, vehicle parameters for industrial unpaved roads can be determined by reviewing maintenance records or other information sources at the facility.

In the event that site-specific values for correction parameters cannot be obtained, then default values may be used. In the absence of site-specific silt content information, an appropriate mean value from Table 13.2.2-1 may be used as a default value, but the quality rating of the equation is reduced by two letters. Because of significant differences found between different types of road surfaces and between different areas of the country, use of the default moisture content value of 0.5 percent in Equation 1b is discouraged. The quality rating should be downgraded two letters when the default moisture content value is used. (It is assumed that readers addressing industrial roads have access to the information needed to develop average vehicle information in Equation 1a for their facility.)

The effect of routine watering to control emissions from unpaved roads is discussed below in Section 13.2.2.3, "Controls". However, all roads are subject to some natural mitigation because of rainfall and other precipitation. The Equation 1a and 1b emission factors can be extrapolated to annual

G3408C

NON-CURRENT

GAS ENGINE SITE SPECIFIC TECHNICAL DATA

CATERPILLAR®

GAS COMPRESSION APPLICATION

IACX

ENGINE SPEED (rpm): 1800
COMPRESSION RATIO: 8.5
AFTERCOOLER TYPE: SCAC
AFTERCOOLER WATER INLET (°F): 130
JACKET WATER OUTLET (°F): 210
ASPIRATION: TA
COOLING SYSTEM: JW+OC, AC
CONTROL SYSTEM: EIS
EXHAUST MANIFOLD: WC
COMBUSTION: LOW EMISSION
NOx EMISSION LEVEL (g/bhp-hr NOx): 1.0
SET POINT TIMING: 34

RATING STRATEGY:
RATING LEVEL:
FUEL SYSTEM:

SITE CONDITIONS:
FUEL: Field Gas
FUEL PRESSURE RANGE (psig): (See note 1) 1.5-5.0
FUEL METHANE NUMBER: 62.1
FUEL LHV (Btu/scf): 1027
ALTITUDE (ft): 2500
INLET AIR TEMPERATURE (°F): 77
STANDARD RATED POWER: 425 bhp@1800rpm

				MAXIMUM RATING	SITE RATING AT MAXIMUM INLET AIR TEMPERATURE		
RATING		NOTES	LOAD	100%	100%	75%	50%
ENGINE POWER (WITHOUT FAN)		(2)	bhp	425	425	319	213
INLET AIR TEMPERATURE			°F	77	77	77	77
ENGINE DATA							
FUEL CONSUMPTION (LHV)		(3)	Btu/bhp-hr	7995	7995	8302	8947
FUEL CONSUMPTION (HHV)		(3)	Btu/bhp-hr	8834	8834	9174	9886
AIR FLOW (@inlet air temp, 14.7 psia)		(4)(5)	ft3/min	953	953	724	515
AIR FLOW (WET)		(4)(5)	lb/hr	4227	4227	3211	2285
FUEL FLOW (60°F, 14.7 psia)			scfm	55	55	43	31
INLET MANIFOLD PRESSURE		(6)	In Hg(abs)	66.7	66.7	51.6	37.0
EXHAUST TEMPERATURE - ENGINE OUTLET		(7)	°F	880	880	827	794
EXHAUST GAS FLOW (@engine outlet temp, 14.5 psia)		(8)(5)	ft3/min	2570	2570	1879	1303
EXHAUST GAS MASS FLOW (WET)		(8)(5)	lb/hr	4391	4391	3338	2376
EMISSIONS DATA - ENGINE OUT							
NOx (as NO2)		(9)(10)	g/bhp-hr	1.00	1.00	1.00	1.00
CO		(9)(10)	g/bhp-hr	1.84	1.84	1.96	2.19
THC (mol. wt. of 15.84)		(9)(10)	g/bhp-hr	3.03	3.03	3.46	3.96
NMHC (mol. wt. of 15.84)		(9)(10)	g/bhp-hr	0.79	0.79	0.90	1.03
NMNEHC (VOCs) (mol. wt. of 15.84)		(9)(10)(11)	g/bhp-hr	0.53	0.53	0.60	0.69
HCHO (Formaldehyde)		(9)(10)	g/bhp-hr	0.30	0.30	0.31	0.35
CO2		(9)(10)	g/bhp-hr	538	538	558	602
EXHAUST OXYGEN		(9)(12)	% DRY	8.0	8.0	7.8	7.4
HEAT REJECTION							
HEAT REJ. TO JACKET WATER (JW)		(13)	Btu/min	14743	14743	13123	10692
HEAT REJ. TO ATMOSPHERE		(13)	Btu/mln	2265	2265	1764	1267
HEAT REJ. TO LUBE OIL (OC)		(13)	Btu/min	2331	2331	2075	1691
HEAT REJ. TO AFTERCOOLER (AC)		(13)(14)	Btu/min	3283	3283	2153	1130
COOLING SYSTEM SIZING CRITERIA							
TOTAL JACKET WATER CIRCUIT (JW+OC)		(14)	Btu/min	19015			
TOTAL AFTERCOOLER CIRCUIT (AC)		(14)(15)	Btu/mln	3447			
A cooling system safety factor of 0% has been added to the cooling system sizing criteria.							

CONDITIONS AND DEFINITIONS

Engine rating obtained and presented in accordance with ISO 3046/1, adjusted for fuel, site altitude and site inlet air temperature. 100% rating at maximum inlet air temperature is the maximum engine capability for the specified fuel at site altitude and maximum site inlet air temperature. Maximum rating is the maximum capability at the specified aftercooler inlet temperature for the specified fuel at site altitude and reduced inlet air temperature. Lowest load point is the lowest continuous duty operating load allowed. No overload permitted at rating shown.

For notes information consult page three.

2.0 PERFORMANCE OVERVIEW SUMMARY

Results of the emissions test are summarized in Table 2-1 and Table 2-2 below; the site conditions are tabulated in Table 2-3: Test Conditions and Operational Data. Emissions rates and factors were calculated using the methods discussed in Section 6 – Emissions Calculations.

Table 2-1: Customer and Source Summary

TEST INFORMATION	
Test Prepared For	IACX Energy 5400 LBJ Freeway, Suite 460 Dallas, TX 75240
Responsible Contact	Russell Gibbs Phone: 575-363-3142 Email: russell@iacx.com
Test Location	Bitter Lake
Unit Number	C-891
Test Date	May 16, 2018
Source	Cooper Bessemer GMVH-10C
Source Serial Number	61569
Site Rated Horsepower	2250
Source Purpose	Compressor
Permit Number	P047R2M1
Hour Meter Reading	222248

Table 2-2: Test Results

TEST RESULTS AND UNIT OPERATIONAL DATA					
Parameter	Units	Average	Run 1	Run 2	Run 3
Fuel Consumption	(sft ³ /hr)	11,430.48	11,411.49	11,433.93	11,446.02
O2 Percentage	%	15.05	15.11	15.04	15.00
Adjusted O2 Percentage	%	15.08	15.12	15.07	15.05
Exhaust Flow Rate	(dsft ³ /hr)	455,258.36	433111.21	428784.89	426355.72
Engine Power	(bhp)	1,412.35	1,410.01	1,412.78	1,414.27
Engine Load	%	62.77	62.67	62.79	62.86
Speed	RPM	319.67	320.00	320.00	319.00
Parameter	Permitted	Average	Run 1	Run 2	Run 3
CO					
ppmvd		183.61	193.95	181.22	175.65
ppm at 15% O2		184.54	196.16	181.95	175.62
lb/MMBTU HHV		0.42	0.44	0.41	0.40
g/bhp-hr		1.95	2.08	1.93	1.86
lb/hr		6.08	6.45	6.00	5.79
ton/yr	39.00	26.63	28.26	26.27	25.38
NOx					
ppmvd		159.30	139.53	163.37	174.99
ppm at 15% O2		160.10	141.11	164.03	174.96
lb/MMBTU HHV		0.59	0.52	0.61	0.65
g/bhp-hr		2.78	2.45	2.85	3.04
lb/hr		8.66	7.62	8.88	9.48
ton/yr	87.60	37.95	33.39	38.89	41.53

Table 2-3: Test Conditions and Operational Data

TEST RUN TIMES					
		Run 1		Run 2	Run 3
Start Time		14:36:30		15:43:00	16:52:00
End Time		15:37:30		16:44:00	17:53:00
SITE CONDITIONS					
Parameter	Units	Average	Run 1	Run 2	Run 3
Ambient Temperature	F	93.00	91.00	93.00	95.00
Humidity	%	15.67	20.00	15.00	12.00
Barometric Pressure	"Hg	29.73	29.77	29.73	29.70
ENGINE DATA					
Ignition Timing	BTDC	3.00	3.00	3.00	3.00
Exhaust Temperature	°F	642.00	639.00	639.00	648.00
Manifold Pressure	PSIg	12.07	12.10	12.20	11.90
Speed	RPM	319.67	320.00	320.00	319.00
Intake Manifold Temp	°F	115.67	114.00	115.00	118.00

2.0 PERFORMANCE OVERVIEW SUMMARY

Results of the emissions test are summarized in Table 2-1 and Table 2-2 below; the site conditions are tabulated in Table 2-3: Test Conditions and Operational Data. Emissions rates and factors were calculated using the methods discussed in Section 6 – Emissions Calculations.

Table 2-1: Customer and Source Summary

TEST INFORMATION	
Test Prepared For	IACX Energy 5400 LBJ Freeway, Suite 460 Dallas, TX 75240
Responsible Contact	Russell Gibbs Phone: 575-363-3142 Email: russell@iacx.com
Test Location	Bitter Lake
Unit Number	C-893
Test Date	Jun 22, 2018
Source	Cooper Bessemer GMVH-10C
Source Serial Number	48776
Site Rated Horsepower	2250
Source Purpose	Compressor
Manufacture Date	Apr 07, 1981
Permit Number	P047R2M1
Hour Meter Reading	191471

Table 2-2: Test Results

TEST RESULTS AND UNIT OPERATIONAL DATA					
Parameter	Units	Average	Run 1	Run 2	Run 3
Fuel Consumption	(sft ³ /hr)	13,166.96	12,654.23	13,271.72	13,574.93
O2 Percentage	%	14.69	14.86	14.65	14.55
Adjusted O2 Percentage	%	14.76	14.90	14.74	14.65
Exhaust Flow Rate	(dsft ³ /hr)	412,637.62	403389.05	408928.27	411749.86
Engine Power	(bhp)	1,349.48	1,296.93	1,360.22	1,391.29
Engine Load	%	59.98	57.64	60.45	61.84
Speed	RPM	320.33	320.00	320.00	321.00
Parameter	Permitted	Average	Run 1	Run 2	Run 3
CO					
ppmvd		241.35	252.44	241.36	230.23
ppm at 15% O2		230.23	246.07	229.28	215.76
lb/MMBTU HHV		0.52	0.55	0.52	0.49
g/bhp-hr		2.44	2.60	2.43	2.28
lb/hr		7.24	7.44	7.27	7.00
ton/yr	39.00	31.73	32.61	31.86	30.67
NOx					
ppmvd		87.28	65.94	89.11	106.80
ppm at 15% O2		83.26	64.27	84.65	100.09
lb/MMBTU HHV		0.31	0.24	0.31	0.37
g/bhp-hr		1.45	1.12	1.47	1.74
lb/hr		4.30	3.19	4.41	5.34
ton/yr	87.60	18.85	13.99	19.32	23.37

Table 2-3: Test Conditions and Operational Data

TEST RUN TIMES					
		Run 1		Run 2	Run 3
Start Time		08:20:00		09:34:00	10:48:30
End Time		09:21:00		10:35:00	11:50:30
SITE CONDITIONS					
Parameter	Units	Average	Run 1	Run 2	Run 3
Ambient Temperature	F	90.67	86.00	91.00	95.00
Humidity	%	29.00	35.00	28.00	24.00
Barometric Pressure	"Hg	29.71	29.73	29.71	29.69
ENGINE DATA					
Ignition Timing	BTDC	2.87	3.20	2.70	2.70
Exhaust Temperature	°F	654.33	643.00	656.00	664.00
Manifold Pressure	PSIg	6.07	6.20	6.10	5.90
Speed	RPM	320.33	320.00	320.00	321.00
Intake Manifold Temp	°F	111.00	106.00	111.00	116.00



Athens, TX (903) 677-0700 . Beeville, TX (361) 354-5200 . Midland, TX (432) 704-5351

LIQUID EXTENDED ANALYSIS REPORT

LABORATORY REPORT NUMBER

190107-1020-12-010719-02

PHYSICAL CONSTANTS PER GPA 2145-09 & TP-17 (1998)

CUSTOMER :	IACX	DATE SAMPLED:	12/27/2018
STATION:	20126	DATE ANALYZED:	01/07/2019
PRODUCER:	IACX	EFFECTIVE DATE:	12/01/2018
LEASE:	BITTER LAKES		

<u>COMPONENT</u>	<u>MOLE %</u>	<u>LIQUID VOL %</u>	<u>WT. %</u>
H2S	0.000	0.000	0.000
OXYGEN	0.000	0.000	0.000
NITROGEN	0.031	0.009	0.011
CARBON DIOXIDE	0.000	0.000	0.000
METHANE	0.056	0.024	0.011
ETHANE	2.243	1.536	0.817
PROPANE	2.873	2.028	1.530
I-BUTANE	1.862	1.560	1.310
N-BUTANE	7.966	6.430	5.606
I-PENTANE	10.254	9.602	8.958
N-PENTANE	13.205	12.256	11.536
HEXANE PLUS	<u>61.510</u>	<u>66.555</u>	<u>70.221</u>
TOTAL	100.000	100.000	100.000

IDEAL SP. GRAVITY	0.6703	BTU / GAL	116007.20
MOL. WT.	82.588	VAPOR PRESS.	39.30
CUBIC FT / GAL	25.678	LBS / GAL	5.59
C1/C2 LV % RATIO	1.563	API GRAVITY	79.60
CO2/C2 LV % RATIO	0.000	SP GRAV AS VAPOR	2.85

SAMPLED BY DT
SAMPLE TYPE: SPOT
CYLINDER NO.: 5152
COMMENT: SPOT

SAMPLE PRESS:
SAMPLE TEMP:
COUNTY / STATE: 0
ANALYST MIKE HOBGOOD

* SEE NEXT PAGE FOR C6+ COMPOSITIONAL BREAKDOWN



Athens, TX (903) 677-0700 . Beeville, TX (361) 354-5200 . Edmond, OK (405) 525-0579

STATION: 20126

LEASE: BITTER LAKES

C6+ FRACTION COMPOSITION

<u>HEXANE ISOMERS (C6'S)</u>		<u>MOLE %</u>	<u>LIQ VOL %</u>	<u>WT. %</u>
2,2-Dimethylbutane	P	0.963	1.029	1.005
2,3-Dimethylbutane	PN	0.000	0.000	0.000
2-Methylpentane	P	7.511	7.975	7.837
3-Methylpentane	P	4.516	4.716	4.712
Methylcyclopentane	N	0.000	0.000	0.000
Benzene	A	1.287	0.922	1.218
Cyclohexane	N	5.380	4.686	5.483
n-Hexane	P	12.773	13.448	13.328
C6 TOTALS		32.430		
<u>HEPTANE ISOMERS (C7'S)</u>				
3,3-Dimethylpentane	P	0.170	0.198	0.206
2,3-Dimethylpentane	P	0.000	0.000	0.000
2,2-Dimethylpentane	P	0.422	0.506	0.513
2,4-Dimethylpentane	P	1.224	1.468	1.485
2 & 3-Methylhexane	P	0.429	0.504	0.521
1,t-3-Dimethylcyclopentane	N	0.000	0.000	0.000
1,c-3-Dimethylcyclopentane	N	0.000	0.000	0.000
1,t-2-Dimethylcyclopentane	N	0.000	0.000	0.000
3-Ethylpentane	N	0.000	0.000	0.000
Toluene	A	1.026	0.879	1.145
Methylcyclohexane	N	7.920	8.147	9.416
Ethylcyclopentane	N	0.000	0.000	0.000
n-Heptane	P	8.547	10.097	10.370
C7 TOTALS		19.738		
<u>OCTANE ISOMERS (C8'S)</u>				
2,4 & 2,5-Dimethylhexane	P	0.627	0.833	0.868
1,t-2,c-4-Trimethylcyclopentane	N	0.000	0.000	0.000
1,t-2,c-3-Trimethylcyclopentane	N	0.000	0.000	0.000
2-Methylheptane	P	2.470	3.258	3.416
1,c-2,t-4-Trimethylcyclopentane	N	0.000	0.000	0.000
3-Methylheptane	P	0.763	0.995	1.055
1,c-3-Dimethylcyclohexane	N	0.088	0.103	0.119
1,t-4-Dimethylcyclohexane	N	0.000	0.000	0.000
methyl-ethylcyclopentanes	N	0.000	0.000	0.000
1,t-3 & 1,c-4 Dimethylcyclohexane	N	0.400	0.461	0.543
1,c-2-Dimethylcyclohexane	N	0.243	0.276	0.330
Ethylcyclohexane	N	0.787	0.904	1.070
Ethylbenzene	A	0.025	0.025	0.032
m & p-Xylene	A	0.093	0.092	0.119
o-Xylene	A	0.090	0.087	0.115
Cyclooctane	P	0.029	0.031	0.039
n-Octane	P	3.257	4.272	4.505
C8 TOTALS		8.871		



Athens, TX (903) 677-0700 . Beeville, TX (361) 354-5200 . Edmond, OK (405) 525-0579

STATION: 20126

LEASE: BITTER LAKES

C6+ FRACTION COMPOSITION

<u>NONANE ISOMERS (C9'S)</u>		<u>MOLE %</u>	<u>LIQ VOL %</u>	<u>WT. %</u>
Trimethylhexanes	P	0.000	0.000	0.000
Dimethylpentanes	P	0.000	0.000	0.000
Isopropylcyclopentane	N	0.000	0.000	0.000
n-Propylcyclopentane	N	0.000	0.000	0.000
3-Methyloctane	P	0.000	0.000	0.000
Trimethylcyclohexanes	N	0.000	0.000	0.000
Isopropylbenzene	A	0.029	0.032	0.042
Isopropylcyclohexane	N	0.000	0.000	0.000
n-Propylcyclohexane	N	0.022	0.028	0.033
n-Propylbenzene	A	0.033	0.037	0.048
m-Ethyltoluene	A	0.000	0.000	0.000
p-Ethyltoluene	A	0.000	0.000	0.000
1,3,5-Trimethylbenzene	A	0.004	0.004	0.006
4 & 5-Methylnonane	P	0.000	0.000	0.000
o-Ethyltoluene & 3-Methylnonane	AP	0.000	0.000	0.000
1,2,3-Trimethylbenzene	A	0.000	0.000	0.000
n-Nonane	P	0.024	0.034	0.037
C9 TOTALS		0.111		
<u>DECANE ISOMERS (C10'S)</u>				
2-Methylnonane	P	0.000	0.000	0.000
tert-Butylbenzene	A	0.013	0.016	0.020
1,2,4-Trimethylbenzene	A	0.029	0.032	0.042
Isobutylcyclohexane & tert-Butylcyclohexane		0.192	0.267	0.326
Isobutylbenzene	A	0.000	0.000	0.000
sec-Butylbenzene	A	0.005	0.007	0.009
n-Butylcyclohexane	N	0.015	0.022	0.026
1,3-Diethylbenzene	A	0.000	0.000	0.000
1,2-Diethylbenzene & n-Butylbenzene	A	0.010	0.013	0.016
1,4-Diethylbenzene	A	0.000	0.000	0.000
n-Decane	P	0.096	0.151	0.166
C10 TOTALS		0.359		
<u>UNDECANE ISOMERS (C11'S)</u>				
n-Undecane	P	0.000	0.000	0.000
<u>DODECANE ISOMERS (C12'S)</u>				
n-Dodecane +	P	0.000	0.000	0.000



Bryan Research & Engineering, LLC

ProMax[®] 5.0

Copyright © 2002-2020 BRE Group, Ltd. All Rights Reserved.

Simulation Report

Project: Bitter Lake - Tank Emissions.pmx

Licensed to Resolute Compliance, LLC and Affiliates

Client Name: IACX

Location: Bitter Lake

Job: NSR - Tanks

ProMax Filename: C:\Users\Kcurtis\OneDrive - Resolute Compliance, LLC\Env\Projects\Env-IACX-Bitter Lake CS NSR-0005\Simulations\Bitter Lake - Tank Emissions.pmx

ProMax Version: 5.0.20259.0

Simulation Initiated: 10/21/2021 5:13:57 PM

Bryan Research & Engineering, LLC

Chemical Engineering Consultants

P.O. Box 4747 Bryan, Texas 77805

Office: (979) 776-5220

FAX: (979) 776-4818

<mailto:sales@bre.com>

<http://www.bre.com/>

Report Navigator can be activated via the ProMax Navigator Toolbar.


An asterisk (*), throughout the report, denotes a user specified value.

A question mark (?) after a value, throughout the report, denotes an extrapolated or approximate value.

Bitter Lake Compressor Station


Tank Simulation using Updated November 2019 AP-42 Section 7 Tank Working and Breathing Emissions

TP: 300 bbl/day
61% HC, 39% Water



"GB Flash" VOCs = 89.38 ton/yr


Annual tank loss calculations for "Mixed Liquid".
Total working and breathing losses are 4.7 ton/yr.
* Only Non-Exempt VOCs are reported.



Annual – Tank 2, 1 x 500 bbl

"C Flash" VOCs = 0 ton/yr

Annual tank loss calculations for "HC".
Total working and breathing losses are 18.74 ton/yr.
* Only Non-Exempt VOCs are reported.



Annual – Tank 2a, 1 x 500 bbl

Properties	HC Load	
Molecular Weight(Total)	51.887	lb/lbmol

"W Flash" VOCs = 0 ton/yr

Annual tank loss calculations for "P.W.".
Total working and breathing losses are 0.0007699 ton/yr.
* Only Non-Exempt VOCs are reported.



Annual – Tank 1, 1 x 500 bbl

Properties	PW Load	
Molecular Weight(Total)	18.313	lb/lbmol

Process Streams		C Flash Condensate		GB Flash	HC	HC Load	Mixed Liquid	P.W.	Produced Water		PW Load
Composition		Status:	Solved	Solved	Solved	Solved	Solved	Solved	Solved	Solved	Solved
Phase: Total		From Block:	Tank 2a	Tank 2	Tank 2a	MIX-102	MIX-101	Tank 1	Tank 2	MIX-103	
To Block:		--	Tank 2a	Tank 2	--	--	--	--	--	--	--
Mole Fraction			%	%	%	%	%	%	%	%	%
H2S			0	0	0	0	0	0	0	0	0
Oxygen			0	0	0	0	0	0	0	0	0
Nitrogen			0.00172106	1.10642	0.00172106	0.00338790	0.00572543	1.42274E-05	1.42274E-05	0.0140528	
Carbon Dioxide			0	0	0	0	0	0	0	0	0
Methane			0.00966319	1.75382	0.00966319	0.0792096	0.0103427	4.62087E-05	4.62087E-05	0.0757185	
Ethane			1.32987	35.5783	1.32987	29.8868	0.414263	0.00147153	0.00147153	1.95686	
Propane			2.44168	18.5979	2.44168	19.9711	0.530618	0.000545750	0.000545750	0.163102	
i-Butane			1.77449	5.02015	1.77449	5.86880	0.343895	0.000110297	0.000110297	0.0105952	
n-Butane			7.78496	14.3695	7.78496	17.9593	1.47125	0.000383072	0.000383072	0.0264928	
i-Pentane			10.3159	7.68772	10.3159	9.23549	1.89383	0.000152587	0.000152587	0.00360991	
n-Pentane			13.3574	7.24944	13.3574	8.85523	2.43885	5.14839E-05	5.14839E-05	0.000621285	
Heptane			19.1843	0.837694	19.1843	1.06378	3.45595	3.21723E-06	3.21723E-06	1.2946E-06	
Octane			8.98448	0.117593	8.98448	0.134248	1.61716	1.82287E-07	1.82287E-07	1.69204E-08	
Nonane			0.113925	0.000439804	0.113925	0.000451459	0.0205007	8.21628E-10	8.21628E-10	2.08546E-11	
Decane			0.369513	0.000451951	0.369513	0.000409992	0.0664889	2.36079E-10	2.36079E-10	5.58404E-13	
Water			0.0318350	2.00883	0.0318350	0.000273603	81.5309	99.9961	99.9961	97.7446	
Benzene			1.31176	0.201529	1.31176	0.154782	0.237698	0.000843501	0.000843501	0.00359700	
Toluene			1.05135	0.0434738	1.05135	0.0358881	0.189493	0.000135054	0.000135054	0.000165743	
Ethylbenzene			0.0256490	0.000308482	0.0256490	0.000280494	0.00461729	8.94708E-07	8.94708E-07	3.51227E-07	
o-Xylene			0.0923411	0.000863570	0.0923411	0.000697262	0.0166222	3.68878E-06	3.68878E-06	1.00072E-06	
2,2-Dimethylbutane			0.980058	0.309802	0.980058	0.406437	0.177858	2.49148E-06	2.49148E-06	1.86941E-05	
2,3-Dimethylbutane			0	0	0	0	0	0	0	0	
2-Methylpentane			7.66524	1.63606	7.66524	2.06933	1.38772	1.68538E-05	1.68538E-05	9.49675E-05	
3-Methylpentane			4.61180	0.868785	4.61180	1.10982	0.834066	2.24986E-05	2.24986E-05	0.000150675	
Methylcyclopentane			0	0	0	0	0	0	0	0	
Cyclohexane			5.50396	0.665434	5.50396	0.670662	0.993640	7.10399E-05	7.10399E-05	0.000290902	
nC6			13.0581	1.94548	13.0581	2.49359	2.35906	9.69081E-06	9.69081E-06	2.68673E-05	
Molar Flow		lbmol/h	lbmol/h	lbmol/h	lbmol/h	lbmol/h	lbmol/h	lbmol/h	lbmol/h	lbmol/h	lbmol/h
H2S		0	0	0	0	0	0	0	0	0	0
Oxygen		0	0	0	0	0	0	0	0	0	0
Nitrogen		0	0.000358562	0.00625737	0.000358562	3.37914E-06	0.00662936	1.34291E-05	1.34291E-05	2.47030E-07	
Carbon Dioxide		0	0	0	0	0	0	0	0	0	0
Methane		0	0.00201321	0.00991880	0.00201321	7.90050E-05	0.0119756	4.36158E-05	4.36158E-05	1.33103E-06	
Ethane		0	0.277063	0.201214	0.277063	0.0298096	0.479666	0.00138895	0.00138895	3.43991E-05	
Propane		0	0.508696	0.105181	0.508696	0.0199196	0.614392	0.000515126	0.000515126	2.86713E-06	
i-Butane		0	0.369694	0.0283916	0.369694	0.00585364	0.398189	0.000104108	0.000104108	1.86249E-07	
n-Butane		0	1.62190	0.0812674	1.62190	0.0179129	1.70353	0.000361576	0.000361576	4.65709E-07	
i-Pentane		0	2.14920	0.0434781	2.14920	0.00921163	2.19282	0.000144025	0.000144025	6.34577E-08	
n-Pentane		0	2.78285	0.0409994	2.78285	0.00883236	2.82389	4.85950E-05	4.85950E-05	1.09214E-08	
Heptane		0	3.99683	0.00473761	3.99683	0.00106103	4.00157	3.03670E-06	3.03670E-06	3.74332E-11	
Octane		0	1.87181	0.000665052	1.87181	0.000133901	1.87247	1.72058E-07	1.72058E-07	2.97439E-13	
Nonane		0	0.0237349	2.48732E-06	0.0237349	4.50293E-07	0.0237374	7.75523E-10	7.75523E-10	3.66598E-16	
Decane		0	0.0769836	2.55603E-06	0.0769836	4.08933E-07	0.0769862	2.22832E-10	2.22832E-10	9.81602E-18	
Water		0	0.00663245	0.0113610	0.00663245	2.72896E-07	94.4029	94.3849	94.3849	0.00171822	
Benzene		0	0.273290	0.00113975	0.273290	0.000154382	0.275225	0.000796169	0.000796169	6.32307E-08	
Toluene		0	0.219037	0.000245868	0.219037	3.57954E-05	0.219411	0.000127476	0.000127476	2.91355E-09	
Ethylbenzene		0	0.00534367	1.74463E-06	0.00534367	2.79770E-07	0.00534626	8.44502E-07	8.44502E-07	6.17412E-12	
o-Xylene		0	0.0192382	4.88395E-06	0.0192382	6.95461E-07	0.0192465	3.48178E-06	3.48178E-06	1.75913E-11	
2,2-Dimethylbutane		0	0.204184	0.00175210	0.204184	0.000405387	0.205938	2.35167E-06	2.35167E-06	3.28619E-10	
2,3-Dimethylbutane		0	0	0	0	0	0	0	0	0	
2-Methylpentane		0	1.59696	0.00925278	1.59696	0.00206399	1.60623	1.59080E-05	1.59080E-05	1.66941E-09	
3-Methylpentane		0	0.960814	0.00491345	0.960814	0.00110696	0.965749	2.12361E-05	2.12361E-05	2.64868E-09	
Methylcyclopentane		0	0	0	0	0	0	0	0	0	
Cyclohexane		0	1.14668	0.00376339	1.14668	0.000668929	1.15052	6.70536E-05	6.70536E-05	5.11368E-09	
nC6		0	2.72050	0.0110027	2.72050	0.00248715	2.73151	9.14701E-06	9.14701E-06	4.72293E-10	
Mass Fraction			%	%	%	%	%	%	%	%	%
H2S			0	0	0	0	0	0	0	0	0
Oxygen			0	0	0	0	0	0	0	0	0
Nitrogen			0.000575975	0.649309	0.000575975	0.00182910	0.00534963	2.21218E-05	2.21218E-05	0.0214961	
Carbon Dioxide			0	0	0	0	0	0	0	0	0
Methane			0.00185197	0.589419	0.00185197	0.0244901	0.00553420	4.11455E-05	4.11455E-05	0.0663289	
Ethane			0.477719	22.4116	0.477719	17.3197	0.415475	0.00245592	0.00245592	3.21299	
Propane			1.28626	17.1801	1.28626	16.9722	0.780417	0.00133572	0.00133572	0.392722	
i-Butane			1.23213	6.11260	1.23213	6.57404	0.666680	0.000355822	0.000355822	0.0336263	
n-Butane			5.40556	17.4966	5.40556	20.1174	2.85219	0.00123580	0.00123580	0.0840813	
i-Pentane			8.89159	11.6197	8.89159	12.8419	4.55741	0.000611047	0.000611047	0.0142218	
n-Pentane			11.5131	10.9572	11.5131	12.3132	5.86899	0.000206171	0.000206171	0.00244765	
Heptane			22.9649	1.75845	22.9649	2.05433	11.5503	1.78931E-05	1.78931E-05	1.16513E-05	
Octane			12.2605	0.281400	12.2605	0.295545	6.16135	1.15573E-06	1.15573E-06	1.05540E-07	
Nonane			0.174556	0.00118168	0.174556	0.00111592	0.0876988	5.84894E-09	5.84894E-09	1.46052E-10	
Decane			0.628089	0.00134713	0.628089	0.00112426	0.315535	1.86437E-09	1.86437E-09	4.33838E-12	
Water			0.00685155	0.758145	0.00685155	9.49954E-05	48.9905	99.9888	99.9888	96.1532	
Benzene			1.22409	0.329778	1.22409	0.233012	0.619286	0.00365704	0.00365704	0.0153422	
Toluene			1.15726	0.0839143	1.15726	0.0637283	0.582350	0.000690677	0.000690677	0.000833885	
Ethylbenzene			0.0325308	0.000686087	0.0325308	0.000573913	0.0163500	5.27217E-06	5.27217E-06	2.03610E-06	
o-Xylene			0.117117	0.00192064	0.117117	0.00142665	0.0588599	2.17368E-05	2.17368E-05	5.80128E-06	
2,2-Dimethylbutane			1.00897	0.559287	1.00897	0.675020	0.511217	1.19170E-05	1.19170E-05	8.79667E-05	
2,3-Dimethylbutane			0	0	0	0	0	0	0	0	
2-Methylpentane			7.89135	2.95358	7.89135	3.43680	3.98728	8.06135E-05	8.06135E-05	0.000446877	
3-Methylpentane			4.74784	1.56842	4.74784	1.84322	2.39736	0.000107613	0.000107613	0.000709014	
Methylcyclopentane			0	0	0	0	0	0	0	0	
Cyclohexane			5.53377	1.17321	5.53377	1.08780	2.78921	0.000331843	0.000331843	0.00133684	
nC6			13.4433	3.51219	13.4433	4.14143	6.78066	4.63522E-05	4.63522E-05	0.000126426	

Tank Inlet W Flash Water												
1		2		3		4		5		6		7
Solved	Solved	Solved	Solved	Solved	Solved	Solved	Solved	Solved	Solved	Solved	Solved	Solved
MIX-101	Tank 1	MIX-101	MIX-100	MIX-103	MIX-102	MIX-102	MIX-100	MIX-100	MIX-103	MIX-100	MIX-103	MIX-100
%	%	%	%	%	%	%	%	%	%	%	%	%
0*	0*	0*	0*	0*	0*	0*	0*	0*	0*	0*	0*	0
0*	0*	0*	0*	0*	0*	0*	0*	0*	0*	0*	0*	0
0.031*	0*	0.0236570*	0.0140528*	0.00338790*	0.00338790*	0.0236570*	0.0140528*	0.0236570*	0.0140528*	0.0236570*	0.0140528*	0.0236570
0*	0*	0*	0*	0*	0*	0*	0*	0*	0*	0*	0*	0
0.056*	0*	0.186706*	0.0757185*	0.0792096*	0.0792096*	0.186706*	0.0757185*	0.186706*	0.0757185*	0.186706*	0.0757185*	0.186706
2.243*	0*	26.9898*	1.95686*	29.8868*	29.8868*	26.9898*	1.95686*	26.9898*	1.95686*	26.9898*	1.95686*	26.9898
2.873*	0*	16.5476*	0.163102*	19.9711*	19.9711*	16.5476*	0.163102*	16.5476*	0.163102*	16.5476*	0.163102*	16.5476
1.862*	0*	5.07481*	0.0105952*	5.86880*	5.86880*	5.07481*	0.0105952*	5.07481*	0.0105952*	5.07481*	0.0105952*	5.07481
7.966*	0*	15.8203*	0.0264928*	17.9593*	17.9593*	15.8203*	0.0264928*	15.8203*	0.0264928*	15.8203*	0.0264928*	15.8203
10.254*	0*	8.36161*	0.00360991*	9.23549*	9.23549*	8.36161*	0.00360991*	8.36161*	0.00360991*	8.36161*	0.00360991*	8.36161
13.205*	0*	8.06544*	0.000621285*	8.85523*	8.85523*	8.06544*	0.000621285*	8.06544*	0.000621285*	8.06544*	0.000621285*	8.06544
18.712*	0*	0.985644*	2.12946E-06*	1.06378*	1.06378*	0.985644*	2.12946E-06*	0.985644*	2.12946E-06*	0.985644*	2.12946E-06*	0.985644
8.756*	0*	0.124543*	1.69204E-08*	0.134248*	0.134248*	0.124543*	1.69204E-08*	0.124543*	1.69204E-08*	0.124543*	1.69204E-08*	0.124543
0.111*	0*	0.000418989*	2.08546E-11*	0.000451459*	0.000451459*	0.000418989*	2.08546E-11*	0.000418989*	2.08546E-11*	0.000418989*	2.08546E-11*	0.000418989
0.36*	0*	0.000380551*	5.58404E-13*	0.000409992*	0.000409992*	0.000380551*	5.58404E-13*	0.000380551*	5.58404E-13*	0.000380551*	5.58404E-13*	0.000380551
0*	100*	11.4196*	97.7446*	0.000273603*	0.000273603*	11.4196*	97.7446*	11.4196*	97.7446*	11.4196*	97.7446*	11.4196
1.287*	0*	0.143251*	0.00359700*	0.154782*	0.154782*	0.143251*	0.00359700*	0.143251*	0.00359700*	0.143251*	0.00359700*	0.143251
1.026*	0*	0.0332750*	0.000165743*	0.0358881*	0.0358881*	0.0332750*	0.000165743*	0.0332750*	0.000165743*	0.0332750*	0.000165743*	0.0332750
0.025*	0*	0.000260270*	3.51227E-07*	0.000280494*	0.000280494*	0.000260270*	3.51227E-07*	0.000260270*	3.51227E-07*	0.000260270*	3.51227E-07*	0.000260270
0.09*	0*	0.000647078*	1.00072E-06*	0.000697262*	0.000697262*	0.000647078*	1.00072E-06*	0.000647078*	1.00072E-06*	0.000647078*	1.00072E-06*	0.000647078
0.963*	0*	0.372941*	1.86941E-05*	0.406437*	0.406437*	0.372941*	1.86941E-05*	0.372941*	1.86941E-05*	0.372941*	1.86941E-05*	0.372941
0*	0*	0*	0*	0*	0*	0*	0*	0*	0*	0*	0*	0
7.511*	0*	1.90543*	9.49675E-05*	2.06933*	2.06933*	1.90543*	9.49675E-05*	1.90543*	9.49675E-05*	1.90543*	9.49675E-05*	1.90543
4.516*	0*	1.02283*	0.000150675*	1.10982*	1.10982*	1.02283*	0.000150675*	1.02283*	0.000150675*	1.02283*	0.000150675*	1.02283
0*	0*	0*	0*	0*	0*	0*	0*	0*	0*	0*	0*	0
5.38*	0*	0.619628*	0.000290902*	0.670662*	0.670662*	0.619628*	0.000290902*	0.619628*	0.000290902*	0.619628*	0.000290902*	0.619628
12.773*	0*	2.30118*	2.68673E-05*	2.49359*	2.49359*	2.30118*	2.68673E-05*	2.30118*	2.68673E-05*	2.30118*	2.68673E-05*	2.30118
lbmol/h	lbmol/h	lbmol/h	lbmol/h	lbmol/h	lbmol/h	lbmol/h	lbmol/h	lbmol/h	lbmol/h	lbmol/h	lbmol/h	lbmol/h
0*	0	0*	0*	0*	0*	0*	0*	0*	0*	0*	0*	0
0*	0	0*	0*	0*	0*	0*	0*	0*	0*	0*	0*	0
0.00662936*	0	0*	2.94612E-07*	2.16563E-07*	4.72837E-07*	2.90631E-06*	6.40057E-06*	3.04676E-08*	6.69518E-06*	3.04676E-08*	6.69518E-06*	6.69518E-06
0*	0	0*	0*	0*	0*	0*	0*	0*	0*	0*	0*	0
0.019756*	0	0*	2.32514E-06*	1.16687E-06*	1.10550E-05*	6.79500E-05*	5.05147E-05*	1.64163E-07*	5.28398E-05*	1.64163E-07*	5.28398E-05*	5.28398E-05
0.479666*	0	0*	0.000336116*	3.01565E-05*	0.00417120*	0.0256384*	0.00730227*	4.24262E-06*	0.00763839*	4.24262E-06*	0.00763839*	0.00763839
0.614392*	0	0*	0.000206075*	2.51351E-06*	0.00278731*	0.0171322*	0.00447708*	3.53618E-07*	0.00468315*	3.53618E-07*	0.00468315*	0.00468315
0.398189*	0	0*	3.1990E-05*	1.63278E-07*	0.000819089*	0.00503455*	0.00137302*	2.29711E-08*	0.00143622*	2.29711E-08*	0.00143622*	0.00143622
1.70353*	0	0*	0.000197018*	4.08270E-07*	0.00250652*	0.0154064*	0.00428029*	5.74383E-08*	0.00447731*	5.74383E-08*	0.00447731*	0.00447731
2.19282*	0	0*	0.000104131*	5.56311E-08*	0.00128897*	0.00792267*	0.00226229*	7.82657E-09*	0.00236642*	7.82657E-09*	0.00236642*	0.00236642
2.82389*	0	0*	0.000100443*	9.57440E-09*	0.00123589*	0.00759646*	0.00218216*	1.34699E-09*	0.00228260*	1.34699E-09*	0.00228260*	0.00228260
4.00157*	0	0*	1.22747E-05*	3.28164E-11*	0.000148468*	0.000912564*	0.000266673*	4.61683E-12*	0.000278947*	4.61683E-12*	0.000278947*	0.000278947
1.87247*	0	0*	1.55099E-06*	2.60754E-13*	1.87366E-05*	0.000115165*	3.36959E-05*	3.66847E-14*	3.52469E-05*	3.66847E-14*	3.52469E-05*	3.52469E-05
0.0237374*	0	0*	5.21787E-09*	3.21383E-16*	6.30087E-08*	3.87284E-07*	1.13360E-07*	4.52144E-17*	1.18578E-07*	4.52144E-17*	1.18578E-07*	1.18578E-07
0.0769862*	0	0*	4.73918E-09*	8.60536E-18*	5.72212E-08*	3.51711E-07*	1.02961E-07*	1.21066E-18*	1.07700E-07*	1.21066E-18*	1.07700E-07*	1.07700E-07
0*	94.4029*	0.000142213*	0.00150631*	3.81858E-08*	2.34710E-07*	0.00308964*	0.000211918*	0.000211918*	0.00308964*	0.000211918*	0.00308964*	0.00308964
0.275225*	0	0*	1.78397E-06*	5.54321E-08*	2.16024E-05*	0.000132780*	3.87576E-05*	7.79857E-09*	4.05415E-05*	7.79857E-09*	4.05415E-05*	4.05415E-05
0.219411*	0	0*	4.14389E-07*	2.55421E-09*	5.00879E-06*	3.07866E-05*	9.00277E-06*	3.59343E-10*	9.41716E-06*	3.59343E-10*	9.41716E-06*	9.41716E-06
0.00534626*	0	0*	3.24126E-09*	5.41263E-12*	3.91476E-08*	2.40622E-07*	7.04178E-08*	7.61487E-13*	7.36591E-08*	7.61487E-13*	7.36591E-08*	7.36591E-08
0.0192465*	0	0*	8.05836E-09*	1.54217E-11*	9.73146E-08*	5.98147E-07*	1.75071E-07*	2.16963E-12*	1.83130E-07*	2.16963E-12*	1.83130E-07*	1.83130E-07
0.205938*	0	0*	4.64441E-06*	2.88089E-10*	5.67250E-05*	0.000348662*	0.000100902*	4.05303E-11*	0.000105546*	4.05303E-11*	0.000105546*	0.000105546
0*	0	0*	0*	0*	0*	0*	0*	0*	0*	0*	0*	0
1.60623*	0	0*	2.37292E-05*	1.46351E-09*	0.000288810*	0.00177518*	0.000515527*	2.05897E-10*	0.000539256*	2.05897E-10*	0.000539256*	0.000539256
0.965749*	0	0*	1.27378E-05*	2.32200E-09*	0.000154894*	0.000952063*	0.000276733*	3.26675E-10*	0.000289471*	3.26675E-10*	0.000289471*	0.000289471
0*	0	0*	0*	0*	0*	0*	0*	0*	0*	0*	0*	0
1.15052*	0	0*	7.71651E-06*	4.48298E-09*	9.36020E-05*	0.000575327*	0.000167645*	6.30697E-10*	0.000175361*	6.30697E-10*	0.000175361*	0.000175361
2.73151*	0	0*	2.86576E-05*	4.14043E-10*	0.000348023*	0.00213913*	0.000622599*	5.82504E-11*	0.000651256*	5.82504E-11*	0.000651256*	0.000651256
%	%	%	%	%	%	%	%	%	%	%	%	%
0*	0*	0*	0	0	0	0	0	0	0	0	0	0
0*	0*	0*	0	0	0	0	0	0	0	0	0	0
0.0104875*	0*	0.0137702	0.0214961	0.00182910	0.00182910	0.0137702	0.0214961	0.0137702	0.0214961	0.0137702	0.0214961	0.0137702
0*	0*	0*	0	0	0	0	0	0	0	0	0	0
0.0108494*	0*	0.0622364	0.0663289	0.0244901	0.0244901	0.0622364	0.0663289	0.0622364	0.0663289	0.0622364	0.0663289	0.0622364
0.814505*	0*	16.8629	3.21299	17.3197	17.3197	16.8629	3.21299	16.8629	3.21299	16.8629	3.21299	16.8629
1.52995*	0*	15.1616	0.392722	16.9722	16.9722	15.1616	0.392722	15.1616	0.392722	15.1616	0.392722	15.1616
1.30697*	0*	6.12881	0.0336263	6.57404	6.57404	6.12881	0.0336263	6.12881	0.0336263	6.12881	0.0336263	6.12881
5.59149*	0*	19.1061	0.0840813	20.1174	20.1174	19.1061	0.0840813	19.1061	0.0840813	19.1061	0.0840813	19.1061
8.93444*	0*	12.5352	0.0142218	12.8419	12.8419	12.5352	0.0142218	12.5352	0.0142218	12.5352	0.0142218	12.5352
11.5057*	0*	12.0913	0.00244765	12.3132	12.3132	12.0913	0.00244765	12.0913	0.00244765	12.0913	0.00244765	12.0913
22.6434*	0*	2.05216	1.16513E-05	2.05433	2.05433	2.05216	1.16513E-05	2.05216	1.16513E-05	2.05216	1.16513E-05	2.05216
12.0788*	0*	0.295602	1.05540E-07	0.295545	0.295545	0.295602	1.05540E-07	0.295602	1.05540E-07	0.295602	1.05540E-07	0.295602
0.171926*	0*	0.00111658	1.46052E-10	0.00111592	0.00111592	0.00111658	1.46052E-10	0.00111658	1.46052E-10	0.00111658	1.46052E-10	0.00111658
0.618581*	0*	0.000112506	4.33838E-12	0.00112426	0.00112426	0.000112506	4.33838E-12	0.000112506	4.33838E-12	0.000112506	4.33838E-12	0.000112506
0*	100*	4.27470	96.1532	9.49954E-05	9.49954E-05	4.27470	96.1532	4.27470	96.1532	4.27470	96.1532	4.27470
1.21406*	0*	0.232503	0.0153422	0.233012	0.233012	0.232503	0.0153422	0.232503	0.0153422	0.232503	0.0153422	0.232503
1.14165*	0*	0.0637049	0.000833885	0.0637283	0.0637283	0.0637049	0.000833885	0.0637049	0.000833885	0.0637049	0.000833885	0.0637049
0.0320528*	0*	0.000574143	2.03610E-06	0.00057								

Mass Flow	lb/h	lb/h	lb/h	lb/h	lb/h	lb/h	lb/h	lb/h	lb/h
H2S	0	0	0	0	0	0	0	0	0
Oxygen	0	0	0	0	0	0	0	0	0
Nitrogen	0	0.0100445	0.175290	0.0100445	9.46613E-05	0.185711	0.000376194	0.000376194	6.92016E-06
Carbon Dioxide	0	0	0	0	0	0	0	0	0
Methane	0	0.0322969	0.159122	0.0322969	0.00126743	0.192118	0.000699704	0.000699704	2.13531E-05
Ethane	0	8.33103	6.05032	8.33103	0.896346	14.4231	0.0417645	0.0417645	0.00103435
Propane	0	22.4313	4.63802	22.4313	0.878365	27.0920	0.0227148	0.0227148	0.000126428
i-Butane	0	21.4874	1.65018	21.4874	0.340226	23.1436	0.00605098	0.00605098	1.08252E-05
n-Butane	0	94.2686	4.72344	94.2686	1.04114	99.0131	0.0210156	0.0210156	2.70680E-05
i-Pentane	0	155.062	3.13690	155.062	0.664608	158.209	0.0103912	0.0103912	4.57839E-06
n-Pentane	0	200.779	2.95806	200.779	0.637244	203.741	0.00350607	0.00350607	7.87965E-07
Heptane	0	400.490	0.474718	400.490	0.106318	400.965	0.000304283	0.000304283	3.75088E-09
Octane	0	213.814	0.0759679	213.814	0.0152954	213.890	1.96539E-05	1.96539E-05	3.39760E-11
Nonane	0	3.04412	0.000319012	3.04412	5.77524E-05	3.04444	9.94648E-08	9.94648E-08	4.70180E-14
Decane	0	10.9534	0.000363676	10.9534	5.81836E-05	10.9537	3.17048E-08	3.17048E-08	1.39664E-15
Water	0	0.119486	0.204672	0.119486	4.91630E-06	1700.70	1700.37	1700.37	0.0309543
Benzene	0	21.3472	0.0890283	21.3472	0.0120591	21.4984	0.0621902	0.0621902	4.93906E-06
Toluene	0	20.1817	0.0226538	20.1817	0.00329813	20.2161	0.0117454	0.0117454	2.68450E-07
Ethylbenzene	0	0.567311	0.000185219	0.567311	2.97017E-05	0.567586	8.96565E-05	8.96565E-05	6.55476E-10
o-Xylene	0	2.04242	0.000518504	2.04242	7.38336E-05	2.04331	0.000369644	0.000369644	1.86758E-09
2,2-Dimethylbutane	0	17.5956	0.150988	17.5956	0.0349343	17.7468	0.000202656	0.000202656	2.83188E-08
2,3-Dimethylbutane	0	0	0	0	0	0	0	0	0
2-Methylpentane	0	137.619	0.797362	137.619	0.177865	138.417	0.00137088	0.00137088	1.43862E-07
3-Methylpentane	0	82.7985	0.423418	82.7985	0.0953924	83.2237	0.00183003	0.00183003	2.28251E-07
Methylcyclopentane	0	0	0	0	0	0	0	0	0
Cyclohexane	0	96.5044	0.316725	96.5044	0.0562967	96.8268	0.00564319	0.00564319	4.30364E-07
nC6	0	234.440	0.948165	234.440	0.214331	235.389	0.000788247	0.000788247	4.07000E-08

Process Streams		C Flash Condensate		GB Flash	HC	HC Load	Mixed Liquid	P.W.	Produced Water		PW Load
Properties		Status:	Solved	Solved	Solved	Solved	Solved	Solved	Solved	Solved	Solved
Phase: Total		From Block:	Tank 2a	Tank 2	Tank 2	MIX-102	MIX-101	Tank 1	Tank 2	MIX-103	
Property		To Block:	--	Tank 2a	--	--	Tank 2	--	Tank 1	--	
Units											
Temperature	°F	64.1*	64.1	64.1*	64.1	74.4627	59.9358	64.1	64.1	74.4627	
Pressure	psia	14.6959*	14.6959	14.6959*	14.6959	15.6606	18.6959	14.6959	14.6959	0.432350	
Mole Fraction Vapor	%		0	100	0	100	0.0707483	0	0	100	
Mole Fraction Light Liquid	%		100	0	100	0	18.4005	100	100	0	
Mole Fraction Heavy Liquid	%		0	0	0	0	81.5288	0	0	0	
Molecular Weight	lb/lbmol		83.7062	47.7345	83.7062	51.8870	29.9813	18.0166	18.0166	18.3134	
Mass Density	lb/ft³		41.6679	0.127366	41.6679	0.145258	37.0979	62.3333	62.3333	0.00138192	
Molar Flow	lbmol/h	0	20.8338	0.565554	20.8338	0.0997417	115.788	94.3886	94.3886	0.00175787	
Mass Flow	lb/h	0	1743.92	26.9964	1743.92	5.17530	3471.48	1700.56	1700.56	0.0321927	
Vapor Volumetric Flow	ft³/h	0	41.8528	211.959	41.8528	35.6284	93.5762	27.2818	27.2818	23.2956	
Liquid Volumetric Flow	gpm	0	5.21802	26.4260	5.21802	4.44199	11.6666	3.40136	3.40136	2.90439	
Std Vapor Volumetric Flow	MMSCFD	0	0.189746	0.00515085	0.189746	0.000908409	1.05455	0.859655	0.859655	1.60100E-05	
Std Liquid Volumetric Flow	sgpm	0	5.24495	0.105226	5.24495	0.0195247	8.75	3.39983	3.39983	6.85038E-05	
Compressibility			0.00525230	0.979875	0.00525230	0.975922	0.00270964	0.000755695	0.000755695	0.999561	
Specific Gravity			0.668089	1.64815	0.668089	1.79153		0.999431	0.999431	0.632316	
API Gravity			79.6207		79.6207			10.0019	10.0019		
Enthalpy	Btu/h	0	-1.69609E+06	-27754.9	#####	-5036.45	-1.33588E+07	#####	-1.16203E+07	-180.130	
Mass Enthalpy	Btu/lb		-972.575	-1028.09	-972.575	-973.171	-3848.17	-6833.22	-6833.22	-5595.36	
Mass Cp	Btu/(lb*°F)		0.517633	0.397047	0.517633	0.402488	0.744624	0.982682	0.982682	0.447559	
Ideal Gas Cp/Cv Ratio			1.06683	1.11818	1.06683	1.10619	1.19183	1.32611	1.32611	1.31991	
Dynamic Viscosity	cP		0.324585	0.00806216	0.324585	0.00790805		1.07436	1.07436	0.00996717	
Kinematic Viscosity	cSt		0.486302	3.95162	0.486302	3.39868		1.07599	1.07599	450.264	
Thermal Conductivity	Btu/(h*ft*°F)		0.0690535	0.00980846	0.0690535	0.00975191		0.344214	0.344214	0.0117807	
Surface Tension	lb/ft		0.00126148		0.00126148			0.005076207	0.005076207		
Net Ideal Gas Heating Value	Btu/ft³		4261.34	2454.82	4261.34	2698.28	778.818	0.100973	0.100973	37.5794	
Net Liquid Heating Value	Btu/lb		19167.1	19355.9	19167.1	19579.7	9261.19	-1057.53	-1057.53	-246.037	
Gross Ideal Gas Heating Value	Btu/ft³		4597.98	2665.53	4597.98	2926.71	881.435	50.4162	50.4162	90.2216	
Gross Liquid Heating Value	Btu/lb		20693.5	21031.6	20693.5	21251.0	10560.2	2.25942	2.25942	844.862	

lb/h	lb/h	lb/h	lb/h	lb/h	lb/h	lb/h	lb/h	lb/h	lb/h	lb/h
0*	0	0*	0*	0*	0*	0*	0*	0*	0*	0
0*	0	0*	0*	0*	0*	0*	0*	0*	0*	0
0.185711*	0	0*	8.25308E-06*	6.06666E-06*	1.32458E-05*	8.14155E-05*	0.000179302*	8.53500E-07*	0.000187555	0
0*	0	0*	0*	0*	0*	0*	0*	0*	0*	0
0.192118*	0	0*	3.73010E-05*	1.87195E-05*	0.000177350*	0.00109009*	0.000810380*	2.63358E-06*	0.000847681	0
14.4231*	0	0*	0.0101067*	0.000906776*	0.125424*	0.770922*	0.219572*	0.000127571*	0.229679	0
27.0920*	0	0*	0.00908702*	0.000110835*	0.122908*	0.755457*	0.197419*	1.55930E-05*	0.206506	0
23.1436*	0	0*	0.00367326*	9.49008E-06*	0.0476072*	0.292619*	0.0798032*	1.33513E-06*	0.0834765	0
99.0131*	0	0*	0.0114511*	2.37296E-05*	0.145684*	0.895453*	0.248780*	3.33844E-06*	0.260231	0
158.209*	0	0*	0.00751292*	4.01372E-06*	0.0929973*	0.571611*	0.163221*	5.64677E-07*	0.170734	0
203.741*	0	0*	0.00724681*	6.90781E-07*	0.0891683*	0.548075*	0.157440*	9.71839E-08*	0.164687	0
400.965*	0	0*	0.00122995*	3.28826E-09*	0.0148768*	0.0914407*	0.0267211*	4.62616E-10*	0.0279511	0
213.890*	0	0*	0.000177167*	2.97856E-11*	0.00214025*	0.0131551*	0.00384903*	4.19044E-12*	0.00402620	0
3.04444*	0	0*	6.69218E-07*	4.12190E-14*	8.08118E-06*	4.96712E-05*	1.45390E-05*	5.79898E-15*	1.52083E-05	0
10.9537*	0	0*	6.74298E-07*	1.22439E-15*	8.14152E-06*	5.00421E-05*	1.46494E-05*	1.72255E-16*	1.53237E-05	0
0*	0	1700.70*	0.00256201*	0.0271365*	6.87929E-07*	4.22837E-06*	0.0556608*	0.00381776*	0.0582228	0
21.4984*	0	0*	0.000139349*	4.32990E-06*	0.00168740*	0.0103717*	0.00302743*	6.09161E-07*	0.00316677	0
20.2161*	0	0*	3.81811E-05*	2.35340E-07*	0.000461502*	0.00283663*	0.000829501*	3.31093E-08*	0.000867682	0
0.567586*	0	0*	3.44109E-07*	5.74632E-10*	4.15611E-06*	2.55456E-05*	7.47591E-06*	8.08432E-11*	7.82001E-06	0
2.04331*	0	0*	8.55516E-07*	1.63724E-09*	1.03314E-05*	6.35022E-05*	1.85864E-05*	2.30338E-10*	1.94420E-05	0
17.7468*	0	0*	0.000400233*	2.48261E-08*	0.00488830*	0.0300461*	0.00869524*	3.49271E-09*	0.00909547	0
0*	0	0*	0*	0*	0*	0*	0*	0*	0	0
138.417*	0	0*	0.00204487*	1.26118E-07*	0.0248883*	0.152976*	0.044257*	1.77432E-08*	0.0464706	0
83.2237*	0	0*	0.00109768*	2.00099E-07*	0.0133481*	0.0820444*	0.0238476*	2.81514E-08*	0.0249452	0
0*	0	0*	0*	0*	0*	0*	0*	0*	0	0
96.8268*	0	0*	0.000649418*	3.77285E-07*	0.00787749*	0.0484192*	0.0141089*	5.30791E-08*	0.0147583	0
235.389*	0	0*	0.00246958*	3.56803E-08*	0.0299910*	0.184340*	0.0536527*	5.01975E-09*	0.0561223	0

Tank Inlet	W Flash	Water	1	2	3	4	5	6	7
Solved	Solved	Solved	Solved	Solved	Solved	Solved	Solved	Solved	Solved
--	Tank 1	--	--	--	--	--	--	--	--
MIX-101	--	MIX-101	MIX-100	MIX-103	MIX-102	MIX-102	MIX-100	MIX-103	MIX-100
60*	64.1*	60*	74.4627	74.4627	74.4627	74.4627	74.4627	74.4627	74.4627
18.6959*	14.6959*	18.6959*	3.69764	0.432350	15.6606	15.6606	3.69764	0.432350	3.69764
0.342597			100	100	100	100	100	100	100
99.6574		100	0	0	0	0	0	0	0
0		0	0	0	0	0	0	0	0
82.8047		18.0153	48.1267	18.3134	51.8870	51.8870	48.1267	18.3134	48.1267
27.7563		62.3697	0.0311970	0.00138192	0.145258	0.145258	0.0311970	0.00138192	0.0311970
21.3850	0	94.4029	0.00124535	0.00154106	0.0139567	0.0857850	0.0270557	0.000216807	0.0283010
1770.78	0	1700.70	0.0599344	0.0282222	0.724170	4.45113	1.30210	0.00397049	1.36203
63.7976	0	27.2680	1.92116	20.4224	4.98542	30.6430	41.7379	2.87317	43.6591
7.95398	0	3.39964	0.239521	2.54617	0.621559	3.82043	5.20369	0.358213	5.44321
0.194767	0	0.859786	1.13421E-05	1.40354E-05	0.000127112	0.000781297	0.000246413	1.97460E-06	0.000257755
5.35019*	0	3.39981*	0.000221430	6.00548E-05	0.00273206	0.0167927	0.00481066	8.44893E-06	0.00503209
0.0100012		0.000968330	0.995141	0.999561	0.975922	0.975922	0.995141	0.999561	0.995141
		1.00002	1.66169	0.632316	1.79153	1.79153	1.66169	0.632316	1.66169
		9.99777							
#####	0	#####	-70.5070	-157.913	-704.741	-4331.71	-1531.79	-22.2163	-1602.30
-976.737		-6837.93	-1176.40	-5595.36	-973.171	-973.171	-1176.40	-5595.36	-1176.40
0.515635		0.983071	0.401601	0.447559	0.402488	0.402488	0.401601	0.447559	0.401601
1.06803		1.32632	1.11477	1.31991	1.10619	1.10619	1.11477	1.31991	1.11477
		1.13468	0.00819033	0.00996717	0.00790805	0.00790805	0.00819033	0.00996717	0.00819033
		1.13574	16.3896	450.264	3.39868	3.39868	16.3896	450.264	16.3896
		0.342316	0.00972470	0.0117807	0.00975191	0.00975191	0.00972470	0.0117807	0.00972470
		0.00510743							
4216.86		0	2395.09	37.5794	2698.28	2698.28	2395.09	37.5794	2395.09
19173.6		-1059.76	18692.5	-246.037	19579.7	19579.7	18692.5	-246.037	18692.5
4550.39		50.3100	2603.51	90.2216	2926.71	2926.71	2603.51	90.2216	2603.51
20702.3		0	20336.5	844.862	21251.0	21251.0	20336.5	844.862	20336.5

GRI-GLYCalc VERSION 4.0 - SUMMARY OF INPUT VALUES

Case Name: Bitter Lake
File Name: C:\Users\Joseline Laureano\OneDrive - Resolute Compliance, LLC\Env\Projects\Env-IACX-Bitter Lake CS
NSR-0005\Simulations\updated.ddf
Date: August 24, 2021

DESCRIPTION:

Description:

Annual Hours of Operation: 8760.0 hours/yr

WET GAS:

Temperature: 112.00 deg. F
Pressure: 834.70 psig
Wet Gas Water Content: Saturated

Component	Conc. (vol %)
Carbon Dioxide	0.2550
Nitrogen	4.4110
Methane	87.2070
Ethane	4.6480
Propane	1.7660
Isobutane	0.3080
n-Butane	0.5760
Isopentane	0.1770
n-Pentane	0.1790
n-Hexane	0.0968
Cyclohexane	0.0020
Other Hexanes	0.1900
Heptanes	0.1190
Methylcyclohexane	0.0439
Ethylbenzene	0.0010
Xylenes	0.0020
C8+ Heavies	0.0249

DRY GAS:

Flow Rate: 30.0 MMSCF/day
Water Content: 7.0 lbs. H2O/MMSCF

LEAN GLYCOL:

Glycol Type: TEG
Water Content: 1.5 wt% H2O
Recirculation Ratio: 3.0 gal/lb H2O

PUMP:

Glycol Pump Type: Electric/Pneumatic

REGENERATOR OVERHEADS CONTROL DEVICE:

Control Device: Condenser
Temperature: 80.0 deg. F
Pressure: 16.7 psia

Control Device: Combustion Device
Destruction Efficiency: 95.0 %
Excess Oxygen: 0.0 %
Ambient Air Temperature: 70.0 deg. F

GRI-GLYCalc VERSION 4.0 - AGGREGATE CALCULATIONS REPORT

Case Name: Bitter Lake

File Name: C:\Users\Joseline Laureano\OneDrive - Resolute Compliance, LLC\Env\Projects\Env-IACX-Bitter Lake CS
NSR-0005\Simulations\updated.ddf

Date: August 24, 2021

DESCRIPTION:

Description:

Annual Hours of Operation: 8760.0 hours/yr

EMISSIONS REPORTS:

CONTROLLED REGENERATOR EMISSIONS

Component	lbs/hr	lbs/day	tons/yr
Methane	0.3769	9.046	1.6508
Ethane	0.1147	2.752	0.5023
Propane	0.1023	2.455	0.4481
Isobutane	0.0310	0.744	0.1358
n-Butane	0.0739	1.774	0.3237
Isopentane	0.0260	0.625	0.1141
n-Pentane	0.0305	0.732	0.1337
n-Hexane	0.0251	0.601	0.1097
Cyclohexane	0.0019	0.047	0.0085
Other Hexanes	0.0429	1.030	0.1880
Heptanes	0.0370	0.887	0.1619
Methylcyclohexane	0.0362	0.868	0.1584
Ethylbenzene	0.0042	0.100	0.0182
Xylenes	0.0080	0.193	0.0352
C8+ Heavies	0.0004	0.010	0.0018
Total Emissions	0.9110	21.864	3.9902
Total Hydrocarbon Emissions	0.9110	21.864	3.9902
Total VOC Emissions	0.4194	10.067	1.8372
Total HAP Emissions	0.0372	0.894	0.1631
Total BTEX Emissions	0.0122	0.293	0.0534

UNCONTROLLED REGENERATOR EMISSIONS

Component	lbs/hr	lbs/day	tons/yr
Methane	7.5441	181.058	33.0431
Ethane	2.3013	55.230	10.0795
Propane	2.0802	49.926	9.1114
Isobutane	0.6426	15.423	2.8146
n-Butane	1.5536	37.286	6.8047
Isopentane	0.5831	13.995	2.5540
n-Pentane	0.7508	18.019	3.2885
n-Hexane	0.7671	18.411	3.3600
Cyclohexane	0.0672	1.614	0.2945
Other Hexanes	1.1666	27.997	5.1095
Heptanes	1.9334	46.401	8.4682
Methylcyclohexane	1.8514	44.434	8.1093
Ethylbenzene	0.6009	14.422	2.6320
Xylenes	1.6285	39.084	7.1328
C8+ Heavies	2.9352	70.445	12.8563
Total Emissions	26.4061	633.745	115.6585
Total Hydrocarbon Emissions	26.4061	633.745	115.6585
Total VOC Emissions	16.5607	397.457	72.5359
Total HAP Emissions	2.9965	71.917	13.1248
Total BTEX Emissions	2.2294	53.505	9.7648

EQUIPMENT REPORTS:

CONDENSER AND COMBUSTION DEVICE

Condenser Outlet Temperature: 80.00 deg. F
 Condenser Pressure: 16.70 psia
 Condenser Duty: 7.71e-002 MM BTU/hr
 Hydrocarbon Recovery: 0.66 bbls/day
 Produced Water: 7.47 bbls/day
 Ambient Temperature: 70.00 deg. F
 Excess Oxygen: 0.00 %
 Combustion Efficiency: 95.00 %
 Supplemental Fuel Requirement: 7.71e-002 MM BTU/hr

Component	Emitted	Destroyed
Methane	5.00%	95.00%
Ethane	4.98%	95.02%
Propane	4.92%	95.08%

Isobutane	4.83%	95.17%
n-Butane	4.76%	95.24%
Isopentane	4.47%	95.53%
n-Pentane	4.06%	95.94%
n-Hexane	3.27%	96.73%
Cyclohexane	2.88%	97.12%
Other Hexanes	3.68%	96.32%
Heptanes	1.91%	98.09%
Methylcyclohexane	1.95%	98.05%
Ethylbenzene	0.69%	99.31%
Xylenes	0.49%	99.51%
C8+ Heavies	0.01%	99.99%

ABSORBER

Calculated Absorber Stages: 1.26
 Specified Dry Gas Dew Point: 7.00 lbs. H2O/MMSCF
 Temperature: 112.0 deg. F
 Pressure: 834.7 psig
 Dry Gas Flow Rate: 30.0000 MMSCF/day
 Glycol Losses with Dry Gas: 0.5614 lb/hr
 Wet Gas Water Content: Saturated
 Calculated Wet Gas Water Content: 94.32 lbs. H2O/MMSCF
 Specified Lean Glycol Recirc. Ratio: 3.00 gal/lb H2O

Component	Remaining in Dry Gas	Absorbed in Glycol
Water	7.41%	92.59%
Carbon Dioxide	99.80%	0.20%
Nitrogen	99.98%	0.02%
Methane	99.98%	0.02%
Ethane	99.95%	0.05%
Propane	99.92%	0.08%
Isobutane	99.89%	0.11%
n-Butane	99.86%	0.14%
Isopentane	99.86%	0.14%
n-Pentane	99.82%	0.18%
n-Hexane	99.72%	0.28%
Cyclohexane	98.79%	1.21%
Other Hexanes	99.78%	0.22%
Heptanes	99.51%	0.49%
Methylcyclohexane	98.70%	1.30%
Ethylbenzene	82.82%	17.18%
Xylenes	76.72%	23.28%
C8+ Heavies	97.90%	2.10%

REGENERATOR

No Stripping Gas used in regenerator.

Component	Remaining in Glycol	Distilled Overhead
Water	29.64%	70.36%
Carbon Dioxide	0.00%	100.00%
Nitrogen	0.00%	100.00%
Methane	0.00%	100.00%
Ethane	0.00%	100.00%
Propane	0.00%	100.00%
Isobutane	0.00%	100.00%
n-Butane	0.00%	100.00%
Isopentane	0.50%	99.50%
n-Pentane	0.50%	99.50%
n-Hexane	0.50%	99.50%
Cyclohexane	3.20%	96.80%
Other Hexanes	1.00%	99.00%
Heptanes	0.50%	99.50%
Methylcyclohexane	4.00%	96.00%
Ethylbenzene	10.41%	89.59%
Xylenes	12.93%	87.07%
C8+ Heavies	12.02%	87.98%

STREAM REPORTS:

WET GAS STREAM

Temperature: 112.00 deg. F
Pressure: 849.40 psia
Flow Rate: 1.25e+006 scfh

Component	Conc. (vol%)	Loading (lb/hr)
Water	1.99e-001	1.18e+002
Carbon Dioxide	2.54e-001	3.70e+002
Nitrogen	4.40e+000	4.07e+003
Methane	8.70e+001	4.61e+004

Ethane	4.64e+000	4.61e+003
Propane	1.76e+000	2.57e+003
Isobutane	3.07e-001	5.90e+002
n-Butane	5.75e-001	1.10e+003
Isopentane	1.77e-001	4.21e+002
n-Pentane	1.79e-001	4.26e+002
n-Hexane	9.66e-002	2.75e+002
Cyclohexane	2.00e-003	5.55e+000
Other Hexanes	1.90e-001	5.40e+002
Heptanes	1.19e-001	3.93e+002
Methylcyclohexane	4.38e-002	1.42e+002
Ethylbenzene	9.98e-004	3.50e+000
Xylenes	2.00e-003	7.00e+000
C8+ Heavies	2.48e-002	1.40e+002

Total Components	100.00	6.19e+004

DRY GAS STREAM

Temperature: 112.00 deg. F
 Pressure: 849.40 psia
 Flow Rate: 1.25e+006 scfh

Component	Conc. (vol%)	Loading (lb/hr)

Water	1.47e-002	8.75e+000
Carbon Dioxide	2.54e-001	3.69e+002
Nitrogen	4.41e+000	4.07e+003
Methane	8.72e+001	4.61e+004
Ethane	4.65e+000	4.60e+003
Propane	1.76e+000	2.56e+003
Isobutane	3.08e-001	5.89e+002
n-Butane	5.75e-001	1.10e+003
Isopentane	1.77e-001	4.20e+002
n-Pentane	1.79e-001	4.25e+002
n-Hexane	9.65e-002	2.74e+002
Cyclohexane	1.98e-003	5.48e+000
Other Hexanes	1.90e-001	5.38e+002
Heptanes	1.18e-001	3.91e+002
Methylcyclohexane	4.33e-002	1.40e+002
Ethylbenzene	8.28e-004	2.90e+000
Xylenes	1.53e-003	5.37e+000
C8+ Heavies	2.44e-002	1.37e+002

Total Components	100.00	6.17e+004

LEAN GLYCOL STREAM

Temperature: 112.00 deg. F

Flow Rate: 5.46e+000 gpm

Component	Conc. (wt%)	Loading (lb/hr)
-----------	----------------	--------------------

TEG	9.85e+001	3.03e+003
Water	1.50e+000	4.61e+001
Carbon Dioxide	2.43e-012	7.47e-011
Nitrogen	2.36e-012	7.26e-011
Methane	8.25e-018	2.53e-016
Ethane	3.53e-008	1.09e-006
Propane	2.75e-009	8.47e-008
Isobutane	6.27e-010	1.93e-008
n-Butane	1.25e-009	3.85e-008
Isopentane	9.53e-005	2.93e-003
n-Pentane	1.23e-004	3.77e-003
n-Hexane	1.25e-004	3.85e-003
Cyclohexane	7.23e-005	2.22e-003
Other Hexanes	3.83e-004	1.18e-002
Heptanes	3.16e-004	9.71e-003
Methylcyclohexane	2.51e-003	7.71e-002
Ethylbenzene	2.27e-003	6.98e-002
Xylenes	7.87e-003	2.42e-001
C8+ Heavies	1.31e-002	4.01e-001

Total Components	100.00	3.07e+003
------------------	--------	-----------

RICH GLYCOL STREAM

Temperature: 112.00 deg. F

Pressure: 849.40 psia

Flow Rate: 5.73e+000 gpm

NOTE: Stream has more than one phase.

Component	Conc. (wt%)	Loading (lb/hr)
-----------	----------------	--------------------

TEG	9.43e+001	3.02e+003
Water	4.85e+000	1.56e+002
Carbon Dioxide	2.33e-002	7.47e-001
Nitrogen	2.26e-002	7.26e-001
Methane	2.35e-001	7.54e+000

Ethane 7.17e-002 2.30e+000
Propane 6.48e-002 2.08e+000
Isobutane 2.00e-002 6.43e-001
n-Butane 4.84e-002 1.55e+000
Isopentane 1.83e-002 5.86e-001

n-Pentane 2.35e-002 7.55e-001
n-Hexane 2.40e-002 7.71e-001
Cyclohexane 2.16e-003 6.95e-002
Other Hexanes 3.67e-002 1.18e+000
Heptanes 6.06e-002 1.94e+000

Methylcyclohexane 6.01e-002 1.93e+000
Ethylbenzene 2.09e-002 6.71e-001
Xylenes 5.83e-002 1.87e+000
C8+ Heavies 1.04e-001 3.34e+000

Total Components 100.00 3.21e+003

REGENERATOR OVERHEADS STREAM

Temperature: 212.00 deg. F
Pressure: 14.70 psia
Flow Rate: 2.61e+003 scfh

Component	Conc. (vol%)	Loading (lb/hr)
-----------	-----------------	--------------------

Water 8.85e+001 1.09e+002
Carbon Dioxide 2.47e-001 7.47e-001
Nitrogen 3.77e-001 7.26e-001
Methane 6.85e+000 7.54e+000
Ethane 1.11e+000 2.30e+000

Propane 6.87e-001 2.08e+000
Isobutane 1.61e-001 6.43e-001
n-Butane 3.89e-001 1.55e+000
Isopentane 1.18e-001 5.83e-001
n-Pentane 1.52e-001 7.51e-001

n-Hexane 1.30e-001 7.67e-001
Cyclohexane 1.16e-002 6.72e-002
Other Hexanes 1.97e-001 1.17e+000
Heptanes 2.81e-001 1.93e+000
Methylcyclohexane 2.75e-001 1.85e+000

Ethylbenzene 8.24e-002 6.01e-001
Xylenes 2.23e-001 1.63e+000
C8+ Heavies 2.51e-001 2.94e+000

Total Components 100.00 1.37e+002

CONDENSER PRODUCED WATER STREAM

Temperature: 80.00 deg. F

Flow Rate: 2.18e-001 gpm

Component	Conc. (wt%)	Loading (lb/hr)	(ppm)
-----------	----------------	--------------------	-------

Water	1.00e+002	1.09e+002	999870.
Carbon Dioxide	3.66e-003	3.99e-003	37.
Nitrogen	7.08e-005	7.72e-005	1.
Methane	1.56e-003	1.71e-003	16.
Ethane	6.18e-004	6.74e-004	6.
Propane	3.84e-004	4.18e-004	4.
Isobutane	6.67e-005	7.27e-005	1.
n-Butane	2.21e-004	2.41e-004	2.
Isopentane	5.85e-005	6.38e-005	1.
n-Pentane	7.60e-005	8.29e-005	1.
n-Hexane	5.64e-005	6.15e-005	1.
Cyclohexane	2.84e-005	3.10e-005	0.
Other Hexanes	7.52e-005	8.19e-005	1.
Heptanes	4.88e-005	5.32e-005	0.
Methylcyclohexane	2.63e-004	2.86e-004	3.
Ethylbenzene	1.53e-003	1.67e-003	15.
Xylenes	4.33e-003	4.72e-003	43.
C8+ Heavies	2.09e-007	2.28e-007	0.
Total Components	100.00	1.09e+002	1000000.

CONDENSER RECOVERED OIL STREAM

Temperature: 80.00 deg. F

Flow Rate: 1.92e-002 gpm

Component	Conc. (wt%)	Loading (lb/hr)
-----------	----------------	--------------------

Water	1.93e-002	1.58e-003
Carbon Dioxide	1.14e-002	9.30e-004
Nitrogen	2.28e-003	1.86e-004
Methane	5.27e-002	4.31e-003
Ethane	8.80e-002	7.19e-003
Propane	4.11e-001	3.36e-002
Isobutane	2.73e-001	2.23e-002
n-Butane	9.20e-001	7.52e-002
Isopentane	7.59e-001	6.21e-002

n-Pentane	1.72e+000	1.40e-001
n-Hexane	3.25e+000	2.66e-001
Cyclohexane	3.48e-001	2.84e-002
Other Hexanes	3.77e+000	3.08e-001
Heptanes	1.46e+001	1.19e+000
Methylcyclohexane	1.38e+001	1.13e+000
Ethylbenzene	6.31e+000	5.16e-001
Xylenes	1.79e+001	1.46e+000
C8+ Heavies	3.58e+001	2.93e+000

Total Components	100.00	8.18e+000

CONDENSER VENT STREAM

Temperature: 80.00 deg. F
 Pressure: 16.70 psia
 Flow Rate: 2.82e+002 scfh

Component	Conc. (vol%)	Loading (lb/hr)

Water	3.09e+000	4.13e-001
Carbon Dioxide	2.27e+000	7.42e-001
Nitrogen	3.48e+000	7.26e-001
Methane	6.32e+001	7.54e+000
Ethane	1.03e+001	2.29e+000
Propane	6.24e+000	2.05e+000
Isobutane	1.44e+000	6.20e-001
n-Butane	3.42e+000	1.48e+000
Isopentane	9.71e-001	5.21e-001
n-Pentane	1.14e+000	6.10e-001
n-Hexane	7.82e-001	5.01e-001
Cyclohexane	6.20e-002	3.88e-002
Other Hexanes	1.34e+000	8.58e-001
Heptanes	9.92e-001	7.39e-001
Methylcyclohexane	9.91e-001	7.24e-001
Ethylbenzene	1.05e-001	8.30e-002
Xylenes	2.04e-001	1.61e-001
C8+ Heavies	6.54e-003	8.28e-003

Total Components	100.00	2.01e+001

COMBUSTION DEVICE OFF GAS STREAM

Temperature: 1000.00 deg. F

Pressure: 14.70 psia
Flow Rate: 1.29e+001 scfh

Component	Conc. (vol%)	Loading (lb/hr)

Methane	6.93e+001	3.77e-001
Ethane	1.13e+001	1.15e-001
Propane	6.85e+000	1.02e-001
Isobutane	1.57e+000	3.10e-002
n-Butane	3.75e+000	7.39e-002
Isopentane	1.07e+000	2.60e-002
n-Pentane	1.25e+000	3.05e-002
n-Hexane	8.58e-001	2.51e-002
Cyclohexane	6.80e-002	1.94e-003
Other Hexanes	1.47e+000	4.29e-002
Heptanes	1.09e+000	3.70e-002
Methylcyclohexane	1.09e+000	3.62e-002
Ethylbenzene	1.15e-001	4.15e-003
Xylenes	2.23e-001	8.04e-003
C8+ Heavies	7.17e-003	4.14e-004

Total Components	100.00	9.11e-001

Section 8

Map(s)

A map such as a 7.5 minute topographic quadrangle showing the exact location of the source. The map shall also include the following:

The UTM or Longitudinal coordinate system on both axes	An indicator showing which direction is north
A minimum radius around the plant of 0.8km (0.5 miles)	Access and haul roads
Topographic features of the area	Facility property boundaries
The name of the map	The area which will be restricted to public access
A graphical scale	

Section 9

Proof of Public Notice

(for NSR applications submitting under 20.2.72 or 20.2.74 NMAC)

(This proof is required by: 20.2.72.203.A.14 NMAC “Documentary Proof of applicant’s public notice”)

X I have read the AQB “Guidelines for Public Notification for Air Quality Permit Applications”

This document provides detailed instructions about public notice requirements for various permitting actions. It also provides public notice examples and certification forms. Material mistakes in the public notice will require a re-notice before issuance of the permit.

Unless otherwise allowed elsewhere in this document, the following items document proof of the applicant’s Public Notification. Please include this page in your proof of public notice submittal with checkmarks indicating which documents are being submitted with the application.

New Permit and **Significant Permit Revision** public notices must include all items in this list.

Technical Revision public notices require only items 1, 5, 9, and 10.

Per the Guidelines for Public Notification document mentioned above, include:

1. **X** A copy of the certified letter receipts with post marks (20.2.72.203.B NMAC)
 2. **X** A list of the places where the public notice has been posted in at least four publicly accessible and conspicuous places, including the proposed or existing facility entrance. (e.g: post office, library, grocery, etc.)
 3. **X** A copy of the property tax record (20.2.72.203.B NMAC).
 4. **X** A sample of the letters sent to the owners of record.
 5. **X** A sample of the letters sent to counties, municipalities, and Indian tribes.
 6. **X** A sample of the public notice posted and a verification of the local postings.
 7. **X** A table of the noticed citizens, counties, municipalities and tribes and to whom the notices were sent in each group.
 8. **X** A copy of the public service announcement (PSA) sent to a local radio station and documentary proof of submittal.
 9. **X** A copy of the classified or legal ad including the page header (date and newspaper title) or its affidavit of publication stating the ad date, and a copy of the ad. When appropriate, this ad shall be printed in both English and Spanish.
 10. **X** A copy of the display ad including the page header (date and newspaper title) or its affidavit of publication stating the ad date, and a copy of the ad. When appropriate, this ad shall be printed in both English and Spanish.
 11. **X** A map with a graphic scale showing the facility boundary and the surrounding area in which owners of record were notified by mail. This is necessary for verification that the correct facility boundary was used in determining distance for notifying land owners of record.
-

7020 3160 0000 4931 8628

U.S. Postal Service™
CERTIFIED MAIL® RECEIPT
 Domestic Mail Only

For delivery information, visit our website at www.usps.com®.

Roswell, NM 88202

OFFICIAL USE

Certified Mail Fee	\$3.75	0189 06	Postmark Here
Extra Services & Fees (check box, add fee as appropriate)	\$3.05		
<input type="checkbox"/> Return Receipt (hardcopy)	\$0.00		
<input type="checkbox"/> Return Receipt (electronic)	\$0.00		
<input type="checkbox"/> Certified Mail Restricted Delivery	\$0.00		
<input type="checkbox"/> Adult Signature Required	\$0.00		
<input type="checkbox"/> Adult Signature Restricted Delivery	\$0.00		
Postage	\$0.58		
Total Postage and Fees	\$7.38		09/03/2021
Sent To Hondo Resources Inc.			
Street and Apt. No., or PO Box No. PO Box 2623			
City, State, ZIP+4® Roswell, NM, 88202			
PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions			

7020 3160 0000 4931 8635

U.S. Postal Service™
CERTIFIED MAIL® RECEIPT
 Domestic Mail Only

For delivery information, visit our website at www.usps.com®.

Roswell, NM 88201

OFFICIAL USE

Certified Mail Fee	\$3.75	0189 06	Postmark Here
Extra Services & Fees (check box, add fee as appropriate)	\$3.05		
<input type="checkbox"/> Return Receipt (hardcopy)	\$0.00		
<input type="checkbox"/> Return Receipt (electronic)	\$0.00		
<input type="checkbox"/> Certified Mail Restricted Delivery	\$0.00		
<input type="checkbox"/> Adult Signature Required	\$0.00		
<input type="checkbox"/> Adult Signature Restricted Delivery	\$0.00		
Postage	\$0.58		
Total Postage and Fees	\$7.38		09/03/2021
Sent To U.S. Bureau of Land Management			
Street and Apt. No., or PO Box No. 2909 W. 2nd St.			
City, State, ZIP+4® Roswell, NM, 88201			
PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions			

7020 3160 0000 4931 8611

U.S. Postal Service™
CERTIFIED MAIL® RECEIPT
 Domestic Mail Only

For delivery information, visit our website at www.usps.com®.

Roswell, NM 88201

OFFICIAL USE

Certified Mail Fee	\$3.75	0189 06	Postmark Here
Extra Services & Fees (check box, add fee as appropriate)	\$3.05		
<input type="checkbox"/> Return Receipt (hardcopy)	\$0.00		
<input type="checkbox"/> Return Receipt (electronic)	\$0.00		
<input type="checkbox"/> Certified Mail Restricted Delivery	\$0.00		
<input type="checkbox"/> Adult Signature Required	\$0.00		
<input type="checkbox"/> Adult Signature Restricted Delivery	\$0.00		
Postage	\$0.58		
Total Postage and Fees	\$7.38		09/03/2021
Sent To City Clerks Office			
Street and Apt. No., or PO Box No. 425 N. Richardson			
City, State, ZIP+4® Roswell, NM, 88201			
PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions			

7020 3160 0000 4931 8642

U.S. Postal Service™
CERTIFIED MAIL® RECEIPT
 Domestic Mail Only

For delivery information, visit our website at www.usps.com®.

Roswell, NM 88201

OFFICIAL USE

Certified Mail Fee	\$3.75	0189 06	Postmark Here
Extra Services & Fees (check box, add fee as appropriate)	\$3.05		
<input type="checkbox"/> Return Receipt (hardcopy)	\$0.00		
<input type="checkbox"/> Return Receipt (electronic)	\$0.00		
<input type="checkbox"/> Certified Mail Restricted Delivery	\$0.00		
<input type="checkbox"/> Adult Signature Required	\$0.00		
<input type="checkbox"/> Adult Signature Restricted Delivery	\$0.00		
Postage	\$0.58		
Total Postage and Fees	\$7.38		09/03/2021
Sent To Gary L. Key			
Street and Apt. No., or PO Box No. 1012 E. 2nd St.			
City, State, ZIP+4® Roswell, NM, 88201			
PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions			

7020 3160 0000 4931 8604

U.S. Postal Service™
CERTIFIED MAIL® RECEIPT
 Domestic Mail Only

For delivery information, visit our website at www.usps.com®.

Roswell, NM 88203

OFFICIAL USE

Certified Mail Fee	\$3.75	0189 06	Postmark Here
Extra Services & Fees (check box, add fee as appropriate)	\$3.05		
<input type="checkbox"/> Return Receipt (hardcopy)	\$0.00		
<input type="checkbox"/> Return Receipt (electronic)	\$0.00		
<input type="checkbox"/> Certified Mail Restricted Delivery	\$0.00		
<input type="checkbox"/> Adult Signature Required	\$0.00		
<input type="checkbox"/> Adult Signature Restricted Delivery	\$0.00		
Postage	\$0.58		
Total Postage and Fees	\$7.38		09/03/2021
Sent To Chaves County Manager			
Street and Apt. No., or PO Box No. 1 St Mary's Pl.			
City, State, ZIP+4® Roswell, NM, 88203			
PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions			

SENDER: COMPLETE THIS SECTION

- Complete items 1, 2, and 3.
- Print your name and address on the reverse so that we can return the card to you.
- Attach this card to the back of the mailpiece, or on the front if space permits.

1. Article Addressed to:

Hondo Resources Inc.
P.O. Box 2623
Roswell, NM 88202



9590 9402 5644 9308 1072 21

2. Article Number (Transfer from service label)

7020 3160 0000 4931 8628

PS Form 3811, July 2015 PSN 7530-02-000-9053

Domestic Return Receipt

COMPLETE THIS SECTION ON DELIVERY

A. Signature

X *Susan Y. Held* ☐ Agent
☒ Addressee

B. Received by (Printed Name)

Susan Y. Held C. Date of Delivery

D. Is delivery address different from item 1? ☐ Yes
If YES, enter delivery address below: ☐ No

3. Service Type

- ☐ Adult Signature
- ☐ Adult Signature Restricted Delivery
- ☒ Certified Mail®
- ☐ Certified Mail Restricted Delivery
- ☐ Collect on Delivery
- ☐ Collect on Delivery Restricted Delivery

☐ Priority Mail Express®


- ☐ Registered Mail™
- ☐ Registered Mail Restricted Delivery
- ☐ Return Receipt for Merchandise
- ☐ Signature Confirmation™
- ☐ Signature Confirmation Restricted Delivery

SENDER: COMPLETE THIS SECTION

- Complete items 1, 2, and 3.
- Print your name and address on the reverse so that we can return the card to you.
- Attach this card to the back of the mailpiece, or on the front if space permits.

1. Article Addressed to:

City Clerks Office
425 N. Richardson
Roswell, NM 88201



9590 9402 5644 9308 1072 14

2. Article Number (Transfer from service label)

7020 3160 0000 4931 8611

PS Form 3811, July 2015 PSN 7530-02-000-9053

Domestic Return Receipt

COMPLETE THIS SECTION ON DELIVERY

A. Signature

X *Cheryl E. Roswell* ☐ Agent
☐ Addressee

B. Received by (Printed Name)

Cheryl E. Roswell C. Date of Delivery

D. Is delivery address different from item 1? ☒ Yes
If YES, enter delivery address below: ☐ No

3. Service Type

- ☐ Adult Signature
- ☐ Adult Signature Restricted Delivery
- ☒ Certified Mail®
- ☐ Certified Mail Restricted Delivery
- ☐ Collect on Delivery
- ☐ Collect on Delivery Restricted Delivery

☐ Priority Mail Express®

- ☐ Registered Mail™
- ☐ Registered Mail Restricted Delivery
- ☐ Return Receipt for Merchandise
- ☐ Signature Confirmation™
- ☐ Signature Confirmation Restricted Delivery

SENDER: COMPLETE THIS SECTION

- Complete items 1, 2, and 3.
- Print your name and address on the reverse so that we can return the card to you.
- Attach this card to the back of the mailpiece, or on the front if space permits.

1. Article Addressed to:

Gary L. Key
1012 E. 2nd St
Roswell, NM 88201



9590 9402 5644 9308 1072 38

2. Article Number (Transfer from service label)

7020 3160 0000 4931 8642

PS Form 3811, July 2015 PSN 7530-02-000-9053

Domestic Return Receipt

COMPLETE THIS SECTION ON DELIVERY

A. Signature

X *Gary L. Key* ☐ Agent
☐ Addressee

B. Received by (Printed Name)

Gary L. Key C. Date of Delivery

D. Is delivery address different from item 1? ☐ Yes
If YES, enter delivery address below: ☐ No

3. Service Type

- ☐ Adult Signature
- ☐ Adult Signature Restricted Delivery
- ☒ Certified Mail®
- ☐ Certified Mail Restricted Delivery
- ☐ Collect on Delivery
- ☐ Collect on Delivery Restricted Delivery

☐ Priority Mail Express®

- ☐ Registered Mail™
- ☐ Registered Mail Restricted Delivery
- ☐ Return Receipt for Merchandise
- ☐ Signature Confirmation™
- ☐ Signature Confirmation Restricted Delivery

SENDER: COMPLETE THIS SECTION

- Complete items 1, 2, and 3.
- Print your name and address on the reverse so that we can return the card to you.
- Attach this card to the back of the mailpiece, or on the front if space permits.

1. Article Addressed to:

Chaves County Manager
1 St Mary's Pl
Roswell, NM 88203



9590 9402 5644 9308 1072 07

2. Article Number (Transfer from service label)

7020 3160 0000 4931 8604

PS Form 3811, July 2015 PSN 7530-02-000-9053

COMPLETE THIS SECTION ON DELIVERY

A. Signature

X

☐ Agent☐ Addressee

B. Received by (Printed Name)

C. Date of Delivery

D. Is delivery address different from item 1? ☐ Yes
If YES, enter delivery address below: ☐ No

3. Service Type

☐ Adult Signature☐ Adult Signature Restricted Delivery☒ Certified Mail®☐ Certified Mail Restricted Delivery☐ Collect on Delivery☐ Collect on Delivery Restricted Delivery☐ Priority Mail Express®☐ Registered Mail™☐ Registered Mail Restricted Delivery☐ Return Receipt for Merchandise☐ Signature Confirmation™☐ Signature Confirmation Restricted Delivery☐ Restricted Delivery

Domestic Return Receipt

SENDER: COMPLETE THIS SECTION

- Complete items 1, 2, and 3.
- Print your name and address on the reverse so that we can return the card to you.
- Attach this card to the back of the mailpiece, or on the front if space permits.

1. Article Addressed to:

U.S. Bureau of Land Management
Roswell Field Office
2809 W. 2nd St
Roswell, NM 88201



9590 9402 5644 9308 1072 45

2. Article Number (Transfer from service label)

7020 3160 0000 4931 8635

PS Form 3811, July 2015 PSN 7530-02-000-9053

COMPLETE THIS SECTION ON DELIVERY

A. Signature

X

☐ Agent☐ Addressee

B. Received by (Printed Name)

C. Date of Delivery

D. Is delivery address different from item 1? ☐ Yes
If YES, enter delivery address below: ☐ No

3. Service Type

☐ Adult Signature☐ Adult Signature Restricted Delivery☒ Certified Mail®☐ Certified Mail Restricted Delivery☐ Collect on Delivery☐ Collect on Delivery Restricted Delivery☐ Priority Mail Express®☐ Registered Mail™☐ Registered Mail Restricted Delivery☐ Return Receipt for Merchandise☐ Signature Confirmation™☐ Signature Confirmation Restricted Delivery☐ Restricted Delivery

Domestic Return Receipt

List of Places Where Public Notice was Posted

Roswell Fire Station #4

- Located at 10 E Challenger St, Roswell, NM 88203

Roswell Public Library

- Located at 301 N Pennsylvania Ave, Roswell, NM 882010

Roswell Public Health Division

- Located at 200 E Chisum St, Roswell, NM 88203

Bitter Lake Compressor Station

- Located at 33 deg, 33 min, 11.001 sec and longitude -104 deg, 23 min, 26.9988 sec

October 11, 2021

CERTIFIED MAIL 7020 3160 0000 4931 8642

RETURN RECEIPT REQUESTED (certified mail is required, **return receipt is optional**)

Dear **Gary L. Key**

IACX Roswell LLC announces its application submittal to the New Mexico Environment Department for an air quality permit for the **modification** of its **natural gas compressor station** facility. The expected date of application submittal to the Air Quality Bureau is **August 27, 2021**.

The exact location for the proposed facility known as **Bitter Lake Compressor Station**, is at latitude **33** deg, **33** min, **11.001** sec and longitude **-104** deg, **23** min, **26.9988** sec. The approximate location of this facility is **1.6** miles **south of Salt Creek Wilderness** in Chaves County.

The proposed **modification** consists of transitioning the GCP O&G permit to an NSR permit due to the proximity to the Salt Creek Wilderness.

The estimated maximum quantities of any regulated air contaminant will be as follows in pound per hour (pph) and tons per year (tpy) and may change slightly during the course of the Department's review:

Pollutant:	Pounds per hour	Tons per year
PM 10	1.13 pph	4.64 tpy
PM 2.5	1.00 pph	4.41 tpy
Sulfur Dioxide (SO ₂)	0.34 pph	1.53 tpy
Nitrogen Oxides (NO _x)	18.33 pph	80.23 tpy
Carbon Monoxide (CO)	17.63 pph	77.27 tpy
Volatile Organic Compounds (VOC)	21.48 pph	52.33 tpy
Total sum of all Hazardous Air Pollutants (HAPs)	1.94 pph	8.58 tpy
Toxic Air Pollutant (TAP)	pph	tpy
Green House Gas Emissions as Total CO ₂ e	n/a	tpy

The standard and maximum operating schedules of the facility will be from 12:00 a.m. to 12:00 p.m. 7 days a week and a maximum of 52 weeks per year.

The owner and/or operator of the Facility is: **Tony Hines; IACX Roswell LLC; 5001 LBJ Freeway, Suite 300, Dallas, TX 75244**

If you have any comments about the construction or operation of this facility, and you want your comments to be made as part of the permit review process, you must submit your comments in writing to this address: Permit Programs Manager; New Mexico Environment Department; Air

Quality Bureau; 525 Camino de los Marquez, Suite 1; Santa Fe, New Mexico; 87505-1816; (505) 476-4300; 1 800 224-7009; https://www.env.nm.gov/aqb/permit/aqb_draft_permits.html. Other comments and questions may be submitted verbally.

Please refer to the company name and facility name, or send a copy of this notice along with your comments, since the Department may have not yet received the permit application. Please include a legible return mailing address with your comments. Once the Department has performed a preliminary review of the application and its air quality impacts, the Department's notice will be published in the legal section of a newspaper circulated near the facility location.

Atención

Este es un aviso de la oficina de Calidad del Aire del Departamento del Medio Ambiente de Nuevo México, acerca de las emisiones producidas por un establecimiento en esta área. Si usted desea información en español, por favor comuníquese con esa oficina al teléfono 505-476-5557.

Sincerely,

IACX Roswell LLC

5001 LBJ Freeway, Suite 300, Dallas, TX 75244

Notice of Non-Discrimination

NMED does not discriminate on the basis of race, color, national origin, disability, age or sex in the administration of its programs or activities, as required by applicable laws and regulations. NMED is responsible for coordination of compliance efforts and receipt of inquiries concerning non-discrimination requirements implemented by 40 C.F.R. Part 7, including Title VI of the Civil Rights Act of 1964, as amended; Section 504 of the Rehabilitation Act of 1973; the Age Discrimination Act of 1975, Title IX of the Education Amendments of 1972, and Section 13 of the Federal Water Pollution Control Act Amendments of 1972. If you have any questions about this notice or any of NMED's non-discrimination programs, policies or procedures, or if you believe that you have been discriminated against with respect to a NMED program or activity, you may contact: Kathryn Becker, Non-Discrimination Coordinator, NMED, 1190 St. Francis Dr., Suite N4050, P.O. Box 5469, Santa Fe, NM 87502, (505) 827-2855, nd.coordinator@state.nm.us. You may also visit our website at <https://www.env.nm.gov/non-employee-discrimination-complaint-page/> to learn how and where to file a complaint of discrimination.

October 11, 2021

CERTIFIED MAIL 7020 3160 0000 4931 8628

RETURN RECEIPT REQUESTED (certified mail is required, **return receipt is optional**)

Dear **Hondo Resources Inc.**

IACX Roswell LLC announces its application submittal to the New Mexico Environment Department for an air quality permit for the **modification** of its **natural gas compressor station** facility. The expected date of application submittal to the Air Quality Bureau is **August 27, 2021**.

The exact location for the proposed facility known as **Bitter Lake Compressor Station**, is at latitude **33** deg, **33** min, **11.001** sec and longitude **-104** deg, **23** min, **26.9988** sec. The approximate location of this facility is **1.6** miles **south of Salt Creek Wilderness** in Chaves County.

The proposed **modification** consists of transitioning the GCP O&G permit to an NSR permit due to the proximity to the Salt Creek Wilderness.

The estimated maximum quantities of any regulated air contaminant will be as follows in pound per hour (pph) and tons per year (tpy) and may change slightly during the course of the Department's review:

Pollutant:	Pounds per hour	Tons per year
PM 10	1.13 pph	4.64 tpy
PM 2.5	1.00 pph	4.41 tpy
Sulfur Dioxide (SO ₂)	0.34 pph	1.53 tpy
Nitrogen Oxides (NO _x)	18.33 pph	80.23 tpy
Carbon Monoxide (CO)	17.63 pph	77.27 tpy
Volatile Organic Compounds (VOC)	21.48 pph	52.33 tpy
Total sum of all Hazardous Air Pollutants (HAPs)	1.94 pph	8.58 tpy
Toxic Air Pollutant (TAP)	pph	tpy
Green House Gas Emissions as Total CO ₂ e	n/a	tpy

The standard and maximum operating schedules of the facility will be from 12:00 a.m. to 12:00 p.m. 7 days a week and a maximum of 52 weeks per year.

The owner and/or operator of the Facility is: **Tony Hines; IACX Roswell LLC; 5001 LBJ Freeway, Suite 300, Dallas, TX 75244**

If you have any comments about the construction or operation of this facility, and you want your comments to be made as part of the permit review process, you must submit your comments in writing to this address: Permit Programs Manager; New Mexico Environment Department; Air

Quality Bureau; 525 Camino de los Marquez, Suite 1; Santa Fe, New Mexico; 87505-1816; (505) 476-4300; 1 800 224-7009; https://www.env.nm.gov/aqb/permit/aqb_draft_permits.html. Other comments and questions may be submitted verbally.

Please refer to the company name and facility name, or send a copy of this notice along with your comments, since the Department may have not yet received the permit application. Please include a legible return mailing address with your comments. Once the Department has performed a preliminary review of the application and its air quality impacts, the Department's notice will be published in the legal section of a newspaper circulated near the facility location.

Atención

Este es un aviso de la oficina de Calidad del Aire del Departamento del Medio Ambiente de Nuevo México, acerca de las emisiones producidas por un establecimiento en esta área. Si usted desea información en español, por favor comuníquese con esa oficina al teléfono 505-476-5557.

Sincerely,

IACX Roswell LLC

5001 LBJ Freeway, Suite 300, Dallas, TX 75244

Notice of Non-Discrimination

NMED does not discriminate on the basis of race, color, national origin, disability, age or sex in the administration of its programs or activities, as required by applicable laws and regulations. NMED is responsible for coordination of compliance efforts and receipt of inquiries concerning non-discrimination requirements implemented by 40 C.F.R. Part 7, including Title VI of the Civil Rights Act of 1964, as amended; Section 504 of the Rehabilitation Act of 1973; the Age Discrimination Act of 1975, Title IX of the Education Amendments of 1972, and Section 13 of the Federal Water Pollution Control Act Amendments of 1972. If you have any questions about this notice or any of NMED's non-discrimination programs, policies or procedures, or if you believe that you have been discriminated against with respect to a NMED program or activity, you may contact: Kathryn Becker, Non-Discrimination Coordinator, NMED, 1190 St. Francis Dr., Suite N4050, P.O. Box 5469, Santa Fe, NM 87502, (505) 827-2855, nd.coordinator@state.nm.us. You may also visit our website at <https://www.env.nm.gov/non-employee-discrimination-complaint-page/> to learn how and where to file a complaint of discrimination.

October 11, 2021

CERTIFIED MAIL 7020 3160 0000 4931 8635

RETURN RECEIPT REQUESTED (certified mail is required, return receipt is optional)

Dear U.S. Bureau of Land Management

IACX Roswell LLC announces its application submittal to the New Mexico Environment Department for an air quality permit for the **modification** of its **natural gas compressor station** facility. The expected date of application submittal to the Air Quality Bureau is **August 27, 2021**.

The exact location for the proposed facility known as **Bitter Lake Compressor Station**, is at latitude **33** deg, **33** min, **11.001** sec and longitude **-104** deg, **23** min, **26.9988** sec. The approximate location of this facility is **1.6** miles **south of Salt Creek Wilderness** in Chaves County.

The proposed **modification** consists of transitioning the GCP O&G permit to an NSR permit due to the proximity to the Salt Creek Wilderness.

The estimated maximum quantities of any regulated air contaminant will be as follows in pound per hour (pph) and tons per year (tpy) and may change slightly during the course of the Department's review:

Pollutant:	Pounds per hour	Tons per year
PM 10	1.13 pph	4.64 tpy
PM 2.5	1.00 pph	4.41 tpy
Sulfur Dioxide (SO ₂)	0.34 pph	1.53 tpy
Nitrogen Oxides (NO _x)	18.33 pph	80.23 tpy
Carbon Monoxide (CO)	17.63 pph	77.27 tpy
Volatile Organic Compounds (VOC)	21.48 pph	52.33 tpy
Total sum of all Hazardous Air Pollutants (HAPs)	1.94 pph	8.58 tpy
Toxic Air Pollutant (TAP)	pph	tpy
Green House Gas Emissions as Total CO ₂ e	n/a	tpy

The standard and maximum operating schedules of the facility will be from 12:00 a.m. to 12:00 p.m. 7 days a week and a maximum of 52 weeks per year.

The owner and/or operator of the Facility is: **Tony Hines; IACX Roswell LLC; 5001 LBJ Freeway, Suite 300, Dallas, TX 75244**

If you have any comments about the construction or operation of this facility, and you want your comments to be made as part of the permit review process, you must submit your comments in writing to this address: Permit Programs Manager; New Mexico Environment Department; Air

Quality Bureau; 525 Camino de los Marquez, Suite 1; Santa Fe, New Mexico; 87505-1816; (505) 476-4300; 1 800 224-7009; https://www.env.nm.gov/aqb/permit/aqb_draft_permits.html. Other comments and questions may be submitted verbally.

Please refer to the company name and facility name, or send a copy of this notice along with your comments, since the Department may have not yet received the permit application. Please include a legible return mailing address with your comments. Once the Department has performed a preliminary review of the application and its air quality impacts, the Department's notice will be published in the legal section of a newspaper circulated near the facility location.

Atención

Este es un aviso de la oficina de Calidad del Aire del Departamento del Medio Ambiente de Nuevo México, acerca de las emisiones producidas por un establecimiento en esta área. Si usted desea información en español, por favor comuníquese con esa oficina al teléfono 505-476-5557.

Sincerely,

IACX Roswell LLC

5001 LBJ Freeway, Suite 300, Dallas, TX 75244

Notice of Non-Discrimination

NMED does not discriminate on the basis of race, color, national origin, disability, age or sex in the administration of its programs or activities, as required by applicable laws and regulations. NMED is responsible for coordination of compliance efforts and receipt of inquiries concerning non-discrimination requirements implemented by 40 C.F.R. Part 7, including Title VI of the Civil Rights Act of 1964, as amended; Section 504 of the Rehabilitation Act of 1973; the Age Discrimination Act of 1975, Title IX of the Education Amendments of 1972, and Section 13 of the Federal Water Pollution Control Act Amendments of 1972. If you have any questions about this notice or any of NMED's non-discrimination programs, policies or procedures, or if you believe that you have been discriminated against with respect to a NMED program or activity, you may contact: Kathryn Becker, Non-Discrimination Coordinator, NMED, 1190 St. Francis Dr., Suite N4050, P.O. Box 5469, Santa Fe, NM 87502, (505) 827-2855, nd.coordinator@state.nm.us. You may also visit our website at <https://www.env.nm.gov/non-employee-discrimination-complaint-page/> to learn how and where to file a complaint of discrimination.

October 11, 2021

CERTIFIED MAIL 7020 3160 0000 4931 8604

RETURN RECEIPT REQUESTED (certified mail is required, **return receipt is optional**)

Dear **Chaves County Manager**

IACX Roswell LLC announces its application submittal to the New Mexico Environment Department for an air quality permit for the **modification** of its **natural gas compressor station** facility. The expected date of application submittal to the Air Quality Bureau is **August 27, 2021**.

The exact location for the proposed facility known as **Bitter Lake Compressor Station**, is at latitude **33** deg, **33** min, **11.001** sec and longitude **-104** deg, **23** min, **26.9988** sec. The approximate location of this facility is **1.6 miles south of Salt Creek Wilderness in Chaves County**.

The proposed **modification** consists of transitioning the GCP O&G permit to an NSR permit due to the proximity to the Salt Creek Wilderness.

The estimated maximum quantities of any regulated air contaminant will be as follows in pound per hour (pph) and tons per year (tpy) and may change slightly during the course of the Department's review:

Pollutant:	Pounds per hour	Tons per year
PM 10	1.13 pph	4.64 tpy
PM 2.5	1.00 pph	4.41 tpy
Sulfur Dioxide (SO ₂)	0.34 pph	1.53 tpy
Nitrogen Oxides (NO _x)	18.33 pph	80.23 tpy
Carbon Monoxide (CO)	17.63 pph	77.27 tpy
Volatile Organic Compounds (VOC)	21.48 pph	52.33 tpy
Total sum of all Hazardous Air Pollutants (HAPs)	1.94 pph	8.58 tpy
Toxic Air Pollutant (TAP)	pph	tpy
Green House Gas Emissions as Total CO ₂ e	n/a	tpy

The standard and maximum operating schedules of the facility will be from 12:00 a.m. to 12:00 p.m. 7 days a week and a maximum of 52 weeks per year.

The owner and/or operator of the Facility is: **Tony Hines; IACX Roswell LLC; 5001 LBJ Freeway, Suite 300, Dallas, TX 75244**

If you have any comments about the construction or operation of this facility, and you want your comments to be made as part of the permit review process, you must submit your comments in writing to this address: Permit Programs Manager; New Mexico Environment Department; Air

Quality Bureau; 525 Camino de los Marquez, Suite 1; Santa Fe, New Mexico; 87505-1816; (505) 476-4300; 1 800 224-7009; https://www.env.nm.gov/aqb/permit/aqb_draft_permits.html. Other comments and questions may be submitted verbally.

Please refer to the company name and facility name, or send a copy of this notice along with your comments, since the Department may have not yet received the permit application. Please include a legible return mailing address with your comments. Once the Department has performed a preliminary review of the application and its air quality impacts, the Department's notice will be published in the legal section of a newspaper circulated near the facility location.

Atención

Este es un aviso de la oficina de Calidad del Aire del Departamento del Medio Ambiente de Nuevo México, acerca de las emisiones producidas por un establecimiento en esta área. Si usted desea información en español, por favor comuníquese con esa oficina al teléfono 505-476-5557.

Sincerely,

IACX Roswell LLC

5001 LBJ Freeway, Suite 300, Dallas, TX 75244

Notice of Non-Discrimination

NMED does not discriminate on the basis of race, color, national origin, disability, age or sex in the administration of its programs or activities, as required by applicable laws and regulations. NMED is responsible for coordination of compliance efforts and receipt of inquiries concerning non-discrimination requirements implemented by 40 C.F.R. Part 7, including Title VI of the Civil Rights Act of 1964, as amended; Section 504 of the Rehabilitation Act of 1973; the Age Discrimination Act of 1975, Title IX of the Education Amendments of 1972, and Section 13 of the Federal Water Pollution Control Act Amendments of 1972. If you have any questions about this notice or any of NMED's non-discrimination programs, policies or procedures, or if you believe that you have been discriminated against with respect to a NMED program or activity, you may contact: Kathryn Becker, Non-Discrimination Coordinator, NMED, 1190 St. Francis Dr., Suite N4050, P.O. Box 5469, Santa Fe, NM 87502, (505) 827-2855, nd.coordinator@state.nm.us. You may also visit our website at <https://www.env.nm.gov/non-employee-discrimination-complaint-page/> to learn how and where to file a complaint of discrimination.

NOTICE

IACX Roswell LLC announces its application to the New Mexico Environment Department for an air quality permit for the **modification** of its **natural gas compressor station** facility. The expected date of application submittal to the Air Quality Bureau is **August 27, 2021**.

The exact location for the proposed facility known as, **Bitter Lake Compressor Station**, is at latitude **33** deg, **33** min, **11.001** sec and longitude - **104** deg, **23** min, **26.9988** sec. The approximate location of this facility is **1.6** miles **south** of **Salt Creek Wilderness** in **Chaves County**].

The proposed **modification** consists of **transitioning the GCP O&G permit to an NSR permit due to the proximity to the Salt Creek Wilderness**.

The estimated maximum quantities of any regulated air contaminants will be as follows in pound per hour (pph) and tons per year (tpy). These reported emissions could change slightly during the course of the Department's review:

Pollutant:	Pounds per hour	Tons per year
PM 10	1.13 pph	4.64 tpy
PM 2.5	1.00 pph	4.41 tpy
Sulfur Dioxide (SO2)	0.34 pph	1.53 tpy
Nitrogen Oxides (NOx)	18.33 pph	80.23 tpy
Carbon Monoxide (CO)	17.63 pph	77.27 tpy
Volatile Organic Compounds (VOC)	21.48 pph	52.33 tpy
Total sum of all Hazardous Air Pollutants (HAPs)	1.94 pph	8.58 tpy
Toxic Air Pollutant (TAP)	pph	tpy
Green House Gas Emissions as Total CO2e	n/a	tpy

The standard and maximum operating schedules of the facility will be from 12:00 a.m. to 12:00 p.m. 7 days a week and a maximum of 52 weeks per year.

The owner and/or operator of the Facility is: **Tony Hines; IACX Roswell LLC; 5001 LBJ Freeway, Suite 300, Dallas, TX 75244**

If you have any comments about the construction or operation of this facility, and you want your comments to be made as part of the permit review process, you must submit your comments in writing to this address: Permit Programs Manager; New Mexico Environment Department; Air Quality Bureau; 525 Camino de los Marquez, Suite 1; Santa Fe, New Mexico; 87505-1816; (505) 476-4300; 1 800 224-7009; https://www.env.nm.gov/aqb/permit/aqb_draft_permits.html. Other comments and questions may be submitted verbally.

With your comments, please refer to the company name and facility name, or send a copy of this notice along with your comments. This information is necessary since the Department may have not yet received the permit application. Please include a legible return mailing address. Once the Department has completed its preliminary review of the application and its air quality impacts, the Department's notice will be published in the legal section of a newspaper circulated near the facility location.

Atención

Este es un aviso de la oficina de Calidad del Aire del Departamento del Medio Ambiente de Nuevo México, acerca de las emisiones producidas por un establecimiento en esta área. Si usted desea información en español, por favor comuníquese con esa oficina al teléfono 505-476-5557.

Notice of Non-Discrimination

NMED does not discriminate on the basis of race, color, national origin, disability, age or sex in the administration of its programs or activities, as required by applicable laws and regulations. NMED is responsible for coordination of compliance efforts and receipt of inquiries concerning non-discrimination requirements implemented by 40 C.F.R. Part 7, including Title VI of the Civil Rights Act of 1964, as amended; Section 504 of the Rehabilitation Act of 1973; the Age Discrimination Act of 1975, Title IX of the Education Amendments of 1972, and Section 13 of the Federal Water Pollution Control Act Amendments of 1972. If you have any questions about this notice or any of NMED's non-discrimination programs, policies or procedures, or if you believe that you have been discriminated against with respect to a NMED program or activity, you may contact: Kathryn Becker, Non-Discrimination Coordinator, NMED, 1190 St. Francis Dr., Suite N4050, P.O. Box 5469, Santa Fe, NM 87502, (505) 827-2855, nd.coordinator@state.nm.us. You may also visit our website at <https://www.env.nm.gov/non-employee-discrimination-complaint-page/> to learn how and where to file a complaint of discrimination.

This Notice is Also Posted at the Following Locations:

Roswell Fire Station #4 located 10 E Challenger St, Roswell, NM 88203, Roswell Public Library located at 301 N Pennsylvania Ave, Roswell, NM 882010, Roswell Public Health Division located at 200 E Chisum St, Roswell, NM 88203, and Bitter Lake Compressor Station located at **33** deg, **33** min, **11.001** sec and longitude -**104** deg, **23** min, **26.9988** sec.

General Posting of Notices – Certification

I, Mike Space, the undersigned, certify that on 8/31/21, posted a true and correct copy of the attached Public Notice in the following publicly accessible and conspicuous places in the **ROSWELL** of **CHAVEZ** County, State of New Mexico on the following dates:

1. Bitter Lake Compressor Station at 33 deg. 33 min. 11.001 sec and longitude -104 deg. 23 min. 26.9988 sec {8/27/2021}
2. Roswell Fire Station #4 located 10 E Challenger St, Roswell, NM 88203 {8/31/21}
3. Roswell Public Library located at 301 N Pennsylvania Ave, Roswell, NM 882010 {8/31/21}
4. Roswell Public Health Division located at 200 E Chisum St, Roswell, NM 88203 {8/31/21}

Signed this 1st day of October, 2021.

Will Space
Signature

10/1/2021
Date

Mike Space
Printed Name

Consultant
Title {APPLICANT OR RELATIONSHIP TO APPLICANT}

Notices That Were Sent

- Chavez County Manager
- Gary L. Key
- Hondo Resources Inc.
- U.S. Bureau of Land Management

Account: R042873 * Tax Rate does not include the Pecos Valley Artesian Conservancy District

Location		Owner Information	Assessment History				
Parcel Number 4-144-052-068-322-000000		Owner Name UNITED STATES OF AMERICA	Actual Value (2021)		\$33,208		
Tax Area 11N_8_10 - 11N-FC-CSW		In Care Of Name BUREAU OF LAND MANAGEMENT-ROSWELL FIELD OFFICE	Primary Taxable		\$11,070		
Situs Address		Owner Address 2809 W 2ND ST	Exempt		(\$11,070)		
Legal Summary S: 1 T: 9S R: 25E ALL LESS LOT 4 S: 2 T: 9S R: 25E SW4SE4 S: 10 T: 9S R: 25E SE4NW4-NE4SW4-S2NE4-NW4SE4 LESS HWY & RR R/W'S (ADDED TO ACCOUNT) S: 11 T: 9S R: 25E NE4-NE4SE4-S2SE4 S: 12 T: 9S R: 25E ALL S: 13 T: 9S R: 25E ALL S: 14 T: 9S R: 25E ALL LESS S2SW4SE4-W2NE4NW4-NW4NW4 S: 15 T: 9S R: 25E ALL LESS NW4NW4 S: 20 T: 9S R: 25E E2 LESS HWY & RR R/W S: 21 T: 9S R: 25E N2-W2SW4-E2SE4 S: 22 T: 9S R: 25E ALL LESS N2NE4-N2SW4SE4 S: 23 T: 9S R: 25E ALL S: 24 T: 9S R: 25E ALL S: 25 T: 9S R: 25E ALL S: 26 T: 9S R: 25E ALL S: 27 T: 9S R: 25E ALL S: 28 T: 9S R: 25E E2-SE4SW4 S: 32 T: 9S R: 25E NE4NE4-S2NE4-SE4-E2SW4 S: 33 T: 9S R: 25E ALL S: 34 T: 9S R: 25E N2-SE4-SE4SW4 S: 35 T: 9S R: 25E ALL		ROSWELL, NM 88201-2019	Adjusted Taxable Total		\$0		
		UNITED STATES OF AMERICA	Tax Area: 11N 8 10		Tax Rate: 0.023359		
			Type	Actual	Assessed	Acres	SQFT
			Exempt Land	\$32,906	\$10,969	10445.850	0.000
			Tax Area: 11N 8 15		Tax Rate: 0.022359		
			Type	Actual	Assessed	Acres	
			Exempt Land	\$302	\$101	95.839	

Images			
Tax Year		Taxes	
*2021		\$0.00	GIS
2020		\$0.00	
* Estimated			

Location		Owner Information	Assessment History					
Parcel Number 4-143-049-114-198-000000		Owner Name KEY,GARY L ; KEY,JERI L	Actual Value (2021)		\$27,448			
Tax Area 11N_8_10 - 11N-FC-CSW		Owner Address 1012 E SECOND ST	Primary Taxable		\$9,150			
Situs Address		ROSWELL, NM 88201	Tax Area: 11N_8_10 Tax Rate: 0.023359					
Legal Summary S: 3 T: 9S R: 25E NE4 - SE4NW4 - SW4 N & W OF HWY 70 - N2NW4 - SW4NW4 S: 4 T: 9S R: 25E E2E2 N & W OF HWY 70 - W2 S: 5 T: 9S R: 25E SE4NE4 - E2SE4 S: 6 T: 9S R: 25E NW4 (LOTS 3 4 5) S: 8 T: 9S R: 25E N2N2 - SE4NE4 - S2 THAT PT N & W OF HWY 70 S: 9 T: 9S R: 25E NW4 - NW4SW4 N & W OF HWY 70 - E2NE4 N & W OF HWY 70 S: 17 T: 9S R: 25E NW4 N & W OF HWY 70 S: 18 T: 9S R: 25E E2 N & W OF HWY 70 BK 731 PG 1793 WD		UNITED STATES OF AMERICA	Type	Actual	Assessed	Acres	SQFT	Units
			Agriculture Land	\$6,041	\$2,014	1917.910	0.000	
			Non-Residential Improvement	\$21,407	\$7,136			69960.000

Images		
Tax Year	Taxes	
*2021	\$213.74	
2020	\$213.74	

* Estimated

Account: R045425 * Tax Rate does not include the Pecos Valley Artesian Conservancy District

Location		Owner Information	Assessment History				
Parcel Number 4-143-050-031-338-000000		Owner Name HONDO RESOURCES INC	Actual Value (2021)		\$506		
Tax Area 11N_8_10 - 11N-FC-CSW		Owner Address PO BOX 2623	Primary Taxable		\$169		
Situs Address		ROSWELL, NM 88202-2623	Tax Area: 11N 8 10 Tax Rate: 0.023359				
Legal Summary S: 9 T: 9S R: 25E SE1/4SE1/4 S & E OF OLD CLOVIS HWY & N & W OF AT & SF		UNITED STATES OF AMERICA	Type	Actual	Assessed	Acres	SQFT
RR R/W S: 10 T: 9S R: 25E W1/2W1/2 S & E OF OLD CLOVIS HWY & N & W OF AT & SF RR R/W			Non-Residential Land	\$506	\$169	20.227	0.000
BK: 425 PG: 488 WD							

Images			
Tax Year	Taxes	GIS	
*2021	\$3.94		
2020	\$3.94		

* Estimated

Account: R045426 * Tax Rate does not include the Pecos Valley Artesian Conservancy District

Location		Owner Information	Assessment History				
Parcel Number 4-143-050-061-098-000000		Owner Name HONDO RESOURCES INC	Actual Value (2021)		\$10,593		
Tax Area 11N_8_10 - 11N-FC-CSW		Owner Address PO BOX 2623	Primary Taxable		\$3,531		
Situs Address		ROSWELL, NM 88202-2623	Tax Area: 11N 8 10 Tax Rate: 0.023359				
Legal Summary S: 3 T: 9S R: 25E S1/2N1/2 & S1/2 S & E OF HWY 70 & N & W 0F OLD CLOVIS		UNITED STATES OF AMERICA	Type	Actual	Assessed	Acres	SQFT
HWY. S: 9 T: 9S R: 25E E2E2 S & E OF HWY 70 & N & W OF OLD CLOVIS HWY S: 10 T: 9S R: 25E			Non-Residential Land	\$10,593	\$3,531	321.582	0.000
W1/2 N & W OF OLD CLOVIS HWY LESS 5.10 AC IN NE4NW4 BK: 425 PG: 488 WD							

Images			
Tax Year		Taxes	
*2021		\$82.48	GIS
2020		\$82.48	

* Estimated

Public Service Announcement

IACX Roswell LLC announces its application to the New Mexico Environment Department for an air quality permit for the **modification** of its **natural gas compressor station** facility. The expected date of application submittal to the Air Quality Bureau is **August 27, 2021**.

The exact location for the proposed facility known as, **Bitter Lake Compressor Station**, is at latitude 33 deg, 33 min, 11.001 sec and longitude -104 deg, 23 min, 26.9988 sec. The approximate location of this facility is 1.6 miles south of Salt Creek Wilderness in Chaves County].

The proposed **modification** consists of transitioning the GCP O&G permit to an NSR permit due to the proximity to the Salt Creek Wilderness.

The standard and maximum operating schedules of the facility will be from 12:00 a.m. to 12:00 p.m. 7 days a week and a maximum of 52 weeks per year.

The owner and/or operator of the Facility is: **Tony Hines; IACX Roswell LLC; 5001 LBJ Freeway, Suite 300, Dallas, TX 75244**

If you have any comments about the construction or operation of this facility, and you want your comments to be made as part of the permit review process, you must submit your comments in writing to this address: Permit Programs Manager; New Mexico Environment Department; Air Quality Bureau; 525 Camino de los Marquez, Suite 1; Santa Fe, New Mexico; 87505-1816; (505) 476-4300; 1 800 224-7009; https://www.env.nm.gov/aqb/permit/aqb_draft_permits.html. Other comments and questions may be submitted verbally.

Atención

Este es un aviso de la oficina de Calidad del Aire del Departamento del Medio Ambiente de Nuevo México, acerca de las emisiones producidas por un establecimiento en esta área. Si usted desea información en español, por favor comuníquese con esa oficina al teléfono 505-476-5557.

This Notice is Also Posted at the Following Locations:

Farmer County Market located at 600 E 2nd St, Roswell, NM 88201, Roswell Public Library located at 301 N Pennsylvania Ave, Roswell, NM 882010, Roswell Public Health Division located at 200 E Chisum St, Roswell, NM 88203, and Bitter Lake Compressor Station located at 33 deg, 33 min, 11.001 sec and longitude -104 deg, 23 min, 26.9988 sec.

From: Markham, Desiree <Desiree.Markham@enmu.edu>

Sent: Friday, September 3, 2021 7:45 PM

To: Becca Edwards <be@resolutecompliance.com>; Joseline Laureano <jl@resolutecompliance.com>

Subject: Fwd: [EXTERNAL] RE: [EXTERNAL] RE: [EXTERNAL] Air Quality Permit Application - Public Service Announcement

Good evening,

Apologies I was traveling. Here is the attached spot and air time and date.

Air time:11:46:41

September 2, 2021

11:46:41 PLY 02 UWIACX UW IACX PUBLIC SERVICE ANNOUNC

Please let me know if you need anything else.

Happy Labor Day!

Desirée


AFFIDAVIT OF PUBLICATION
STATE OF NEW MEXICO

I, Jennifer Martinez
Legals Clerk

Of the Roswell Daily Record, a daily newspaper published at Roswell, New Mexico do solemnly swear that the clipping hereto attached was published in the regular and entire issue of said paper and not in a supplement thereof for a period of:


One time with the issue dated


September 2, 2021


Clerk

Sworn and subscribed to before me

this 7th day of August, 2021


Notary Public



Air Quality Permit Application...

Publish September 2, 2021

NOTICE OF AIR QUALITY PERMIT APPLICATION

IACX Roswell LLC announces its application submittal to the New Mexico Environment Department for an air quality permit for the **modification** of its **natural gas compressor station** facility. The expected date of application submittal to the Air Quality Bureau is **August 27, 2021**.

The exact location for the proposed facility known as, **Bitter Lake Compressor Station**, is at 33 deg. 33 min, 11.001 sec and longitude -104 deg. 23 min, 26.9988 sec. The approximate location of this facility is **1.6 miles south of Salt Creek Wilderness** in **Chaves County**.

The proposed **modification** consists of **transitioning the GCP O&G permit to an NSR permit due to the proximity to the Salt Creek Wilderness**.

The estimated maximum quantities of any regulated air contaminant will be as follows in pound per hour (pph) and tons per year (tpy) and could change slightly during the course of the Department's review:

Pollutant:	Pounds per hour	Tons per year
PM 10	1.13 pph	4.64 tpy
PM 2.5	1.00 pph	4.41 tpy
Sulfur Dioxide (SO2)	0.34 pph	1.53 tpy
Nitrogen Oxides (NOx)	18.33 pph	80.23 tpy
Carbon Monoxide (CO)	17.63 pph	77.27 tpy
Volatile Organic Compounds (VOC)	21.48 pph	92.33 tpy
Total sum of all Hazardous Air Pollutants (HAPs)	1.94 pph	8.58 tpy
Toxic Air Pollutant (TAP)	pph	tpy
Green House Gas Emissions as Total CO2e	n/a	tpy

The standard and maximum operating schedules of the facility will be from 12:00 a.m. to 12:00 p.m. 7 days a week and a maximum of 52 weeks per year.

The owner and/or operator of the Facility is: **Tony Hines; IACX Roswell LLC; 5001 LBJ Freeway, Dallas, Texas, 75244**.

If you have any comments about the construction or operation of this facility, and you want your comments to be made as part of the permit review process, you must submit your comments in writing to this address: Permit Programs Manager, New Mexico Environment Department, Air Quality Bureau, 525 Camino de los Marquez, Suite 1, Santa Fe, New Mexico, 87505-1816, (505) 476-4300; 1 800 224-7009; https://www.env.nm.gov/aqb/permit/aqb_draft_permits.html. Other comments and questions may be submitted verbally.

Please refer to the company name and site name, or send a copy of this notice along with your comments, since the Department may have not yet received the permit application. Please include a legible return mailing address with your comments. Once the Department has performed a preliminary review of the application and its air quality impacts, the Department's notice will be published in the legal section of a newspaper circulated near the facility location.

General information about air quality and the permitting process can be found at the Air Quality Bureau's web site. The regulation dealing with public participation in the permit review process is 20.2.72.206 NMAC. This regulation can be found in the "Permits" section of this web site.

Atención

Este es un aviso de la oficina de Calidad del Aire del Departamento del Medio Ambiente de Nuevo México, acerca de las emisiones producidas por un establecimiento en esta área. Si usted desea información en español, por favor comuníquese con esa oficina al teléfono 505-476-5557.

Notice of Non-Discrimination

NMED does not discriminate on the basis of race, color, national origin, disability, age or sex in the administration of its programs or activities, as required by applicable laws and regulations. NMED is responsible for coordination of compliance efforts and receipt of inquiries concerning non-discrimination requirements implemented by 40 C.F.R. Part 7, including Title VI of the Civil Rights Act of 1964, as amended; Section 504 of the Rehabilitation Act of 1973; the Age Discrimination Act of 1975, Title IX of the Education Amendments of 1972, and Section 13 of the Federal Water Pollution Control Act Amendments of 1972. If you have any questions about this notice or any of NMED's non-discrimination programs, policies or procedures, or if you believe that you have been discriminated against with respect to a NMED program or activity, you may contact: Kathryn Becker, Non-Discrimination Coordinator, NMED, 1190 St. Francis Dr., Suite N4050, P.O. Box 5469, Santa Fe, NM 87502, (505) 827-2855, nd.coordinator@state.nm.us. You may also visit our website at <https://www.env.nm.gov/non-employee-discrimination-complaint-page/> to learn how and where to file a complaint of discrimination.

Roswell Seven-day forecast

Today

A stray afternoon t-storm

High 91°

SSE at 4-8 mph

POP: 45%

Tonight

Partly cloudy

Low 69°

S at 4-8 mph

POP: 25%

Friday

A thunderstorm around

92°/69°

S at 4-8 mph

POP: 40%

Saturday

Mostly sunny

92°/69°

SSE at 4-8 mph

POP: 15%

Sunday

Mostly cloudy

90°/66°

NE at 6-12 mph

POP: 5%

Monday

Partly sunny

92°/65°

ESE at 4-8 mph

POP: 5%

Tuesday

Warm with lots of sun

93°/63°

ESE at 4-8 mph

POP: 5%

Wednesday

Increasing clouds

91°/65°

SSW at 6-12 mph

POP: 25%

Almanac

Roswell through 8 p.m. Wednesday

Temperatures

High/low 94°/68°
Normal high/low 92°/66°
Record high 100° in 2020
Record low 45° in 1915
Humidity at noon 32%

Precipitation

24 hours ending 8 p.m. Wed. 0.00"
Month to date 0.00"
Normal month to date 0.05"
Year to date 14.42"
Normal year to date 7.79"

Air Quality Index

Today's Forecast **Moderate**

Yesterday's A.Q.I. Reading 60

0-50 51-100 101-150 151+

Good Moderate Unhealthy sensitive Unhealthy

Source: Texas Commission on Environmental Quality

Sun and Moon

	Rise	Set
Today	6:33 a.m.	7:22 p.m.
Fri.	6:34 a.m.	7:20 p.m.

The Moon


	Rise	Set
Today	1:56 a.m.	4:53 p.m.
Fri.	2:53 a.m.	5:39 p.m.

New First Full Last

Sep 6 Sep 13 Sep 20 Sep 28

New Mexico Weather

Shown is today's weather. Temperatures are today's highs and tonight's lows.



Regional Cities

	Today Hi/Lo/W	Fri. Hi/Lo/W
Alamogordo	85/67/t	88/66/t
Albuquerque	84/64/c	86/66/t
Angel Fire	71/45/pc	72/43/t
Artesia	90/70/t	91/69/t
Carlsbad	90/69/t	92/69/t
Chama	70/46/t	74/45/t
Clayton	88/61/pc	88/63/pc
Cloudcroft	67/50/t	68/52/t
Clovis	85/66/t	87/65/s
Deming	87/64/t	89/65/t
Espanola	82/56/c	83/57/t
Farmington	80/56/c	87/56/t
Gallup	76/50/c	80/50/t
Hobbs	91/68/t	93/67/s
Las Cruces	88/66/t	90/66/t
Las Vegas	82/53/pc	83/56/t
Los Alamos	74/56/pc	77/59/t
Los Lunas	86/61/c	87/65/t
Lovington	91/67/t	92/66/pc
Portales	85/67/t	86/66/s
Prewitt	74/46/c	75/52/t
Raton	84/54/pc	85/54/t
Red River	69/45/c	71/42/t
Roswell	91/69/t	92/69/t
Ruidoso	73/56/t	75/57/t
Santa Fe	81/56/c	85/57/t
Silver City	80/59/t	81/61/t
T or C	86/66/t	89/66/t
Tucumcari	91/68/pc	93/68/s
White Rock	79/56/pc	82/60/t

W-weather, s-sunny, pc-partly cloudy, c-cloudy, sh-showers, t-thunderstorms, r-rain, sf-snow flurries, sn-snow, i-ice

National Cities

	Today Hi/Lo/W	Fri. Hi/Lo/W		Today Hi/Lo/W	Fri. Hi/Lo/W
Anchorage	61/52/sh	59/53/r	Miami	89/76/pc	90/77/t
Atlanta	86/67/s	84/67/s	Midland	93/72/s	94/72/s
Baltimore	78/56/s	78/58/s	Minneapolis	73/61/c	67/61/pc
Boston	71/58/r	70/58/pc	New Orleans	90/77/t	89/75/pc
Charlotte	84/58/s	82/60/s	New York	75/59/pc	72/58/s
Chicago	78/61/s	76/65/t	Omaha	78/67/t	79/63/c
Cleveland	72/54/s	74/56/pc	Orlando	87/75/t	90/74/t
Dallas	98/79/s	98/78/s	Philadelphia	77/58/pc	75/60/s
Denver	80/60/c	82/56/t	Phoenix	96/81/pc	100/83/pc
Detroit	77/55/s	76/61/pc	Pittsburgh	73/49/s	74/53/pc
El Paso	89/71/t	92/70/t	Portland, OR	84/55/s	85/58/s
Honolulu	88/76/sh	88/75/s	Raleigh	81/57/s	81/58/s
Houston	95/76/t	94/77/pc	St. Louis	82/63/s	79/68/t
Indianapolis	78/57/s	77/63/s	Salt Lake City	86/61/s	83/58/s
Kansas City	83/68/s	81/68/t	San Diego	75/66/pc	76/67/pc
Las Vegas	98/77/s	99/79/s	Seattle	77/53/s	76/57/s
Los Angeles	77/61/pc	82/62/pc	Tucson	90/72/t	90/74/c
Lubbock	91/72/s	92/73/s	Washington, DC	78/60/s	78/62/pc

U.S. Extremes


(For the 48 contiguous states)

High: 104° Zapata, Texas
Low: 27° Meacham, Ore.

State Extremes

High: 94° Carlsbad
Low: 37° Angel Fire

National Cities



Lil Nas X honored by anti-suicide group The Trevor Project

By MARK KENNEDY
AP ENTERTAINMENT WRITER

NEW YORK — Lil Nas X has been awarded the inaugural Suicide Prevention Advocate of the Year Award from the advocacy group The Trevor Project.

The Trevor Project is a nonprofit dedicated to suicide prevention and crisis intervention for lesbian, gay, bisexual, transgender, queer and questioning young people.

The group cited Lil Nas X's "openness about struggling with his sexuality and suicidal ideation, his continued advocacy around mental health

issues, and his unapologetic celebration of his queer identity."

In an interview, Amit Paley, CEO and executive director at The Trevor Project, said the awareness that the "Old Town Road" artist has brought to suicide prevention and mental health has been "profound."

"He has done it in a way that has resonated and impacted communities where these conversations are often taboo, but where they are so needed," Paley said.

"The fact that he has been so open, so vulnerable about his men-

tal health journey, his thoughts of suicide, he is really helping to destigmatize conversations that are too often shrouded in shame."

In February, Lil Nas X shared a series of intimate TikTok videos documenting his life story, including his battle with depression, anxiety and suicidal ideation during his rise to fame. In May, he released a music video which depicts Lil Nas X uplifting a younger version of himself in high school when he was contemplating suicide and struggling to come to terms with his sexuality.

"It's particularly inspiring to see someone who is Black and LGBTQ and proud and unapologetic," said Paley. "And to see someone talk about their experiences with depression and anxiety and suicidal ideation and to talk about those as part of their art and part of their platform to make other people comfortable talking about the challenges that they are going through."

The Trevor Project's national survey on LGBTQ youth mental health in 2021 found that 42% of

LGBTQ youth seriously considered attempting suicide in the past year, including more than half of transgender and nonbinary youth.

Paley said the past year has been an especially challenging time for LGBTQ youth, both from a public health perspective and also financially and emotionally. The pandemic may have cut them off from school and resources there for support.

"They might have been trapped in homes with families that were

unsupportive or at times rejecting. They might be encountering emotional or even physical abuse or at times thrown out of their homes and experiencing housing instability," said Paley.

"We had a political climate that has been very challenging for LGBTQ people and especially we've seen in states across the country legislation targeting transgender and non-binary young people. All of these things have an impact on people's mental health."

Roswell Daily Record

Roswell UFO Incident

Crash Site Package

2x3 B/W \$500

2col by 3 inch ad all month long in our publication.

Want color? Give us a call.

*Plus NM Sales Tax

Actual size of ad. (3.389" wide x 3" tall)

Call the Advertising Department 575-622-7710

Melanie Page Ext. 204 advertising2@rdrnews.com

Merle Alexander Ext. 206 advertising1@rdrnews.com

Roswell Daily Record

Roswell UFO Incident

Area 51 Package

2x4 B/W \$600

2col by 4 inch ad all month long in our publication.

Want color? Give us a call.

*Plus NM Sales Tax

Actual size of ad. (3.389" wide x 4" tall)

Call the Advertising Department 575-622-7710

Melanie Page Ext. 204 advertising2@rdrnews.com

Merle Alexander Ext. 206 advertising1@rdrnews.com

NOTICE OF AIR QUALITY PERMIT APPLICATION

IACX Roswell LLC announces its application submittal to the New Mexico Environment Department for an air quality permit for the **modification** of its **natural gas compressor** station facility. The expected date of application submittal to the Air Quality Bureau is **August 27, 2021**.

The exact location for the proposed facility known as, **Bitter Lake Compressor Station**, is at 33 deg, 33 min, 11.001 sec and longitude -104 deg, 23 min, 26.9988 sec. The approximate location of this facility is **1.6 miles south of Salt Creek Wilderness** in Chaves County.

The proposed **modification** consists of transitioning the GCP O&G permit to an NSR permit due to the proximity to the Salt Creek Wilderness.

The estimated maximum quantities of any regulated air contaminant will be as follows in pound per hour (pph) and tons per year (tpy) and could change slightly during the course of the Department's review:

Pollutant:	Pounds per hour	Tons per year
PM 10	1.13 pph	4.64 tpy
PM 2.5	1.00 pph	4.41 tpy
Sulfur Dioxide (SO2)	0.35 pph	1.54 tpy
Nitrogen Oxides (NOx)	18.33 pph	80.23 tpy
Carbon Monoxide (CO)	17.63 pph	77.27 tpy
Volatile Organic Compounds (VOC)	21.48 pph	52.33 tpy
Total sum of all Hazardous Air Pollutants (HAPs)	1.94 pph	8.58 tpy
Toxic Air Pollutant (TAP)	pph	tpy
Green House Gas Emissions as Total CO2e	n/a	tpy

The standard and maximum operating schedules of the facility will be from **12:00 a.m. to 12:00 p.m. 7 days a week** and a maximum of **52 weeks per year**.

The owner and/or operator of the Facility is: **Tony Hines; IACX Roswell LLC; 5001 LBJ Freeway, Dallas, Texas, 75244.**

If you have any comments about the construction or operation of this facility, and you want your comments to be made as part of the permit review process, you must submit your comments in writing to this address: Permit Programs Manager; New Mexico Environment Department; Air Quality Bureau; 525 Camino de los Marquez, Suite 1; Santa Fe, New Mexico; 87505-1816; (505) 476-4300; 1 800 224-7009; https://www.env.nm.gov/aqb/permit/aqb_draft_permits.html. Other comments and questions may be submitted verbally.

Please refer to the company name and site name, or send a copy of this notice along with your comments, since the Department may have not yet received the permit application. Please include a legible return mailing address with your comments. Once the Department has performed a preliminary review of the application and its air quality impacts, the Department's notice will be published in the legal section of a newspaper circulated near the facility location.

General information about air quality and the permitting process can be found at the Air Quality Bureau's web site. The regulation dealing with public participation in the permit review process is 20.2.72.206 NMAC. This regulation can be found in the "Permits" section of this web site.

Atención

Este es un aviso de la oficina de Calidad del Aire del Departamento del Medio Ambiente de Nuevo México, acerca de las emisiones producidas por un establecimiento en esta área. Si usted desea información en español, por favor comuníquese con esa oficina al teléfono 505-476-5557.

Notice of Non-Discrimination

NMED does not discriminate on the basis of race, color, national origin, disability, age or sex in the administration of its programs or activities, as required by applicable laws and regulations. NMED is responsible for coordination of compliance efforts and receipt of inquiries concerning non-discrimination requirements implemented by 40 C.F.R. Part 7, including Title VI of the Civil Rights Act of 1964, as amended; Section 504 of the Rehabilitation Act of 1973; the Age Discrimination Act of 1975, Title IX of the Education Amendments of 1972, and Section 13 of the Federal Water Pollution Control Act Amendments of 1972. If you have any questions about this notice or any of NMED's non-discrimination programs, policies or procedures, or if you believe that you have been discriminated against with respect to a NMED program or activity, you may contact: Kathryn Becker, Non-Discrimination Coordinator, NMED, 1190 St. Francis Dr., Suite N4050, P.O. Box 5469, Santa Fe, NM 87502, (505) 827-2855, nd.coordinator@state.nm.us. You may also visit our website at <https://www.env.nm.gov/non-employee-discrimination-complaint-page/> to learn how and where to file a complaint of discrimination.


AFFIDAVIT OF PUBLICATION
STATE OF NEW MEXICO

I, Noely Martinez
Legals Clerk

Of the Roswell Daily Record, a daily newspaper published at Roswell, New Mexico do solemnly swear that the clipping hereto attached was published in the regular and entire issue of said paper and not in a supplement thereof for a period of:


One time with the issue dated

September 2, 2021




Clerk

Sworn and subscribed to before me
this 2nd day of September, 2021



Notary Public



Shop Smart

SHOP THE CLASSIFIEDS!

Roswell Daily Record • 622-7710

LEGALS

Air Quality Permit Application...

Publish September 2, 2021

NOTICE OF AIR QUALITY PERMIT APPLICATION

IACX Roswell LLC announces its application submittal to the New Mexico Environment Department for an air quality permit for the **modification of its natural gas compressor station** facility. The expected date of application submittal to the Air Quality Bureau is **August 27, 2021**.

The exact location for the proposed facility known as, **Bitter Lake Compressor Station**, is at 33 deg, 33 min, 11.001 sec and longitude -104 deg, 23 min, 26.9988 sec. The approximate location of this facility is **1.6 miles south of Salt Creek Wilderness in Chaves County**.

The proposed **modification** consists of transitioning the GCP O&G permit to an NSR permit due to the proximity to the Salt Creek Wilderness.

The estimated maximum quantities of any regulated air contaminant will be as follows in pound per hour (pph) and tons per year (tpy) and could change slightly during the course of the Department's review:

Pollutant:	Pounds per hour	Tons per year
PM 10	1.13 pph	4.64 tpy
PM 2.5	1.00 pph	4.41 tpy
Sulfur Dioxide (SO2)	0.34 pph	1.53 tpy
Nitrogen Oxides (NOx)	18.33 pph	80.23 tpy
Carbon Monoxide (CO)	17.63 pph	77.27 tpy
Volatile Organic Compounds (VOC)	21.48 pph	52.33 tpy
Total sum of all Hazardous Air Pollutants (HAPs)	1.94 pph	8.58 tpy
Toxic Air Pollutant (TAP)	pph	tpy
Green House Gas Emissions as Total CO2e	n/a	tpy

The standard and maximum operating schedules of the facility will be from 12:00 a.m. to 12:00 p.m. 7 days a week and a maximum of 52 weeks per year.

The owner and/or operator of the Facility is: **Tony Hines; IACX Roswell LLC; 5001 LBJ Freeway, Dallas, Texas, 75244**.

If you have any comments about the construction or operation of this facility, and you want your comments to be made as part of the permit review process, you must submit your comments in writing to this address: Permit Programs Manager; New Mexico Environment Department; Air Quality Bureau; 525 Camino de los Marquez, Suite 1; Santa Fe, New Mexico; 87505-1816; (505) 476-4300; 1 800 224-7009; https://www.env.nm.gov/aqb/permit/aqb_draft_permits.html. Other comments and questions may be submitted verbally.

Please refer to the company name and site name, or send a copy of this notice along with your comments, since the Department may have not yet received the permit application. Please include a legible return mailing address with your comments. Once the Department has performed a preliminary review of the application and its air quality impacts, the Department's notice will be published in the legal section of a newspaper circulated near the facility location.

General information about air quality and the permitting process can be found at the Air Quality Bureau's web site. The regulation dealing with public participation in the permit review process is 20.2.72.206 NMAC. This regulation can be found in the "Permits" section of this web site.

Atención

Este es un aviso de la oficina de Calidad del Aire del Departamento del Medio Ambiente de Nuevo México, acerca de las emisiones producidas por un establecimiento en esta área. Si usted desea información en español, por favor comuníquese con esa oficina al teléfono 505-476-5557.

Notice of Non-Discrimination

NMED does not discriminate on the basis of race, color, national origin, disability, age or sex in the administration of its programs or activities, as required by applicable laws and regulations. NMED is responsible for coordination of compliance efforts and receipt of inquiries concerning non-discrimination requirements implemented by 40 C.F.R. Part 7, including Title VI of the Civil Rights Act of 1964, as amended; Section 504 of the Rehabilitation Act of 1973; the Age Discrimination Act of 1975, Title IX of the Education Amendments of 1972, and Section 13 of the Federal Water Pollution Control Act Amendments of 1972. If you have any questions about this notice or any of NMED's non-discrimination programs, policies or procedures, or if you believe that you have been discriminated against with respect to a NMED program or activity, you may contact: Kathryn Becker, Non-Discrimination Coordinator, NMED, 1190 St. Francis Dr., Suite N4050, P.O. Box 5469, Santa Fe, NM 87502, (505) 827-2855, nd.coordinator@state.nm.us. You may also visit our website at <https://www.env.nm.gov/non-employee-discrimination-complaint-page/> to learn how and where to file a complaint of discrimination.

Public Meeting...

Publish September 2, 2021

NOTICE OF PUBLIC MEETING

Notice is hereby given that a meeting of the Board of Directors of the Colonias Infrastructure Board will convene at 9:00 a.m. on Thursday, September 16, 2021. The meeting location, as well as the method for public attendance, will be posted on the NMFA's website as soon as reasonably practicable due to the Covid-19 public health emergency declared by the Governor of the State of New Mexico.

The agenda will be available at least seventy-two hours prior to the meeting from the New Mexico Finance Authority, 207 Shelby Street, Santa Fe, New Mexico, and at www.nmfinance.com. Anyone who has questions regarding the meeting or needs special accommodations should contact Angela Quintana at (505) 992-9648 .

Public documents, including the agenda and minutes, can be provided in various accessible formats. If you are an individual with a disability who is in need of a Reader, amplifier, qualified sign language interpreter, or any other form of auxiliary aid or service to attend or participate in the hearing or meeting, or if a summary or other type of accessible format is needed, please contact the NMFA at (505) 984-1454 at least one week prior to the meeting or as soon as possible.

Pitch In!

PUT TRASH IN ITS PLACE

Strategy Board Meeting...

Publish September 2, 2021

The Chaves County Comprehensive Strategy Board will be having a telephone/online conference meeting on Tuesday, September 14, 2021. This meeting will be held at 12:00 pm. The meeting is open to the public. For any additional information on how to attend this meeting, please call 575-624-6596 , Continuum Coordinator. If you are an individual with a disability who is need of a reader, qualified sign language interpreter, or any form of auxiliary aid or service to attend or participate in the hearing of a meeting, please contact the Continuum Coordinator at 575-624-6596 or by email (elly.hollon@chaves.county.nm.gov).

GET YOUR SMOKEY ON

ONLY YOU CAN PREVENT WILDFIRES.

9 out of 10 wildfires are caused by humans.
9 out of 10 wildfires can be prevented.

SMOKEY BEAR.COM

LEGALS

Notice of Sale...

Publish August 26, September 2, 9, 16, 2021

STATE OF NEW MEXICO
COUNTY OF CHAVES
FIFTH JUDICIAL DISTRICT COURT

No. D-504-CV-2020-00680

NEWREZ LLC D/B/A SHELLPOINT MORTGAGE SERVICING,

Plaintiff,

vs.

RICK SANDERS AND MELISSA SANDERS,

Defendants.

NOTICE OF SALE

NOTICE IS HEREBY GIVEN that on September 29, 2021, at the hour of 11:30 AM, the undersigned Special Master, or his designee, will, at the east entrance of the Chaves County Courthouse, at 400 N. Virginia Ave, Roswell, NM 88201, sell all of the rights, title, and interests of the above-named Defendant(s), in and to the hereinafter described real property to the highest bidder for cash. The property to be sold is located at 709 South Pine Avenue, Roswell, New Mexico 88203, and is more particularly described as follows:

LOT FOURTEEN (14) EXCEPT the South 2 feet thereof, in BLOCK FOUR (4) of DAY SUBDIVISION, a subdivision in the City of Roswell, County of Chaves and State of New Mexico, as shown on the Official Plat filed in the Chaves County Clerk's Office on February 5, 1958 and recorded in Book C of Plat Records, Chaves County, New Mexico, at Page 69,

including any improvements, fixtures, and attachments, such as, but not limited to, mobile homes. , (hereinafter the "Property"). If there is a conflict between the legal description and the street address, the legal description shall control.

The foregoing sale will be made to satisfy an in rem foreclosure judgment rendered by this Court in the above-entitled and numbered cause on August 10, 2021, being an action to foreclose a mortgage on the Property. Plaintiff's in rem judgment is in the amount of \$109,948.66, and the same bears interest at the rate of 4.00% per annum, accruing at the rate of \$12.05 per diem. The Court reserves entry of final in rem judgment against Defendant(s), Rick Sanders and Melissa Sanders, for the amount due after foreclosure sale, including interest, costs, and fees as may be assessed by the Court. Plaintiff has the right to bid at the foregoing sale in an amount equal to its in rem judgment, and to submit its bid either verbally or in writing. Plaintiff may apply all or any part of its in rem judgment to the purchase price in lieu of cash.

In accordance with the Court's decree, the proceeds of sale are to be applied first to the costs of sale, including the Special Master's fees, and then to satisfy the above-described in rem judgment, including interest, with any remaining balance to be paid unto the registry of the Court in order to satisfy any future adjudication of priority lienholders.

NOTICE IS FURTHER GIVEN that in the event that the Property is not sooner redeemed, the undersigned Special Master will, as set forth above, offer for sale and sell the Property to the highest bidder for cash or equivalent, for the purpose of satisfying, in the adjudged order of priorities, the in rem judgment and decree of foreclosure described herein, together with any additional costs and attorney's fees, including the costs of advertisement and publication for the foregoing sale, and, reasonable receiver and Special Master's fees in an amount to be fixed by the Court. The amount of the in rem judgment due is \$109,948.66, plus interest to and including date of sale in the amount of \$1,277.30, for a total in rem judgment of \$111,225.96.

The foregoing sale may be postponed and rescheduled at the discretion of the Special Master, and is subject to all taxes, utility liens and other restrictions and easements of record, and subject to a one (1) month right of redemption held by the Defendant(s) upon entry of an order approving sale, an in rem order of the Court approving the terms and conditions of sale.

Witness my hand this 23rd day of August, 2021.

/s/ David Washburn
DAVID WASHBURN, Special Master
8100 Wyoming Blvd NE
Suite M-4, Box 272
Albuquerque, NM 87113
Telephone: (505) 318-0300
E-mail: sales@nsi.legal



KEEP ROSWELL BEAUTIFUL

LEGALS

Second Notice of Sale...

Publish August 12, 19, 26, September 2, 2021

STATE OF NEW MEXICO
COUNTY OF CHAVES
FIFTH JUDICIAL DISTRICT COURT

No. D-504-CV-2019-00357

NATIONSTAR MORTGAGE LLC D/B/A MR. COOPER,

Plaintiff,

vs.

NATHAN D. KENNARD AKA NATHAN DALE KENNARD AND SECRETARY OF HOUSING AND URBAN DEVELOPMENT,

Defendants.

SECOND NOTICE OF SALE

NOTICE IS HEREBY GIVEN that on October 6, 2021, at the hour of 11:30 AM, the undersigned Special Master, or his designee, will, at the east entrance of the Chaves County Courthouse, at 400 N. Virginia Ave, Roswell, NM 88201, sell all of the rights, title, and interests of the above-named Defendant(s), in and to the hereinafter described real property to the highest bidder for cash. The property to be sold is located at 3701 Bandolina Avenue, Roswell, New Mexico 88201, and is more particularly described as follows:

Lot 9, Block 9 of Tierra Berrenda No. 4 Addition, in the City of Roswell, County of CHAVES and State of New Mexico, as shown on the Official Plat recorded May 4, 1960 in Plat Book C, Page 116, Real Property Records of CHAVES County, New Mexico

including any improvements, fixtures, and attachments, such as, but not limited to, mobile homes,(hereinafter the "Property"). If there is a conflict between the legal description and the street address, the legal description shall control.

The foregoing sale will be made to satisfy a foreclosure judgment rendered by this Court in the above-entitled and numbered cause on September 16, 2019, being an action to foreclose a mortgage on the Property. Plaintiff's judgment is in the amount of \$115,417.73, and the same bears interest at the rate of 4.125% per annum, accruing at the rate of \$13.04 per diem. The Court reserves entry of final judgment against Defendant(s), Nathan D. Kennard, for the amount due after foreclosure sale, including interest, costs, and fees as may be assessed by the Court. Plaintiff has the right to bid at the foregoing sale in an amount equal to its judgment, and to submit its bid either verbally or in writing. Plaintiff may apply all or any part of its judgment to the purchase price in lieu of cash.

In accordance with the Court's decree, the proceeds of sale are to be applied first to the costs of sale, including the Special Master's fees, and then to satisfy the above-described judgment, including interest, with any remaining balance to be paid unto the registry of the Court in order to satisfy any future adjudication of priority lienholders.

NOTICE IS FURTHER GIVEN that in the event that the Property is not sooner redeemed, the undersigned Special Master will, as set forth above, offer for sale and sell the Property to the highest bidder for cash or equivalent, for the purpose of satisfying, in the adjudged order of priorities, the judgment and decree of foreclosure described herein, together with any additional costs and attorney's fees, including the costs of advertisement and publication for the foregoing sale, and, reasonable receiver and Special Master's fees in an amount to be fixed by the Court. The amount of the judgment due is \$115,417.73, plus interest to and including date of sale in the amount of \$10,810.16, for a total judgment of \$126,227.89.

The foregoing sale may be postponed and rescheduled at the discretion of the Special Master, and is subject to all taxes, utility liens and other restrictions and easements of record, and subject to a one (1) month right of redemption held by the Defendant(s) upon entry of an order approving sale, an order of the Court approving the terms and conditions of sale.

Witness my hand this 10th day of August, 2021.

/s/ David Washburn
DAVID WASHBURN, Special Master
8100 Wyoming Blvd NE
Suite M-4, Box 272
Albuquerque, NM 87113
Telephone: (505) 318-0300
E-mail: sales@nsi.legal

Recycle This Paper

CLASSIFIEDS INDEX

Announcements

005 Special Notice	110 Blade Work
010 Card of Thanks	115 Bookkeeping
015 Personals/Special	120 Carpentry
020 Transportation	125 Carpet Cleaning
025 Lost & Found	130 Carpeting
Instruction	135 Ceramic Tile
030 Education	140 Cleaning
035 Music – Dance/Drama	145 Clock & Watch Repair
040 Instructions Wanted	150 Concrete
Employment	155 Counseling
045 Employment Opportunities	160 Crafts/Arts
050 Salesperson/Agents	165 Ditching
055 Employment Agencies	170 Drafting
060 Jobs Wanted – M & F	175 Drapery
Services	180 Drilling
070 Agricultural Analysis	185 Electrical
075 Air Conditioning	190 Engraving
080 Alterations	195 Elderly Care
085 Appliance Repair	200 Fencing
090 Auto Repair	205 Fertilizer
100 Babysitting	210 Firewood – Coal
105 Childcare	215 Floor Covering
	220 Furniture Repair
	224 Garage Door Repair

General Construction

225 General Construction	320 Photography
226 Waterwell	325 Piano Tuning
230 General Repair	330 Plumbing
232 Chimney Sweep	335 Printing
235 Hauling	340 Radio/TV's/Stereo's
240 Horseshoeing	345 Remodeling
245 House Wrecking	350 Roofing
250 Insulation	355 Sand Blasting
255 Insurance	356 Satellite
260 Ironing & Washing	360 Screens/Shutters
265 Janitorial	365 Security
269 Excavating	370 Sewer Service & Repair
270 Landscape/Lawnwork	375 Sewing Machine Service
280 Masonry/Concrete	380 Sharpening
285 Miscellaneous Service	385 Slenderizing
290 Mobile Home Service	390 Steam Cleaning
293 Monuments	395 Stucco Plastering
295 Musical	400 Tax Service
300 Oil Field Services	401 Telephone Service
305 Computers	405 Tractor Work
306 Rubber Stamps	410 Tree Service
310 Painting/Decorating	415 Typing Service
315 Pest Control	420 Upholstery
316 Pets	425 Vacuum Cleaners
	426 Video/Recording
	430 Wallpapering

Welding

445 Wrought Iron	435 Welding
450 Services Wanted	445 Wrought Iron
Financial	450 Services Wanted
455 Money: Loan/Borrow	Financial
456 Credit Cards	455 Money: Loan/Borrow
460 Insurance Co.	456 Credit Cards
465 Oil, Mineral, Water, Land - Lease/Sale	460 Insurance Co.
470 Investment: Stocks/Sale	465 Oil, Mineral, Water, Land - Lease/Sale
475 Mortgages for Sale	470 Investment: Stocks/Sale
480 Mortgages Wanted	475 Mortgages for Sale
485 Business Opportunities	480 Mortgages Wanted
Real Estate	485 Business Opportunities
490 Homes for Sale	Real Estate
495 Acreage/Farm/Ranch	490 Homes for Sale
500 Business for Sale	495 Acreage/Farm/Ranch
505 Commercial Business Property	500 Business for Sale
510 Resort Out of Town Property	505 Commercial Business Property
515 Mobile Homes/Sale	510 Resort Out of Town Property
520 Lots for Sale	515 Mobile Homes/Sale
525 Building Transfer	520 Lots for Sale

Real Estate Wanted


535 Apartments, Furnished	530 Real Estate Wanted
540 Apartments, Unfurnished	Rentals
545 Houses, Furnished	535 Apartments, Furnished
550 Houses, Unfurnished	540 Apartments, Unfurnished
555 Mobile Homes – Rental	545 Houses, Furnished
560 Sleeping Rooms	550 Houses, Unfurnished
565 Rest Homes	555 Mobile Homes – Rental
569 Mobile Home	560 Sleeping Rooms
Lots/Space	565 Rest Homes
570 Mobile Home Courts	569 Mobile Home
571 RV Parks	Lots/Space
575 Resort Homes	570 Mobile Home Courts
580 Office/Business Rentals	571 RV Parks
585 Warehouse & Storage	575 Resort Homes
590 Farms/Acreage – Rent	580 Office/Business Rentals
595 Miscellaneous for Rent	585 Warehouse & Storage
600 Want to Rent	590 Farms/Acreage – Rent
Merchandise	595 Miscellaneous for Rent
605 Miscellaneous for Sale	600 Want to Rent
610 Garage Sales, Individuals	Merchandise
611 Garage Sales,	605 Miscellaneous for Sale

Businesses

615 Coins/Gold/Silver	Businesses
620 Want to Buy – Miscellaneous	615 Coins/Gold/Silver
625 Antiques	620 Want to Buy – Miscellaneous
630 Auction Sales	625 Antiques
635 Good Things to Eat	630 Auction Sales
640 Household Goods	635 Good Things to Eat
645 Sewing Machines	640 Household Goods
650 Washers & Dryers	645 Sewing Machines
652 Computers	650 Washers & Dryers
655 TV's & Radios	652 Computers
660 Stereos	655 TV's & Radios
665 Musical Merchandise	660 Stereos
670 Industrial Equipment	665 Musical Merchandise
675 Camera/Photography	670 Industrial Equipment
680 Heating Equipment	675 Camera/Photography
685 Air Conditioning Equipment	680 Heating Equipment
690 Business/Office Equipment	685 Air Conditioning Equipment
695 Machinery	690 Business/Office Equipment
700 Building Materials	695 Machinery
705 Lawn/Garden/Fertilizer	700 Building Materials
710 Plants/Flowers	705 Lawn/Garden/Fertilizer
715 Hay & Feed Sale	710 Plants/Flowers

Livestock & Supplies

721 Boarding Stables	720 Livestock & Supplies
725 Livestock Wanted	721 Boarding Stables
730 Poultry & Supplies	725 Livestock Wanted
735 Poultry Wanted	730 Poultry & Supplies
740 Show Fowl	735 Poultry Wanted
745 Pets for Sale	740 Show Fowl
Recreational	745 Pets for Sale
750 Sports Equipment	Recreational
755 Bicycles for Sale	750 Sports Equipment
760 Hunting & Camping Equipment	755 Bicycles for Sale
765 Guns & Ammunition	760 Hunting & Camping Equipment
770 Boats & Accessories	765 Guns & Ammunition
775 Motorcycles	770 Boats & Accessories
780 RV's/Campers	775 Motorcycles
785 Trailers Wanted	780 RV's/Campers
790 Automobiles for Sale	785 Trailers Wanted
795 Trucks & Vans	790 Automobiles for Sale
796 SUV's	795 Trucks & Vans
800 Classic Automobiles	796 SUV's
805 Imported Automobiles	800 Classic Automobiles
810 Auto Parts & Accessories	805 Imported Automobiles
815 Wanted – Autos	810 Auto Parts & Accessories



IACX Roswell LLC
Bitter Lake Compressor Station
Chavez County, NM

Owners Notified

Project No.
Report No.
Date:

Env-IACX-Bitter Lake CS
NSR-0005
October 2021

Section 10

Written Description of the Routine Operations of the Facility

A written description of the routine operations of the facility. Include a description of how each piece of equipment will be operated, how controls will be used, and the fate of both the products and waste generated. For modifications and/or revisions, explain how the changes will affect the existing process. In a separate paragraph describe the major process bottlenecks that limit production. The purpose of this description is to provide sufficient information about plant operations for the permit writer to determine appropriate emission sources.

Bitter Lake is an extension of a local gas transportation system that gathers casinghead gas from multiple wells in the area. The facility compresses the gas for delivery to a main line. The site operates natural gas-fired engines (Units C-891, C-893, C-894, and C-895) to raise the discharge pressure of the gas in the pipeline to overcome the effect of frictional losses in the pipeline upstream of the station or from pressure losses/changes within the facility in order to maintain the required suction pressure at the next downstream facility. The volume of gas flowing and the amount of subsequent frictional losses in the pipeline are dependent on field conditions and downstream plant conditions causing pressure variations. The glycol dehydrator (Unit BL-GDS-1) has a capacity of 30 MMscf/day and the two associated reboilers operate a 0.75 MMBtu/hr (Units BL-GDR-1a and BL-GDR-2a). Only one of the two reboilers operates under normal operating conditions. The second reboiler may be used either as a backup unit or as a second unit in series to accommodate higher production rates and the resultant increased heat load on the glycol system. The helium recovery unit (Unit HRU) re-injects gas into the pipeline for further separation at another facility further downstream; therefore, there are no emissions associated with the unit. There are three condensate tanks located at the facility (Units TK-1, TK-2, and TK-2a), which contain hydrocarbons and water that drop out of the line prior to compression. There are associated loading emissions with the three condensate and produced water tanks (Unit Load-1 and Load-2). There are also lube oil tanks (Units TK-3 and TK-10) along with used lube oil tanks (Units TK-6 and TK-12). Additional emissions result from facility-wide fugitives (Unit FUG), haul roads (Unit Haul), venting emissions during Startup, Shutdown, and Maintenance (Unit SSM), and Malfunction emissions (Unit M).

Section 11

Source Determination

Source submitting under 20.2.70, 20.2.72, 20.2.73, and 20.2.74 NMAC

Sources applying for a construction permit, PSD permit, or operating permit shall evaluate surrounding and/or associated sources (including those sources directly connected to this source for business reasons) and complete this section. Responses to the following questions shall be consistent with the Air Quality Bureau's permitting guidance, Single Source Determination Guidance, which may be found on the Applications Page in the Permitting Section of the Air Quality Bureau website.

Typically, buildings, structures, installations, or facilities that have the same SIC code, that are under common ownership or control, and that are contiguous or adjacent constitute a single stationary source for 20.2.70, 20.2.72, 20.2.73, and 20.2.74 NMAC applicability purposes. Submission of your analysis of these factors in support of the responses below is optional, unless requested by NMED.

A. Identify the emission sources evaluated in this section (list and describe):

B. Apply the 3 criteria for determining a single source:

SIC Code: Surrounding or associated sources belong to the same 2-digit industrial grouping (2-digit SIC code) as this facility, OR surrounding or associated sources that belong to different 2-digit SIC codes are support facilities for this source.

☐ Yes ☐ No

Common Ownership or Control: Surrounding or associated sources are under common ownership or control as this source.

☐ Yes ☐ No

Contiguous or Adjacent: Surrounding or associated sources are contiguous or adjacent with this source.

☐ Yes ☐ No

C. Make a determination:

X The source, as described in this application, constitutes the entire source for 20.2.70, 20.2.72, 20.2.73, or 20.2.74 NMAC applicability purposes. If in "A" above you evaluated only the source that is the subject of this application, all "YES" boxes should be checked. If in "A" above you evaluated other sources as well, you must check **AT LEAST ONE** of the boxes "NO" to conclude that the source, as described in the application, is the entire source for 20.2.70, 20.2.72, 20.2.73, and 20.2.74 NMAC applicability purposes.

☐ The source, as described in this application, **does not** constitute the entire source for 20.2.70, 20.2.72, 20.2.73, or 20.2.74 NMAC applicability purposes (A permit may be issued for a portion of a source). The entire source consists of the following facilities or emissions sources (list and describe):

Section 12

Section 12.A

PSD Applicability Determination for All Sources

(Submitting under 20.2.72, 20.2.74 NMAC)

A PSD applicability determination for all sources. For sources applying for a significant permit revision, apply the applicable requirements of 20.2.74.AG and 20.2.74.200 NMAC and to determine whether this facility is a major or minor PSD source, and whether this modification is a major or a minor PSD modification. It may be helpful to refer to the procedures for Determining the Net Emissions Change at a Source as specified by Table A-5 (Page A.45) of the EPA New Source Review Workshop Manual to determine if the revision is subject to PSD review.

A. This facility is:

- ☒ a minor PSD source before and after this modification (if so, delete C and D below).
- ☐ a major PSD source before this modification. This modification will make this a PSD minor source.
- ☐ an existing PSD Major Source that has never had a major modification requiring a BACT analysis.
- ☐ an existing PSD Major Source that has had a major modification requiring a BACT analysis
- ☐ a new PSD Major Source after this modification.

B. This facility **is not** one of the listed 20.2.74.501 Table I – PSD Source Categories. The “project” emissions for this modification are **not significant. The total emissions from the facility will be less than 250 tpy.** The “project” emissions listed below **do** only result from changes described in this permit application, thus no emissions from other **modifications** to this facility. Also, specifically discuss whether this project results in “de-bottlenecking”, or other associated emissions resulting in higher emissions. The project emissions (before netting) for this project are as follows [see Table 2 in 20.2.74.502 NMAC for a complete list of significance levels]:

- a. NOx: **79.58** TPY
- b. CO: **76.73** TPY
- c. VOC: **51.05** TPY
- d. SOx: **1.53** TPY
- e. PM: **0.00** TPY
- f. PM10: **4.33** TPY
- g. PM2.5: **4.33** TPY
- h. Fluorides: **0.00** TPY
- i. Lead: **0.00** TPY
- j. Sulfur compounds (listed in Table 2): **0.00** TPY
- k. GHG: **0.00** TPY

Section 13

Determination of State & Federal Air Quality Regulations

This section lists each state and federal air quality regulation that may apply to your facility and/or equipment that are stationary sources of regulated air pollutants.

Not all state and federal air quality regulations are included in this list. Go to the Code of Federal Regulations (CFR) or to the Air Quality Bureau's regulation page to see the full set of air quality regulations.

Required Information for Specific Equipment:

For regulations that apply to specific source types, in the 'Justification' column **provide any information needed to determine if the regulation does or does not apply**. For example, to determine if emissions standards at 40 CFR 60, Subpart IIII apply to your three identical stationary engines, we need to know the construction date as defined in that regulation; the manufacturer date; the date of reconstruction or modification, if any; if they are or are not fire pump engines; if they are or are not emergency engines as defined in that regulation; their site ratings; and the cylinder displacement.

Required Information for Regulations that Apply to the Entire Facility:

See instructions in the 'Justification' column for the information that is needed to determine if an 'Entire Facility' type of regulation applies (e.g. 20.2.70 or 20.2.73 NMAC).

Regulatory Citations for Regulations That Do Not, but Could Apply:

If there is a state or federal air quality regulation that does not apply, but you have a piece of equipment in a source category for which a regulation has been promulgated, you must **provide the low level regulatory citation showing why your piece of equipment is not subject to or exempt from the regulation**. For example if you have a stationary internal combustion engine that is not subject to 40 CFR 63, Subpart ZZZZ because it is an existing 2 stroke lean burn stationary RICE with a site rating of more than 500 brake HP located at a major source of HAP emissions, your citation would be 40 CFR 63.6590(b)(3)(i). **We don't want a discussion of every non-applicable regulation, but if it is possible a regulation could apply, explain why it does not**. For example, if your facility is a power plant, you do not need to include a citation to show that 40 CFR 60, Subpart OOO does not apply to your non-existent rock crusher.

Regulatory Citations for Emission Standards:

For each unit that is subject to an emission standard in a source specific regulation, such as 40 CFR 60, Subpart OOO or 40 CFR 63, Subpart HH, include the low level regulatory citation of that emission standard. Emission standards can be numerical emission limits, work practice standards, or other requirements such as maintenance. **Here are examples:** a glycol dehydrator is subject to the general standards at 63.764C(1)(i) through (iii); an engine is subject to 63.6601, Tables 2a and 2b; a crusher is subject to 60.672(b), Table 3 and all transfer points are subject to 60.672(e)(1)

Federally Enforceable Conditions:

All federal regulations are federally enforceable. All Air Quality Bureau State regulations are federally enforceable except for the following: affirmative defense portions at 20.2.7.6.B, 20.2.7.110(B)(15), 20.2.7.11 through 20.2.7.113, 20.2.7.115, and 20.2.7.116; 20.2.37; 20.2.42; 20.2.43; 20.2.62; 20.2.63; 20.2.86; 20.2.89; and 20.2.90 NMAC. Federally enforceable means that EPA can enforce the regulation as well as the Air Quality Bureau and federally enforceable regulations can count toward determining a facility's potential to emit (PTE) for the Title V, PSD, and nonattainment permit regulations.

INCLUDE ANY OTHER INFORMATION NEEDED TO COMPLETE AN APPLICABILITY DETERMINATION OR THAT IS RELEVANT TO YOUR FACILITY'S NOTICE OF INTENT OR PERMIT.

EPA Applicability Determination Index for 40 CFR 60, 61, 63, etc: <http://cfpub.epa.gov/adi/>

STATE REGU- LATIONS CITATION	Title	Applies? Enter Yes or No	Unit(s) or Facility	JUSTIFICATION:
20.2.1 NMAC	General Provisions	Yes	Facility	The Bitter Lake Compressor Station will comply with the General Provisions.
20.2.3 NMAC	Ambient Air Quality Standards NMAAQs	Yes	Facility	The Bitter Lake Compressor Station will not exceed the maximum allowable concentrations identified in this chapter.
20.2.7 NMAC	Excess Emissions	Yes	Facility	The Bitter Lake Compressor Station has established and implemented a plan to minimize emissions during startup, shutdown and scheduled maintenance.
20.2.33 NMAC	Gas Burning Equipment - Nitrogen Dioxide	No	N/A	This facility does not have new gas burning equipment having a heat input of greater than 1,000,000 million British Thermal Units per year per unit This facility does not have existing gas burning equipment having a heat input of greater than 1,000,000 million British Thermal Units per year per unit
20.2.34 NMAC	Oil Burning Equipment: NO ₂	No	N/A	This facility does not have external combustion equipment.
20.2.35 NMAC	Natural Gas Processing Plant – Sulfur	Yes	Facility	This regulation establishes sulfur emission standards for natural gas processing plants. The proposed facility meets the definition of a new natural gas processing plant under this regulation and is subject to the requirements of this regulation [20.2.35.7 (B) NMAC]. The facility will comply with all requirements under 20.2.35 NMAC as applicable.
20.2.38 NMAC	Hydrocarbon Storage Facility	No	N/A	The Bitter Lake Compressor Station is not a petroleum processing facility; therefore, this section is not applicable.
20.2.39 NMAC	Sulfur Recovery Plant - Sulfur	No	N/A	The Bitter Lake Compressor Station is not a sulfur recover plant; therefore, this section is not applicable.
20.2.61.109 NMAC	Smoke & Visible Emissions	Yes	C-891, C-893, C-894, C-895	The visible emissions from the stationary combustion equipment at the Bitter Lake Compressor Station will not exceed an opacity of 20 percent.
20.2.70 NMAC	Operating Permits	No	N/A	The Facility is not a major source. Therefore, this section is not applicable.
20.2.72 NMAC	Construction Permits	No	N/A	The Bitter Lake Compressor Station has previously been issued a construction permit.
20.2.73 NMAC	NOI & Emissions Inventory Requirements	Yes	Facility	The Bitter Lake Compressor Station has been issued a construction permit and therefore, will submit an emission inventory report annually upon request by the department.
20.2.74 NMAC	Permits – Prevention of Significant Deterioration (PSD)	No	N/A	This regulation establishes requirements for obtaining a prevention of significant deterioration permit. The facility currently does not have the potential to emit greater than 250 tons per year of any criteria pollutant and, therefore, is not subject to this regulation.
20.2.75 NMAC	Construction Permit Fees	Yes	Facility	This is a 20.2.73 NMAC application and it is subject to the filing fee at 20.2.75.10 NMAC.
20.2.77 NMAC	New Source Performance	Yes	C-891, C-893, C-894, C-895	This is a stationary source which is subject to the requirements of 40 CFR Part 60.
20.2.78 NMAC	Emission Standards for HAPS	No	Units not Subject to 40 CFR 61	Facility is not subject to the requirements of 40 CFR part 61; therefore, the Bitter Lake Compressor Station is exempt from this rule.
20.2.79 NMAC	Permits – Nonattainment Areas	No	Facility	This regulation establishes the requirements for obtaining a nonattainment area permit. The facility is not located in a non-attainment area and therefore is not subject to this regulation.

<u>STATE REGU- LATIONS</u> CITATION	Title	Applies? Enter Yes or No	Unit(s) or Facility	JUSTIFICATION:
20.2.80 NMAC	Stack Heights	No	N/A	This regulation establishes requirements for the evaluation of stack heights and other dispersion techniques. This regulation does not apply as all stacks at the facility follow good engineering practice.
20.2.82 NMAC	MACT Standards for source categories of HAPS	Yes	C-891, C-893, C-894, C-895	This regulation applies to all sources emitting hazardous air pollutants, which are subject to the requirements of 40 CFR Part 63.

Example of a Table for Applicable FEDERAL REGULATIONS (Note: This is not an exhaustive list):

<u>FEDERAL REGU- LATIONS</u> CITATION	Title	Applies? Enter Yes or No	Unit(s) or Facility	JUSTIFICATION:
40 CFR 50	NAAQS	Yes	Facility	The Bitter Lake Compressor Station complies with the national primary and secondary ambient air quality standards..
NSPS 40 CFR 60, Subpart A	General Provisions	Yes	Units subject to 40 CFR 60	New stationary sources at the Facility will comply with the standards of performance in 40 CFR 60, Subpart A.
NSPS 40 CFR60.40a, Subpart Da	Subpart Da, Performance Standards for Electric Utility Steam Generating Units	No	N/A	This regulation establishes standards of performance for electric utility steam generating units. This regulation does not apply because the facility does not operate any electric utility steam generating units.
NSPS 40 CFR60.40b Subpart Db	Electric Utility Steam Generating Units	No	N/A	This regulation does not apply because the facility does not operate any electric utility steam generating units.
40 CFR 60.40c, Subpart Dc	Standards of Performance for Small Industrial- Commercial- Institutional Steam Generating Units	No	N/A	The facility does not have any boilers.
NSPS 40 CFR 60, Subpart Ka	Standards of Performance for Storage Vessels for Petroleum Liquids for which Construction, Reconstruction, or Modification Commenced After May 18, 1978, and Prior to July 23, 1984	No	N/A	Except as provided in paragraph (b) of this section, the affected facility to which this subpart applies is each storage vessel with a storage capacity greater than 151,416 liters (40,000 gallons) that is used to store petroleum liquids for which construction is commenced after May 18, 1978 and prior to July 23, 1984. The condensate tanks at this facility were constructed after July 23, 1984, therefore, this subpart does not apply.
NSPS 40 CFR 60, Subpart Kb	Standards of Performance for Volatile Organic Liquid Storage	No	N/A	Except as provided in paragraph (b) of this section, the affected facility to which this subpart applies is each storage vessel with a capacity greater than or equal to 75 cubic meters (m3) that is used to store volatile organic liquids (VOL) for which construction, reconstruction, or modification is commenced after July 23, 1984. The tanks at this facility have a design capacity less than or equal to 1,589.874 m3

<u>FEDERAL REGU- LATIONS CITATION</u>	Title	Applies? Enter Yes or No	Unit(s) or Facility	JUSTIFICATION:
	Vessels (Including Petroleum Liquid Storage Vessels) for Which Construction, Reconstruction, or Modification Commenced After July 23, 1984			used for petroleum or condensate stored, processed, or treated prior to custody transfer. The tanks are not subject.
NSPS 40 CFR 60.330 Subpart GG	Stationary Gas Turbines	No	N/A	The provisions of this subpart are applicable to the following affected facilities: All stationary gas turbines with a heat input at peak load equal to or greater than 10.7 gigajoules (10 million Btu) per hour, based on the lower heating value of the fuel fired. The facility does not contain the affected units. This regulation does not apply.
NSPS 40 CFR 60, Subpart KKK	Leaks of VOC from Onshore Gas Plants	No	N/A	The compressor station is not located at an onshore natural gas processing plant; therefore, this section is not applicable.
NSPS 40 CFR Part 60 Subpart LLL	Standards of Performance for Onshore Natural Gas Processing: SO ₂ Emissions	No	N/A	The facility is a natural gas processing plant, however, there is not sulfur recovery plant, thus this location does not meet the applicability criteria of 40 CFR 60.640.
NSPS 40 CFR Part 60 Subpart OOOO	Standards of Performance for Crude Oil and Natural Gas Production, Transmission, and Distribution for which construction, modification or reconstruction commenced after August 23, 2011 and before September 18, 2015	No	N/A	The Facility does not have equipment that is subject to 40 CFR 60, Subpart OOOO.
NSPS 40 CFR Part 60 Subpart OOOOa	Standards of Performance for Crude Oil and Natural Gas Facilities for which Construction, Modification or Reconstruction Commenced After September 18, 2015	Yes	FUG	Since the modification of the Bitter Lake Compressor Station started after the September 18, 2015 applicability date, the fugitive emission components are subject to NSPS OOOOa (per 60.5365a(j)). The facility will follow all applicable standards.

<u>FEDERAL REGU- LATIONS CITATION</u>	Title	Applies? Enter Yes or No	Unit(s) or Facility	JUSTIFICATION:
NSPS 40 CFR 60 Subpart IIII	Standards of performance for Stationary Compression Ignition Internal Combustion Engines	No	N/A	This facility has stationary spark ignition (SI) internal combustion engines (ICE) which do not meet the criteria listed in the subpart and therefore they are not subject to this regulation.
NSPS 40 CFR Part 60 Subpart JJJJ	Standards of Performance for Stationary Spark Ignition Internal Combustion Engines	No	N/A	This regulation establishes standards of performance for stationary spark ignition internal combustion engines. All engines were manufactured before June 12, 2006 and therefore this standard does not apply.
NSPS 40 CFR 60 Subpart TTTT	Standards of Performance for Greenhouse Gas Emissions for Electric Generating Units	No	N/A	The facility does not operate an affected source under this subpart.
NSPS 40 CFR 60 Subpart UUUU	Emissions Guidelines for Greenhouse Gas Emissions and Compliance Times for Electric Utility Generating Units	No	N/A	The facility does not operate an affected source under this subpart.
NSPS 40 CFR 60, Subparts WWW, XXX, Cc, and Cf	Standards of performance for Municipal Solid Waste (MSW) Landfills	No	N/A	The facility does not operate an affected source under this subpart.
NESHAP 40 CFR 61 Subpart A	General Provisions	No	N/A	NSPS 40 CFR 61 does not apply to the facility because the facility does not emit or have the triggering substances on site and/or the facility is not involved in the triggering activity. The facility is not subject to this regulation. None of the subparts of Part 61 apply to the facility.
NESHAP 40 CFR 61 Subpart E	National Emission Standards for Mercury	No	N/A	The facility does not operate an affected source under this subpart.
NESHAP 40 CFR 61 Subpart V	National Emission Standards for Equipment Leaks (Fugitive Emission Sources)	No	N/A	This regulation establishes national emission standards for equipment leaks (fugitive emission sources). The facility does not have equipment that operates in volatile hazardous air pollutant (VHAP) service [40 CFR Part 61.240]. The regulated activities subject to this regulation do not take place at this facility. The facility is not subject to this regulation.
MACT 40 CFR 63, Subpart A	General Provisions	Yes	C-891, C-893, C-894,	The engines will comply with MACT 40 CFR 63, Subpart A.

<u>FEDERAL REGU- LATIONS CITATION</u>	Title	Applies? Enter Yes or No	Unit(s) or Facility	JUSTIFICATION:
			C-895	
MACT 40 CFR Subpart HH	NESHAP for Glycol Dehydrators	Yes	BL- GDS-1	This subpart applies to owners and operators of emissions points including glycol dehydration units, and storage vessels with the potential for flash emissions. This facility is subject to the requirements of 40 CFR 63 Subpart HH, which includes requirements applicable to area sources with TEG Dehydrators. The site is not a major source of hazardous air pollutants (HAPs) but an area source of HAPs and therefore subject to this subpart. The dehydrator has the potential to emit less than 1 tpy (0.90 megagram per year) of benzene, and it is therefore subject to the operating requirements of §63.764(e)(1)(ii).
MACT 40 CFR 63 Subpart HHH		No	N/A	This subpart applies to owners and operators of natural gas transmission and storage facilities that transport or store natural gas prior to entering the pipeline to a local distribution company or to a final end user (if there is no local distribution company), and that are major sources of hazardous air pollutants (HAP) emissions as defined in §63.1271. This regulation does not apply because this facility is not a natural gas transmission or storage facility as defined in this regulation [40 CFR Part 63.1270(a)].
MACT 40 CFR 63 Subpart DDDDD	National Emission Standards for Hazardous Air Pollutants for Major Industrial, Commercial, and Institutional Boilers & Process Heaters	No	N/A	Facility is not a major source of hazardous air pollutants and hence not subject to this regulation.
MACT 40 CFR 63 Subpart UUUUU	National Emission Standards for Hazardous Air Pollutants Coal & Oil Fire Electric Utility Steam Generating Unit	No	N/A	Facility is does not have a coal and oil fire electric utility steam generating unit.
MACT 40 CFR 63 Subpart ZZZZ	National Emissions Standards for Hazardous Air Pollutants for Stationary Reciprocating Internal Combustion Engines (RICE MACT)	Yes	C-891, C-893, C-894, C-895	The engine(s) meet the requirements of MACT ZZZZ.
40 CFR 68	Chemical Accident Prevention	No	N/A	This regulation defines compliance assurance monitoring. This regulation does not apply to this facility because the units do not have potential pre-control device emissions that are equal to or greater than 100 tons per year.
Title IV – Acid Rain 40 CFR 72	Acid Rain	No	N/A	The facility does not operate an affected source under this subpart.
Title IV – Acid Rain 40 CFR 73	Sulfur Dioxide Allowance Emissions	No	N/A	The facility does not operate an affected source under this subpart.
Title IV-Acid Rain 40 CFR 75	Continuous Emissions Monitoring	No	N/A	This regulation establishes sulfur dioxide allowance emissions for certain types of facilities. This part does not apply because the facility is not the type covered by this regulation [40 CFR Part 73.2].
Title IV – Acid Rain 40 CFR 76	Acid Rain Nitrogen Oxides Emission	No	N/A	Except as provided in paragraphs (b) through (d) of this section, the provisions apply to each coal-fired utility unit that is subject to an Acid Rain emissions limitation or reduction requirement for SO ₂ under Phase I or Phase II pursuant to

<u>FEDERAL REGU- LATIONS</u> CITATION	Title	Applies? Enter Yes or No	Unit(s) or Facility	JUSTIFICATION:
	Reduction Program			sections 404, 405, or 409 of the Act. This regulation does not apply.
Title VI – 40 CFR 82	Protection of Stratospheric Ozone	No	N/A	This regulation establishes an acid rain nitrogen oxides emission reduction program. This regulation applies to each coal-fired utility unit that is subject to an acid rain emissions limitation or reduction requirement for SO ₂ . This part does not apply because the facility does not operate any coal-fired units [40 CFR Part 76.1].

Section 14

Operational Plan to Mitigate Emissions

(Submitting under 20.2.70, 20.2.72, 20.2.74 NMAC)

- ☐ **Title V Sources** (20.2.70 NMAC): By checking this box and certifying this application the permittee certifies that it has developed an Operational Plan to Mitigate Emissions During Startups, Shutdowns, and Emergencies defining the measures to be taken to mitigate source emissions during startups, shutdowns, and emergencies as required by 20.2.70.300.D.5(f) and (g) NMAC. This plan shall be kept on site to be made available to the Department upon request. This plan should not be submitted with this application.
- ☒ **NSR** (20.2.72 NMAC), **PSD** (20.2.74 NMAC) & **Nonattainment** (20.2.79 NMAC) **Sources:** By checking this box and certifying this application the permittee certifies that it has developed an Operational Plan to Mitigate Source Emissions During Malfunction, Startup, or Shutdown defining the measures to be taken to mitigate source emissions during malfunction, startup, or shutdown as required by 20.2.72.203.A.5 NMAC. This plan shall be kept on site to be made available to the Department upon request. This plan should not be submitted with this application.
- ☐ **Title V** (20.2.70 NMAC), **NSR** (20.2.72 NMAC), **PSD** (20.2.74 NMAC) & **Nonattainment** (20.2.79 NMAC) **Sources:** By checking this box and certifying this application the permittee certifies that it has established and implemented a Plan to Minimize Emissions During Routine or Predictable Startup, Shutdown, and Scheduled Maintenance through work practice standards and good air pollution control practices as required by 20.2.7.14.A and B NMAC. This plan shall be kept on site or at the nearest field office to be made available to the Department upon request. This plan should not be submitted with this application.
-

- The Bitter Lake Compressor Station has an NGL Flash Drum planned to ensure offloading of the process streams. In the event that the 3rd party pipeline offloads have issues or outages, and they cannot take the residue gas or NGL, the inlet gas will be appropriately curtailed to ensure that gas is not flared.
- Emission from the condensate tanks and produced water tanks are controlled by the vapor recovery unit (VRU) to reduce VOC emissions.
- The Bitter Lake Compressor Station has modern process and safety systems in place that monitor fire and hazardous gases continuously. The Bitter Lake Compressor Station has fulltime monitors to observe and locate any safety and/or process issues that could result in an incident. This safeguards health and safety of not only the employees working at the facility but the surrounding area and environment.

Section 15

Alternative Operating Scenarios

(Submitting under 20.2.70, 20.2.72, 20.2.74 NMAC)

Alternative Operating Scenarios: Provide all information required by the department to define alternative operating scenarios. This includes process, material and product changes; facility emissions information; air pollution control equipment requirements; any applicable requirements; monitoring, recordkeeping, and reporting requirements; and compliance certification requirements. Please ensure applicable Tables in this application are clearly marked to show alternative operating scenario.

Construction Scenarios: When a permit is modified authorizing new construction to an existing facility, NMED includes a condition to clearly address which permit condition(s) (from the previous permit and the new permit) govern during the interval between the date of issuance of the modification permit and the completion of construction of the modification(s). There are many possible variables that need to be addressed such as: Is simultaneous operation of the old and new units permitted and, if so for example, for how long and under what restraints? In general, these types of requirements will be addressed in Section A100 of the permit, but additional requirements may be added elsewhere. Look in A100 of our NSR and/or TV permit template for sample language dealing with these requirements. Find these permit templates at: https://www.env.nm.gov/aqb/permit/aqb_pol.html. Compliance with standards must be maintained during construction, which should not usually be a problem unless simultaneous operation of old and new equipment is requested.

In this section, under the bolded title “Construction Scenarios”, specify any information necessary to write these conditions, such as: conservative-realistic estimated time for completion of construction of the various units, whether simultaneous operation of old and new units is being requested (and, if so, modeled), whether the old units will be removed or decommissioned, any PSD ramifications, any temporary limits requested during phased construction, whether any increase in emissions is being requested as SSM emissions or will instead be handled as a separate Construction Scenario (with corresponding emission limits and conditions, etc).

There are no alternative operating scenarios at Bitter Lake Compressor Station.

Section 16

Air Dispersion Modeling

- 1) Minor Source Construction (20.2.72 NMAC) and Prevention of Significant Deterioration (PSD) (20.2.74 NMAC) ambient impact analysis (modeling): Provide an ambient impact analysis as required at 20.2.72.203.A(4) and/or 20.2.74.303 NMAC and as outlined in the Air Quality Bureau's Dispersion Modeling Guidelines found on the Planning Section's modeling website. If air dispersion modeling has been waived for one or more pollutants, attach the AQB Modeling Section modeling waiver approval documentation.
- 2) SSM Modeling: Applicants must conduct dispersion modeling for the total short term emissions during routine or predictable startup, shutdown, or maintenance (SSM) using realistic worst case scenarios following guidance from the Air Quality Bureau's dispersion modeling section. Refer to "Guidance for Submittal of Startup, Shutdown, Maintenance Emissions in Permit Applications (http://www.env.nm.gov/aqb/permit/app_form.html) for more detailed instructions on SSM emissions modeling requirements.
- 3) Title V (20.2.70 NMAC) ambient impact analysis: Title V applications must specify the construction permit and/or Title V Permit number(s) for which air quality dispersion modeling was last approved. Facilities that have only a Title V permit, such as landfills and air curtain incinerators, are subject to the same modeling required for preconstruction permits required by 20.2.72 and 20.2.74 NMAC.

What is the purpose of this application?	Enter an X for each purpose that applies
New PSD major source or PSD major modification (20.2.74 NMAC). See #1 above.	
New Minor Source or significant permit revision under 20.2.72 NMAC (20.2.72.219.D NMAC). See #1 above. Note: Neither modeling nor a modeling waiver is required for VOC emissions.	X
Reporting existing pollutants that were not previously reported.	
Reporting existing pollutants where the ambient impact is being addressed for the first time.	
Title V application (new, renewal, significant, or minor modification. 20.2.70 NMAC). See #3 above.	
Relocation (20.2.72.202.B.4 or 72.202.D.3.c NMAC)	
Minor Source Technical Permit Revision 20.2.72.219.B.1.d.vi NMAC for like-kind unit replacements.	
Other: i.e. SSM modeling. See #2 above.	
This application does not require modeling since this is a No Permit Required (NPR) application.	
This application does not require modeling since this is a Notice of Intent (NOI) application (20.2.73 NMAC).	
This application does not require modeling according to 20.2.70.7.E(11), 20.2.72.203.A(4), 20.2.74.303, 20.2.79.109.D NMAC and in accordance with the Air Quality Bureau's Modeling Guidelines.	

Check each box that applies:

- ☐ See attached, approved modeling **waiver for all** pollutants from the facility.
- ☐ See attached, approved modeling **waiver for some** pollutants from the facility.
- X** Attached in Universal Application Form 4 (UA4) is a **modeling report for all** pollutants from the facility.
- ☐ Attached in UA4 is a **modeling report for some** pollutants from the facility.
- ☐ No modeling is required.

Section 17

Compliance Test History

(Submitting under 20.2.70, 20.2.72, 20.2.74 NMAC)

To show compliance with existing NSR permits conditions, you must submit a compliance test history. The table below provides an example.

To save paper and to standardize the application format, delete this sentence and the samples in the Compliance Test History Table, and begin your submittal for this attachment on this page.

Compliance Test History Table (Modify this sample table to suit your facility)

Unit No.	Test Description	Test Date
C-891, C-893	Tested in accordance with EPA test methods for NOx and CO as required by Title V permit P500.	4/13/2004
C-894	Tested in accordance with EPA test methods for NOx and CO as required by NSR permit 2923M1.	5/12/2005
C-891	Tested in accordance with EPA test methods for NOx and CO as required by NSR permit 2923M1.	5/16/2018
C-893	Tested in accordance with EPA test methods for NOx and CO as required by NSR permit 2923M1.	6/22/2018
C-893	Tested in accordance with EPA test methods for NOx and CO as required by NSR permit 2923M1.	9/25/2019
C-891	Tested in accordance with EPA test methods for NOx and CO as required by NSR permit 2923M1.	1/28/2020
C-895	Tested in accordance with EPA test methods for NOx and CO as required by NSR permit 2923M1.	4/6/2021
C-894	Tested in accordance with EPA test methods for NOx and CO as required by NSR permit 2923M1.	4/6/2021
C-891	Tested in accordance with EPA test methods for NOx and CO as required by NSR permit 2923M1.	4/7/2021
C-893	Tested in accordance with EPA test methods for NOx and CO as required by NSR permit 2923M1.	5/3/2021
C-895	Tested in accordance with EPA test methods for NOx and CO as required by NSR permit 2923M1.	9/9/2021
C-894	Tested in accordance with EPA test methods for NOx and CO as required by NSR permit 2923M1.	9/9/2021

Section 20

Other Relevant Information

Other relevant information. Use this attachment to clarify any part in the application that you think needs explaining. Reference the section, table, column, and/or field. Include any additional text, tables, calculations or clarifying information.

Additionally, the applicant may propose specific permit language for AQB consideration. In the case of a revision to an existing permit, the applicant should provide the old language and the new language in track changes format to highlight the proposed changes. If proposing language for a new facility or language for a new unit, submit the proposed operating condition(s), along with the associated monitoring, recordkeeping, and reporting conditions. In either case, please limit the proposed language to the affected portion of the permit.

To save paper and to standardize the application format, delete this sentence, and begin your submittal for this attachment on this page.

Section 22: Certification

Company Name: IACX Roswell

I, Justin Wheeler, hereby certify that the information and data submitted in this application are true and as accurate as possible, to the best of my knowledge and professional expertise and experience.

Signed this 27 day of October, 2021, upon my oath or affirmation, before a notary of the State of Texas.

Justin Wheeler
*Signature

10/27/21
Date

Justin Wheeler
Printed Name

Director of EHS
Title

Scribed and sworn before me on this 27th day of October, 2021.


My authorization as a notary of the State of Texas expires on the

28th day of January, 2024.

[Signature]
Notary's Signature

10-27-2021
Date

Kimberly Elaine Caples
Notary's Printed Name



*For Title V applications, the signature must be of the Responsible Official as defined in 20.2.70.7.AE NMAC.

Universal Application 4

Air Dispersion Modeling Report

Refer to and complete Section 16 of the Universal Application form (UA3) to assist your determination as to whether modeling is required. If, after filling out Section 16, you are still unsure if modeling is required, e-mail the completed Section 16 to the AQB Modeling Manager for assistance in making this determination. If modeling is required, a modeling protocol would be submitted and approved prior to an application submittal. The protocol should be emailed to the modeling manager. A protocol is recommended but optional for minor sources and is required for new PSD sources or PSD major modifications. Fill out and submit this portion of the Universal Application form (UA4), the "Air Dispersion Modeling Report", only if air dispersion modeling is required for this application submittal. This serves as your modeling report submittal and should contain all the information needed to describe the modeling. No other modeling report or modeling protocol should be submitted with this permit application.

16-A: Identification

1	Name of facility:	Bitter Lake Compressor Station
2	Name of company:	IACX Roswell LLC
3	Current Permit number:	
4	Name of applicant's modeler:	James VanAssche
5	Phone number of modeler:	972-842-4304
6	E-mail of modeler:	jva@resolutecompliance.com

16-B: Brief

1	Was a modeling protocol submitted and approved?	Yes☒	No☐
2	Why is the modeling being done? The purpose of this application is to obtain a minor NSR permit.	Other (describe below)	
3	Describe the permit changes relevant to the modeling.		
	The facility is an existing GCP permit and is being updated to a minor NSR permit due to the proximity to a Class I area.		
4	What geodetic datum was used in the modeling?	NAD83	
5	How long will the facility be at this location?	Permanent Facility	
6	Is the facility a major source with respect to Prevention of Significant Deterioration (PSD)?	Yes☐	No☒
7	Identify the Air Quality Control Region (AQCR) in which the facility is located	155	

8	List the PSD baseline dates for this region (minor or major, as appropriate).		
	NO2	3/16/1988	
	SO2	7/28/1978	
	PM10	2/20/1979	
	PM2.5	11/13/2013	
9	Provide the name and distance to Class I areas within 50 km of the facility (300 km for PSD permits).		
	The nearest Class I area is Salt Creek Wilderness located at ~ 1.83 km from the facility.		
10	Is the facility located in a non-attainment area? If so describe below	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
11	Describe any special modeling requirements, such as streamline permit requirements.		
	There are no special modeling requirements.		

16-C: Modeling History of Facility

1	Describe the modeling history of the facility, including the air permit numbers, the pollutants modeled, the National Ambient Air Quality Standards (NAAQS), New Mexico AAQS (NMAAQs), and PSD increments modeled. (Do not include modeling waivers).			
	Pollutant	Latest permit and modification number that modeled the pollutant facility-wide.	Date of Permit	Comments
	CO	N/A	N/A	Existing GCP/New NSR Facility
	NO ₂	N/A	N/A	Existing GCP/New NSR Facility
	SO ₂	N/A	N/A	Existing GCP/New NSR Facility
	H ₂ S	N/A	N/A	Existing GCP/New NSR Facility
	PM2.5	N/A	N/A	Existing GCP/New NSR Facility
	PM10	N/A	N/A	Existing GCP/New NSR Facility
	Lead	N/A	N/A	Facility has no permitted lead emissions
	Ozone (PSD only)	N/A	N/A	Not a PSD Permit
	NM Toxic Air Pollutants (20.2.72.402 NMAC)	N/A	N/A	Facility does not require TAL modeling

16-D: Modeling performed for this application

1	For each pollutant, indicate the modeling performed and submitted with this application. Choose the most complicated modeling applicable for that pollutant, i.e., culpability analysis assumes ROI and cumulative analysis were also performed.					
	Pollutant	ROI	Cumulative analysis	Culpability analysis	Waiver approved	Pollutant not emitted or not changed.
	CO	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	NO ₂	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	SO ₂	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

	H ₂ S	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
	PM _{2.5}	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	PM ₁₀	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
	Lead	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
	Ozone	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
	State air toxic(s) (20.2.72.402 NMAC)	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>

16-E: New Mexico toxic air pollutants modeling

1	List any New Mexico toxic air pollutants (NMTAPs) from Tables A and B in 20.2.72.502 NMAC that are modeled for this application. N/A					
2	List any NMTAPs that are emitted but not modeled because stack height correction factor. Add additional rows to the table below, if required. N/A					
	Pollutant	Emission Rate (pounds/hour)	Emission Rate Screening Level (pounds/hour)	Stack Height (meters)	Correction Factor	Emission Rate/ Correction Factor

16-F: Modeling options

1	Was the latest version of AERMOD used with regulatory default options? If not explain below.	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

16-G: Surrounding source modeling

1	Date of surrounding source retrieval	10/1/2021
2	If the surrounding source inventory provided by the Air Quality Bureau was believed to be inaccurate, describe how the sources modeled differ from the inventory provided. If changes to the surrounding source inventory were made, use the table below to describe them. Add rows as needed.	
	AQB Source ID	Description of Corrections
	14E25	Point was deleted due to it corresponding to site and avoid double counting source. This was deleted for NO ₂ , PM 10, PM 2.5, and SO ₂ .
	14E26	Point was deleted due to it corresponding to site and avoid double counting source. This was deleted for NO ₂ , PM 10, PM 2.5, and SO ₂ .
	14E16	Point was deleted due to it corresponding to site and avoid double counting source. This was deleted for NO ₂ , PM 10, PM 2.5, and SO ₂ .
	14E17	Point was deleted due to it corresponding to site and avoid double counting source. This was deleted for NO ₂ , PM 10, PM 2.5, and SO ₂ .
	14E20	Point was deleted due to it corresponding to site and avoid double counting source. This was deleted for NO ₂ , PM 10, PM 2.5, and SO ₂ .
	14E3	Point was deleted due to it corresponding to site and avoid double counting source. This was deleted for NO ₂ , PM 10, PM 2.5, and SO ₂ .

	14E1	Point was deleted due to it corresponding to site and avoid double counting source. This was deleted for NO2.
	14E2	Point was deleted due to it corresponding to site and avoid double counting source. This was deleted for NO2.
	403E1	Source was located over 50 km from site and was too distant to impact grid area. Point was deleted due to it corresponding to site and avoid double counting source. This was deleted for NO2.
	18E3	Point source was not located in the correct location. The coordinates were changed from 557192.75, 3715875.21 to 557000, 3725000.

16-H: Building and structure downwash

1	How many buildings are present at the facility?	There are 3 buildings
2	How many above ground storage tanks are present at the facility?	There are a number of Tanks/Process Vessels of varied sizes, only those that are within receptors reach where modeled.
3	Was building downwash modeled for all buildings and tanks? If not explain why below.	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
	Tanks are outside of the radius of the sources.	
4	Building comments	

16-I: Receptors and modeled property boundary

1	<p>“Restricted Area” is an area to which public entry is effectively precluded. Effective barriers include continuous fencing, continuous walls, or other continuous barriers approved by the Department, such as rugged physical terrain with a steep grade that would require special equipment to traverse. If a large property is completely enclosed by fencing, a restricted area within the property may be identified with signage only. Public roads cannot be part of a Restricted Area. A Restricted Area is required in order to exclude receptors from the facility property. If the facility does not have a Restricted Area, then receptors shall be placed within the property boundaries of the facility.</p> <p>Describe the fence or other physical barrier at the facility that defines the restricted area.</p> <p>The restricted area is defined by a fence with an entry gate.</p>					
2	Receptors must be placed along publicly accessible roads in the restricted area. Are there public roads passing through the restricted area?				Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
3	Are restricted area boundary coordinates included in the modeling files?				Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
4	Describe the receptor grids and their spacing. The table below may be used, adding rows as needed.					
	Grid Type	Shape	Spacing	Start distance from restricted area or center of facility	End distance from restricted area or center of facility	Comments
	Cartesian	Rectangular	50	0	500	
	Cartesian	Rectangular	100	500	1000	
	Cartesian	Rectangular	500	1000	5000	
	Cartesian	Rectangular	1000	5000	15000	
	Describe receptor spacing along the fence line.					

5	The restricted area is defined by a fence with 50-meter grid spacing.
6	Describe the PSD Class I area receptors. Receptors are spread out throughout the Class 1, Salt Creek Wilderness, area due to proximity to site.

16-J: Sensitive areas

1	Are there schools or hospitals or other sensitive areas near the facility? If so describe below. This information is optional (and purposely undefined) but may help determine issues related to public notice.	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
3	The modeling review process may need to be accelerated if there is a public hearing. Are there likely to be public comments opposing the permit application?	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>

16-K: Modeling Scenarios

N/A

1	Identify, define, and describe all modeling scenarios. Examples of modeling scenarios include using different production rates, times of day, times of year, simultaneous or alternate operation of old and new equipment during transition periods, etc. Alternative operating scenarios should correspond to all parts of the Universal Application and should be fully described in Section 15 of the Universal Application (UA3).											
	Sources are intended to run loads as close to 100 percent.											
2	Which scenario produces the highest concentrations? Why?											
3	Were emission factor sets used to limit emission rates or hours of operation? (This question pertains to the "SEASON", "MONTH", "HROFDY" and related factor sets, not to the factors used for calculating the maximum emission rate.)										Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
4	If so, describe factors for each group of sources. List the sources in each group before the factor table for that group. (Modify or duplicate table as necessary. It's ok to put the table below section 16-K if it makes formatting easier.) Sources:											
5	Hour of Day	Factor	Hour of Day	Factor								
	1		13									
	2		14									
	3		15									
	4		16									
	5		17									
	6		18									
	7		19									
	8		20									

	9		21									
	10		22									
	11		23									
	12		24									
	If hourly, variable emission rates were used that were not described above, describe them below.											
N/A												
6	Were different emission rates used for short-term and annual modeling? If so describe below.										Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>

16-L: NO₂ Modeling

1	Which types of NO ₂ modeling were used? Check all that apply.			
	<input type="checkbox"/>	ARM2		
	<input checked="" type="checkbox"/>	100% NO _x to NO ₂ conversion		
	<input type="checkbox"/>	PVMRM		
	<input type="checkbox"/>	OLM		
	<input type="checkbox"/>	Other:		
2	Describe the NO ₂ modeling.			
	NO ₂ was modeled using 100% NO _x and NO ₂ conversion.			
3	Were default NO ₂ /NO _x ratios (0.5 minimum, 0.9 maximum or equilibrium) used? If not describe and justify the ratios used below.		Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Assumed 100 percent NO _x to NO ₂ conversion.			
4	Describe the design value used for each averaging period modeled.			
	1-hour: 98th percentile as calculated by AERMOD Annual: One Year Annual Average			

16-M: Particulate Matter Modeling

1	Select the pollutants for which plume depletion modeling was used.			
	<input type="checkbox"/>	PM2.5		
	<input type="checkbox"/>	PM10		
	<input checked="" type="checkbox"/>	None		
2	Describe the particle size distributions used. Include the source of information.			
	N/A – No particle size distributions were used.			
3	Does the facility emit at least 40 tons per year of NO _x or at least 40 tons per year of SO ₂ ? Sources that emit at least 40 tons per year of NO _x or at least 40 tons per year of SO ₂ are considered to emit significant amounts of precursors and must account for secondary formation of PM2.5.		Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

4	Was secondary PM modeled for PM2.5?			Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
5	If MERPs were used to account for secondary PM2.5 fill out the information below. If another method was used describe below.				
	NO _x (ton/yr)	SO ₂ (ton/yr)	[PM2.5] _{annual}	[PM2.5] _{24-hour}	
	80.23	1.53	0.005173	0.091516	

16-N: Setback Distances

1	Portable sources or sources that need flexibility in their site configuration requires that setback distances be determined between the emission sources and the restricted area boundary (e.g. fence line) for both the initial location and future locations. Describe the setback distances for the initial location.
	NA
2	Describe the requested, modeled, setback distances for future locations, if this permit is for a portable stationary source. Include a haul road in the relocation modeling.
	NA

16-O: PSD Increment and Source IDs

1	The unit numbers in the Tables 2-A, 2-B, 2-C, 2-E, 2-F, and 2-I should match the ones in the modeling files. Do these match? If not, provide a cross-reference table between unit numbers if they do not match below.				Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Unit Number in UA-2		Unit Number in Modeling Files			
2	The emission rates in the Tables 2-E and 2-F should match the ones in the modeling files. Do these match? If not, explain why below.				Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
3	Have the minor NSR exempt sources or Title V Insignificant Activities" (Table 2-B) sources been modeled?				Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
4	Which units consume increment for which pollutants? All sources were modeled to consume increment for all applicable pollutants.					
	Unit ID	NO ₂	SO ₂	PM10	PM2.5	
	C-891		X	X		
	C-893		X	X		
	C-894	X	X	X		
	C-895	X	X	X		
5	PSD increment description for sources. (for unusual cases, i.e., baseline unit expanded emissions after baseline date).			PSD Increment was modeled by using baseline dates (3/16/1988 for NO ₂ , 7/28/1978 for SO ₂ , 2/20/1979 for PM10, and 11/13/2013 for PM2.5). Once those were established, the pollutants were run for their respective time		

		(Annual, 24-Hour, and/or 3-Hour). Each surrounding source was added to the run that it applied to.
6	Are all the actual installation dates included in Table 2A of the application form, as required? This is necessary to verify the accuracy of PSD increment modeling. If not please explain how increment consumption status is determined for the missing installation dates below.	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>

16-P: Flare Modeling

N/A

1	For each flare or flaring scenario, complete the following			
	Flare ID (and scenario)	Average Molecular Weight	Gross Heat Release (cal/s)	Effective Flare Diameter (m)

16-Q: Volume and Related Sources

N/A

1	Were the dimensions of volume sources different from standard dimensions in the Air Quality Bureau (AQB) Modeling Guidelines? If not please explain how increment consumption status is determined for the missing installation dates below.	Yes <input type="checkbox"/>	No <input type="checkbox"/>
2	Describe the determination of sigma-Y and sigma-Z for fugitive sources.		
3	Describe how the volume sources are related to unit numbers. Or say they are the same.		
4	Describe any open pits.		
5	Describe emission units included in each open pit.		

16-R: Background Concentrations

1	Were NMED provided background concentrations used? Identify the background station used below. If non-NMED provided background concentrations were used describe the data that was used.	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
CO: Del Norte High School (350010023)			

	NO ₂ : Hobbs-Jefferson (350250008)			
	PM _{2.5} : Hobbs-Jefferson (350450019)			
	PM ₁₀ : Hobbs-Jefferson (350250008)			
	SO ₂ : Amarillo (483751025)			
	Other:			
	Comments:			
2	Were background concentrations refined to monthly or hourly values? If so describe below.		Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	The corresponding background concentration was used for each run.			

16-S: Meteorological Data

1	Was NMED provided meteorological data used? If so select the station used. Hobbs 2014-2018 was used.	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
2	If NMED provided meteorological data was not used describe the data set(s) used below. Discuss how missing data were handled, how stability class was determined, and how the data were processed.		

16-T: Terrain

1	Was complex terrain used in the modeling? If not, describe why below.	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
2	What was the source of the terrain data?		
	NED 1/3 (USA ~10)		

16-U: Modeling Files

1	Describe the modeling files: Modeling was conducted for all applicable sources and their respective time.		
	File name (or folder and file name)	Pollutant(s)	Purpose (ROI/SIA, cumulative, culpability analysis, other)
	CO 1hr	CO	Cumulative NAAQS
	NO ₂ 24Hr	NO ₂	Cumulative NMAAQs
	NO ₂ Annual	NO ₂	Cumulative NMAAQs and NAAQS
	PM ₂₅	PM _{2.5}	Cumulative NAAQS
	PM ₁₀	PM ₁₀	Cumulative NAAQS
	SO ₂ 24 Hr	SO ₂	Cumulative NMAAQs and NAAQS
	SO ₂ Annual	SO ₂	Cumulative NMAAQs and NAAQS
	NO ₂ Annual INC	NO ₂	Increment

	PM10 INC	PM10	Increment
	PM25 INC	PM2.5	Increment
	SO2 24 HR INC	SO2	Increment
	SO2 Annual INCR	SO2	Increment

16-V: PSD New or Major Modification Applications		N/A	
1	A new PSD major source or a major modification to an existing PSD major source requires additional analysis. Was preconstruction monitoring done (see 20.2.74.306 NMAC and PSD Preapplication Guidance on the AQB website)?	Yes <input type="checkbox"/>	No <input type="checkbox"/>
2	If not, did AQB approve an exemption from preconstruction monitoring?	Yes <input type="checkbox"/>	No <input type="checkbox"/>
3	Describe how preconstruction monitoring has been addressed or attach the approved preconstruction monitoring or monitoring exemption.		
4	Describe the additional impacts analysis required at 20.2.74.304 NMAC.		
5	If required, have ozone and secondary PM2.5 ambient impacts analyses been completed? If so describe below.	Yes <input type="checkbox"/>	No <input type="checkbox"/>

16-W: Modeling Results

1	If ambient standards are exceeded because of surrounding sources, a culpability analysis is required for the source to show that the contribution from this source is less than the significance levels for the specific pollutant. Was culpability analysis performed? If so describe below.							Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>	
2	Identify the maximum concentrations from the modeling analysis. Rows may be modified, added and removed from the table below as necessary.									
Pollutant, Time Period and Standard	Modeled Facility Concentration (µg/m3)	Modeled Concentration with Surrounding Sources (µg/m3)	Secondary PM (µg/m3)	Background Concentration (µg/m3)	Cumulative Concentration (µg/m3)	Value of Standard (µg/m3)	Percent of Standard	Location		
								UTM E (m)	UTM N (m)	Elevation (ft)
CO, NAAQS, 8 – Hour	16.36301	NA	NA	1524	1540.36301	10303.6	14.949	556592.45	3712795.66	1082.52
CO, NAAQS, 1 – Hour	31.67561	NA	NA	2203	2234.67561	40069.6	5.576	556584.19	3712809.50	1082.68
NO2, NMAAQS, Annual	2.43205	NA	NA	8.1	10.53205	94.02	11.201	556547.47	3712816.58	1082.5
NO2, NMAAQS, 24 – Hour	8.63377	NA	NA	NA	8.63377	188.03	4.591	556584.19	3712809.50	1082.5
NO2, NAAQS, 1 – Hour	25.42112	NA	NA	64.2	89.62112	188.03	47.663	556584.19	3712809.50	1082.5
PM2.5, NAAQS, Annual	2.43205	NA	NA	5.9	8.33205	12	69.433	556547.47	3712816.58	1082.5
PM2.5, NAAQS, 24 – Hour	6.35683	NA	NA	13.4	19.75683	35	18.162	556547.47	3712816.58	1082.5
PM10, Annual	2.43205	NA	NA	24.0	26.43205	NA	NA	556547.47	3712816.58	1082.5

Pollutant, Time Period and Standard	Modeled Facility Concentration (µg/m3)	Modeled Concentration with Surrounding Sources (µg/m3)	Secondary PM (µg/m3)	Background Concentration (µg/m3)	Cumulative Concentration (µg/m3)	Value of Standard (µg/m3)	Percent of Standard	Location		
								UTME (m)	UTM N (m)	Elevation (ft)
PM10, NAAQS, 24 – Hour	6.35683	NA	NA	37.3	43.65683	150	29.104	556547.4 7	371281 6.58	1082.5
SO2, NMAAQs, Annual	2.43205	NA	NA	0.670	3.10205	52.4	5.919	556547.4 7	371281 6.58	1082.5
SO2, NMAAQs, 24 – Hour	8.63377	NA	NA	NA	8.63377	261.9	3.296	556484.1 9	371270 9.50	1082.5
SO2, NAAQS, 3 – Hour	24.47196	NA	NA	NA	24.47196	1309.3	1.869	556494.1 0	371273 8.35	1082.5
SO2, NAAQS, 1 – Hour	28.69366	NA	NA	47.0	75.69366	196.4	38.540	556584.1 9	371280 9.50	1082.5
NO2, Class II PSD Increment, Annual	2.386	3.25543	NA	NA	5.64143	25	22.565	546484.1 9	370580 9.50	1096.61
NO2, Class I PSD Increment, Annual	0	0.41	NA	NA	0.41	2.5	1.639	550484.1 9	371680 9.50	1086.55
PM10, Class II PSD Increment, Annual	2.43205	2.43515	NA	NA	4.8672	17	28.630	556547.4 7	371281 6.58	1082.5
PM10, Class I PSD Increment, Annual	0.02	0.02	NA	NA	0.04	4	1	556484.1 9	371480 9.50	1088.49

Pollutant, Time Period and Standard	Modeled Facility Concentration (µg/m3)	Modeled Concentration with Surrounding Sources (µg/m3)	Secondary PM (µg/m3)	Background Concentration (µg/m3)	Cumulative Concentration (µg/m3)	Value of Standard (µg/m3)	Percent of Standard	Location		
								UTM E (m)	UTM N (m)	Elevation (ft)
PM10, Class II PSD Increment, 24 – Hour	6.35683	6.36467	NA	NA	12.7215	30	42.405	556547.4 7	371281 6.58	1082.5
PM10, Class I PSD Increment, 24 – Hour	0.1	0.1	NA	NA	0.2	8	2.5	556484.1 9	371480 9.50	1088.49
SO2, Class II PSD Increment, Annual	2.43205	2.48095	NA	NA	4.913	20	24.565	556547.4 7	371281 6.58	1082.5
SO2, Class I PSD Increment, Annual	0.02	0.07	NA	NA	0.09	2	4.5	550484.1 9	371680 9.50	1086.55
SO2, Class II PSD Increment, 24 – Hour	8.63377	17.42467	NA	NA	26.05844	91	28.635	546484.1 9	370580 9.50	1096.61
SO2, Class I PSD Increment, 24 – Hour	0.17	0.72	NA	NA	0.89	5	17.8	552984.1 9	371480 9.50	1083.4
SO2, Class II PSD Increment, 3 – Hour	24.47196	88.99105	NA	NA	113.46301	512	22.160	546484.1 9	370580 9.50	1096.61

Pollutant, Time Period and Standard	Modeled Facility Concentration (µg/m3)	Modeled Concentration with Surrounding Sources (µg/m3)	Secondary PM (µg/m3)	Background Concentration (µg/m3)	Cumulative Concentration (µg/m3)	Value of Standard (µg/m3)	Percent of Standard	Location		
								UTM E (m)	UTM N (m)	Elevation (ft)
SO2, Class I PSD Increment, 3 – Hour	0.96	4.55	NA	NA	5.5	25	22.00	552984.1 9	371480 9.50	1083.4
PM2.5, Secondary Formation, Annual	0	0	0.005173	NA	0.005173	4	0.12	555484.1 9	370480 9.50	1065
PM2.5, Secondary Formation, 24 – Hour	0	0.01	0.091516	NA	0.101516	9	1.12	555484.1 9	370480 9.50	1065

16-X: Summary/conclusions

1	A statement that modeling requirements have been satisfied and that the permit can be issued.
	This air quality modeling analysis implemented the advanced air dispersion mechanics of the AERMOD dispersion model. The use of AERMOD allowed for the use of the most recent meteorology, modern characterization of the PBL, and consideration of the complex terrain ground receptors surrounding the plant. The emissions from the site were shown to be in compliance with all of the NAAQS and increments.